



"Freedom from Danger"

Sprinkler Impairment

1.0 Purpose

1.1. The purpose of this procedure is to provide a system that minimizes the risks associated with sprinkler system impairment. Unplanned sprinkler impairment as a result of broken heads, dislodged pipes, out-ofservice systems during major demolition and/or construction, or an emergency impairment resulting from a broken supply line or service outage may pose a risk of flooding and/or the spread of fire. In the event of flooding, mold may then become a hazard which must be cleaned, and the source of moisture eliminated.

2.0 Scope

2.1. This procedure applies to all sprinkler impairments -whether planned (for replacement, repair, or maintenance work), or unplanned. See <u>Utility Avoidance Policy</u> for more information.

3.0 Responsibility

3.1 Project Management

3.1.1. BNB Project Management & Supervision are responsible for:

- 3.1.1.1. Issuing, signing, logging, posting, tracking, and closing out all sprinkler impairments.
- 3.1.1.2. Tracking all current and outstanding impairments and ensuring that subcontractors receive appropriate notice if impairment is not properly closed out by the planned restoration date and that reinstatement must occur as soon as possible.
- 3.1.1.3. Ensuring that sprinkler sections and valves are clearly marked and labeled so that specific sections can be found easily in the event of an emergency.
- 3.1.1.4. Ensuring all sprinkler valves are in working order.
- 3.1.1.5. Identifying Halon fire suppression systems and working with the property owner to establish protective measures.

3.2 Workers

3.2.1. Workers responsible for the fire sprinkler impairment shall request permission from BNB prior to the impairment of the fire sprinkler system. After restoring the impaired fire sprinkler system, the responsible workers shall notify BNB.

4.0 Definitions

- 4.1. Foam Fire Suppression System typically used in areas exposed to severe fire hazards and helps to contain the fire more effectively than water. It can be used with either a wet or dry system, and in certain cases, water may be mixed with the foam to better fight the fire or increase pressure in the pipes.
- 4.2. Dry Chemical Fire (Gaseous) Suppression System typically used in areas where water damage is a primary concern, such as museums or computer rooms. These systems use traditional sprinkler pipes and heads but rely on carbon-based chemicals such as halon to suppress the fire. Halon works by absorbing the oxygen in the room, which keeps the fire from spreading.
- 4.3. **Impairment** a condition resulting from an event that causes all or part of a fire sprinkler system to be out of service.
- 4.4. Emergency Impairment Unplanned sprinkler impairment resulting from a broken sprinkler line or head, or a break or outage of the sprinkler supply water service.

Health, Safety and Environmental Manual

"Freedom from Danger"

- 4.5. Planned Impairment Planned sprinkler impairment for maintenance, alteration, or construction activities.
- 4.6. **Designated Ownership Contact** Person designated by the owner to contact for all activities relating to the fire sprinkler impairment. (Building Owner/Property Manager/Building Engineer)

5.0 Procedure

5.1 Planned Impairments

5.1.1. When applicable, the following are guidelines for when sprinkler impairment is planned:

- 5.1.1.1. Notify local fire department
- 5.1.1.2. Provide additional firefighting equipment
- 5.1.1.3. Ensure adequate control of sprinkler system and labeling/tagging of affected valves
- 5.1.1.4. Ensure adequate training/job planning
- 5.1.1.5. Plan to do the work when the facility is not operating, and/or shutdown hazardous processes, if possible.
- 5.1.1.6. Follow applicable lock-out tag-out procedures when applicable.
- 5.1.1.7. Cap all sprinkler heads or otherwise provide appropriate protection in work areas prior to contractor commencing work.
- 5.1.1.8. Prohibit all Hot Work during fire sprinkler impairment:
 - 5.1.1.8.1. There may be instances where elements of the system are isolated specifically for hot work activities. In such cases, fire watch procedures and any other appropriate precautions as per the pre-task plan (PTP) must be implemented.
 - 5.1.1.8.2. Make ready fire hoses / fire extinguishers (confirm that fire extinguishers and/or fire hoses are on hand and in working order at every entrance and exit point of the affected work area)
 - 5.1.1.8.3. Confirm a fire watch is in place and appropriate notifications have been made.
- 5.1.1.9. The fire watch must be trained in the use of fire extinguishing equipment and be familiar with the Project Specific Fire Prevention Plan.
- 5.1.1.10. Any proposed modifications to the building sprinkler system (via submittal of engineering and/or shop drawings) must be approved and permitted by the PTP. NOTE: In some instances, drawings may also require certification from an engineer.
- 5.1.1.11. Standard Impairment Controls
 - 5.1.1.11.1. Whenever a sprinkler system is to be impaired, the applicable subcontractor/vendor must request permission from BNB Project Management & Supervision.
 - 5.1.1.11.2. BNB Project Management & Supervision is to notify:
 - 5.1.1.11.2.1. the local Fire Department, the alarm monitoring service, and security for all impairments.
 - 5.1.1.11.2.2. the Designated Ownership Contact of any sprinkler impairment.
 - 5.1.1.11.2.3. any tenants affected by the sprinkler impairment if building is occupied.

5.2 Un-Planned Impairments

- 5.2.1. When applicable, the following are guidelines for when sprinkler impairment is not planned (emergency impairment):
 - 5.2.1.1. If an emergency impairment occurs, stabilize the situation and initiate impairment precautions with BNB Project Management & Supervision.
 - 5.2.1.2. Correct/repair the cause of the impairment.

Health, Safety and Environmental Manual

"Freedom from Danger"

5.2.1.3. Ensure fire watch is in place.

5.2.2. BNB Project Management & Supervision is to:

- 5.2.2.1. notify the Safety Manager and Designated Ownership Contact. Details are to include the time of impairment, apparent cause of the impairment, expected duration of the impairment, and extent of the impairment to building systems.
- 5.2.2.2. see that an Incident Report Form is completed by the appropriate parties and distributed within 24 hours of the incident.
- 5.2.2.3. notify the Divisional Safety Manager and Designated Ownership Contact when the impairment is cleared.

5.3 Hazards

5.3.1. In the event of a sprinkler system impairment that uses water, the following are potential hazards:

- 5.3.1.1. Flooding
- 5.3.1.2. Water Intrusion (See Environmental Policy)
- 5.3.1.3. Mold
- 5.3.1.4. Electrical Shock
- 5.3.1.5. Property Damage
- 5.3.1.6. Illness from contact with stagnant water inside fire lines
- 5.3.1.7. In the event of a Halon sprinkler system impairment, a potential hazard is Asphyxiation.

5.4 Hazard Controls

5.4.1 Engineering Controls

5.4.1.1. Cap, cover, flag, or otherwise protect sprinklers that have the potential to be damaged

5.4.2 Administrative Controls

5.4.2.1. In facilities where sprinklers are energized and must not be damaged (see <u>Pressurized Lines</u> Policy):

- 5.4.2.1.1. Personnel must be trained on avoiding contact with sprinklers and lines
- 5.4.2.1.2. Signage and / or caution tape may be posted to warn personnel about the location(s) of sprinkler(s)
- 5.4.2.1.3. Stop blocks or other barricades may be used to prevent personnel/equipment travel into areas where sprinklers may be contacted
- 5.4.2.1.4. Make available sprinkler damage kits
- 5.4.2.1.5. Inform crews of sprinkler system shut-off method

5.5 Training

5.5.1. Personnel who work near sprinkler heads should be trained on:

- 5.5.1.1. The hazards of sprinkler impairment during New Hire Orientation
- 5.5.1.2. Notification, shut-off and response procedures for emergency impairment

6.0 References

NFPA 15-17

FEDOSHA 29 CFR 1910.159 - Automatic Sprinkler Systems

7.0 Attachments

Hot Work Permit

Demolition Permit

Pre-Task Plan

Aerial Work Platform Inspection Checklist



"Freedom from Danger"

Steel Erection

1.0 Purpose

1.1. Steel erection is a potentially high-risk task, so it is imperative that proper control measures are utilized to prevent incidents during steel erection. Certain control measures may eliminate hazards, but the process of risk elimination must be started in advance of the work taking place. This standard outlines the hazards and controls associated with steel erection.

2.0 Scope

2.1. Any BNBuilders project that will erect steel must use this standard as a guideline for ensuring proper control measures are in place to eliminate risk. Steel erection activities include hoisting, connecting, welding, bolting, and rigging structural steel, steel joists and metal buildings; installing metal deck, siding systems, miscellaneous metals, ornamental iron and similar materials; and moving from point-to-point to perform these activities.

3.0 Responsibility

3.1 Designers/Architects/Engineers

3.1.1. Designers/Architects/Engineers have the responsibility to eliminate risk through design of the structure and/or process by using methods such as off-site fabrication and assembly.

3.2 Project Management

- 3.2.1. BNB Project Management and Supervision has the duty to ensure that controls have been enacted as early and effectively as possible to eliminate risk. They must communicate with the steel erection subcontractor well in advance of the subcontractor's mobilization on site.
- 3.2.2. BNB Project Management and Supervision must ensure that steel erection subcontractors are provided with a written notification to proceed (see attachment).
- 3.2.3. BNB Project Management and Supervision must ensure adequate access roads into and through the site for the safe delivery and movement of derricks, cranes, trucks, other necessary equipment, and the material to be erected.
- 3.2.4. BNB Project Management and Supervision must ensure a firm, properly graded, drained area, adequately compacted to support the intended loads, readily accessible to the work with adequate space for the safe storage of materials and the safe operation of the erector's equipment.

3.3 Subcontractors

3.1.1. Subcontractors are responsible for attending the preconstruction meeting.

3.4 Workers

3.4.1. Workers engaged in steel erection are responsible for working in a safe manner and following safety requirements.

4.0 Definitions

4.1. **Competent Person** - One who can identify existing or predictable hazards in surroundings or working conditions which are dangerous to employees who is authorized by the nature of their position to take prompt corrective action. This person must have knowledge of the requirements for steel erection.



"Freedom from Danger"

4.2. **Multiple Lift Rigging** - A rigging assembly manufactured by wire rope rigging suppliers that facilitates the attachment of up to 5 independent loads to the hoist rigging of crane.

5.0 Procedure

5.1 Hazards

5.1.1. Hazards associated with steel erection have potentially lethal repercussions if not properly controlled. Hazards may consist of inclement weather, falls, struck-byes, unstable loads, unsafe rigging practices, structural collapse, crane tip overs, fire, flash burn, electrical shock, property damage, injury, and more.

5.2 Engineering Controls

5.2.1. Fall Prevention:

5.2.1.1. Reduce the number of people who need to work at height, e.g. through off site manufacture or prefabrication. Give priority to collective measures over individual measures, e.g. fixed edge protection is preferable to every worker wearing fall prevention equipment. Consider the addition of nets/outrigger platforms to cover shafts/openings below the work. Other fall exposures could be controlled by using aerial work platforms to access the work area. Another engineering control is to install steel posts either inside of curbs or attached to the outside of the curb. This practice will enable decking contractors to utilize the guardrail cables for fall protection at the openings—see photos below.

5.2.2. Struck by Prevention:

5.2.2.1. Control falling objects by installing netting or other overhead protection. Barricade the area within swing radius of crane counterweights to prevent access by personnel.

5.3 Administrative Controls

- 5.3.1. An administrative control to reduce the consequences of dropped items would be to establish controlled access zones around the area underneath of steel erection activities. Signage and barricades could be used to delineate the area and prevent unauthorized access. Workers should tether equipment such as hand/power tools, hard hats, ladders, tape measurers, etc. when possible and the amount of materials stored at heights should be kept to a minimum.
- 5.3.2. In the event of inclement weather such as high wind or lighting storms, operations may need to be suspended.

5.4 Personal Protective Equipment (PPE)

5.4.1. In addition to the required minimum PPE, additional PPE for steel erection activities may include leathers, ear plugs, face shields, personal fall protection, etc.

5.5 Training

- 5.5.1. Personnel must be trained according to the tasks they're engaging in. Typically, most steel erection personnel will need at least one of the following trainings/certifications:
 - 5.5.1.1. Certified crane operator
 - 5.5.1.2. Certified rigger
 - 5.5.1.3. Certified signal person
 - 5.5.1.4. Aerial work platform training
 - 5.5.1.5. Welding certification as applicable
 - 5.5.1.6. Connector training



"Freedom from Danger"

5.5.2. Steel erection training requirements:

- 5.5.2.1. Multiple lift rigging procedures
- 5.5.2.2. Connector procedures
- 5.5.2.3. Controlled decking zone procedures
- 5.5.2.4. Ladder selection and use

5.5.3. Fall Hazard Training:

- 5.5.3.1. Recognition and identification of fall hazards in the work area
- 5.5.3.2. The use and operation of guardrail systems (including perimeter safety cable systems), personal fall arrest systems, positioning device systems, fall restraint systems, safety net systems, and other protection to be used
- 5.5.3.3. The correct procedures for erecting, maintaining, disassembling, and inspecting the fall protection systems to be used
- 5.5.3.4. The procedures to be followed to prevent falls to lower levels and through or into holes and openings in walking/working surfaces and walls; and the fall protection requirements for structural steel erection
- 5.5.3.5. Procedures for erecting, maintaining, disassembling, and inspecting the fall protection systems to be used
- 5.5.3.6. Site-specific fall prevention plan

6.0 References

FED / OSHA 1926 Subpart R - Steel Erection

7.0 Attachments

Crane Pick Plan



"Freedom from Danger"

Utility Avoidance

1.0 Purpose

1.1. The purpose of this policy is to ensure any work in close proximity to utilities is carried out in a manner that supports our goal of Freedom from Danger.

2.0 Scope

2.1. Any scope of work that involves the penetration of the ground or a structure whether by hand or machine or is located in proximity to overhead utilities must be executed in accordance with this standard. Activities covered by this standard range from saw cutting, jackhammering, coring, trenching, excavating, demolition, boring, drilling, grading, mass excavation, etc.

3.0 Responsibility

3.1 Project Management & Supervision

3.1.1. BNB Project Management & Supervision are responsible for:

- 3.1.1.1. ensuring compliance with this standard;
- 3.1.1.2. acquiring safety submittals from subcontractors;
- 3.1.1.3. setting up and hosting pre-dig meetings;
- 3.1.1.4. ensuring completion and filing of "Dig Permits" and "Overhead Utility Permits"


3.2 Subcontractors

3.2.1. Subcontractors are responsible for following the requirements of this program, submitting required submittals to the BNB Project Team, attending pre-dig meetings, and completing "Dig Permits" and "Utility Avoidance Checklist".

4.0 Definitions

- 4.1. **Proximity** nearness in place
- 4.2. Strike Unwanted contact with an energized utility
- 4.3. Overhead Utility Typical overhead utilities are power lines such as those running along sidewalks
- 4.4. **Underground Utility** Typical underground utilities are gas, water, sewer, storm drain, and communications
- 4.5. **Potholing** The act of digging with only hand tools or vacuum/water extraction methods
- 4.6. **Proximity Warning Device** A piece of equipment that assists operators who may become distracted or unable to see the dangerous overhead high voltage power lines in their work area

"Freedom from Danger"



Health, Safety and Environmental Manual

"Freedom from Danger"

5.0 Procedure

5.1 Underground Utilities Procedures

5.1.1. Required Submittals for Subcontractors

- 5.1.1.1. For activities involving the penetration of the ground's surface, the Subcontractor shall submit the following in addition to typically required safety documents prior to starting work:
 - 5.1.1.1.1 the name(s) of the designated "Competent Person" with supporting documentation indicating training and competency. (No excavating or work in excavations will be allowed without the Competent Person onsite and supervising these operations at all times)
 - 5.1.1.1.2. A Job Hazard Analysis that adequately addresses the task(s) involving penetration of the ground's surface and safe measures for preventing utility strikes.

5.2 New Utility Procedures

- 5.2.1. All new underground electrical utilities will be encased in concrete that is dyed red. CDF will not be used for duct banks
- 5.2.2. Duct banks will be installed a minimum of 4' below finish grade when possible.
- 5.2.3. When duct banks are installed less than 4' deep the entire trench will be filled with concrete up to rough grade if possible.
- 5.2.4. Warning signs will be posted at source of electrical and at feed location (i.e. sign at panel and tower crane).
- 5.2.5. Duct bank locations will be marked with red paint with regularly scheduled re-marking to ensure lines are identified at all times.
- 5.2.6. On sites where ground conditions (mud) obscure locate paint/markings stakes or delineators will be installed every 20' to identify utilities route.
- 5.2.7. Newly installed underground utilities will be incorporated into existing Live Utility Map.

5.2.8. Location of all underground utilities will be reviewed at:

- 5.2.8.1. Preparatory meetings with subcontractors.
- 5.2.8.2. New Hire Orientations.
- 5.2.8.3. Weekly safety meetings.

5.2.9. When working within 10' of newly installed utilities the following steps must be taken:

- 5.2.9.1. Contractor performing work must call for locates prior to work and coordinate with BNB to ensure new utilities are identified prior to dig.
- 5.2.9.2. Radar Imagine affected area as needed.
- 5.2.9.3. MOP must be submitted 1 week prior to scheduled work.
- 5.2.9.4. JHA must be submitted 1 week prior to scheduled work.
- 5.2.9.5. Dig Permit must be completed.
- 5.2.9.6. Core Drilling / Saw Cutting Checklist.
- 5.2.10. MOP, JHA, Utilities Permit, must be reviewed day of work with BNB Staff, all workers involved in planned utilities.



"Freedom from Danger"

5.3 Live Utility Map Requirements

- 5.3.1. Live Utilities Awareness Map shall be generated at start of all projects.
- 5.3.2. Applicable utility phone numbers must be included on Live Utilities Map.
- 5.3.3. Map colors must match AWPA color codes as outlined below.
- 5.3.4. Valve locations must be indicated on map.
- 5.3.5. Dimensions/depth shall be outlined on map as necessary
- 5.3.6. Newly installed utilities shall be incorporated into map.
- 5.3.7. Maps shall be dated to ensure most recent version is posted.
- 5.3.8. Map shall be incorporated into sub preparatory meetings, jobsite orientations and be posted in job shack, jobsite office and on safety board.

5.4 Strike Prevention Procedures

- 5.4.1. Every effort must be made to **remove or de-energize utilities as the first** order of business.
- 5.4.2. If a utility is properly identified, shut down, and "safed-off" via lock out tag out, and the utility is struck during an activity, BNB does **not** consider the event a utility strike, but it **would be considered property damage** and must be repaired by the party responsible for the damage.
- 5.4.3. Note, lock out tag out must be performed by a qualified person and testing must verify a zero-energy state for the utility.
- 5.4.4. When within three (3) feet or 36 inches in any direction of known utilities that are energized, hand digging, or vacuum excavation is required.

5.5 Potholing Procedures

- **5.5.1.** Potholing is performed to verify the location and depth of utility lines and potholing procedures shall be followed to prevent damage to the identified underground utilities. Before ground-penetrating activities begin, potholing for the utilities will take place. Potholing will be done using hand labor or a vacuum excavation system. NOTE: Utilities typically identified by locate services have a three-foot safe zone. In other words, the utility should be within a ten-foot zone of either side of the markings.
- 5.5.2. Potholing will be performed to locate the utility. The utility MUST be found prior to the start of excavation operations. The soil must be excavated in 6" lifts (approximately) by hand to verify that no utilities are present. If utilities are located, then the utilities must be exposed by hand. The proper tools that can be used for handwork are shovels and pry bars (or other tools of this nature), OR vacuum excavation systems. At no time should a pickaxe or other similar tools be used. Before using a vacuum excavation system, contact the utility owner to determine if the utility owner will allow the use of a vacuum system. Not all utility owners allow the use of vacuum systems for locating the utility.
- 5.5.3. Do not assume that the utility will continue on the same line and grade. If any damage occurs to any line, contact the utility company, the utility engineer and the project superintendent IMMEDIATELY. An Incident Report must be completed IMMEDIATELY by the BNB Project Team. All existing utilities will be located, marked and visually verified prior to starting any operation. Locate markings must be protected as applicable. It is recommended that time-stamped photos be taken of markings prior to breaking ground.
- **5.5.4.** Underground Utility Pothole Spacing and Frequency Any deviation from this procedure will require approval from the BNB Project Manager. The following spacing and frequency requirements will be followed on all projects:
- **5.5.5.** Life threatening utilities such as gas, forced sewer mains, water mains and electrical services will be exposed through the entire length of the excavation.
- **5.5.6.** Gas and electric lines within 25 feet of your work area will be potholed and marked every 25 feet to verify that the line has not changed directions.



"Freedom from Danger"

- **5.5.7.** Gas and electric lines outside the 25 feet of the work zone will be potholed at least once on each end of the limits of the excavation to verify Underground Service Alert and the utility plans.
- 5.5.8. Communication Lines- Fiber-optic lines will be potholed every 25 feet within the work area. Telephone/Cable lines will be potholed every 50 feet within the work area. IF there is any damage to a fiber optic line, DO NOT LOOK INTO THE FIBER OPTICS. THE LIGHT WAVES GOING THROUGH THE FIBER OPTICS CAN CAUSE SERIOUS EYE INJURIES.

5.5.9. Other Utilities:

- 5.5.9.1. Will be potholed every 25 feet for lines less than 8" in diameter.
- 5.5.9.2. Will be potholed every 50 feet for lines 8" though 24" in diameter.
- 5.5.9.3. Will be potholed every 100 feet for lines greater than 24" in diameter.
- 5.5.9.4. At least two (2) potholes must be obtained for each utility within the work zone regardless of the size of the work area.

5.5.10. Utilities in Roadways:

- 5.5.10.1. Utilities that are located within the roadway will be potholed.
- 5.5.10.2. Street plates will be obtained to cover a pothole when there is live traffic on the roadway. The street plates shall be of sufficient size and thickness to allow traffic to safely drive over them by pre-grind to allow the trench plates to be flush with the horizontal plane. The street plates shall be secured in place in accordance with the local, state and/or federal requirements.
- 5.5.10.3. For roadway work not scheduled to be excavated in the current operation, an asphalt patch will be placed over the pothole. This will be done after all pothole information has been recorded and the pothole has been offset using stakes and ribbon.

5.5.11. Utility Locating:

- 5.5.11.1. Subcontractors shall locate and identify all utilities prior to the start of ground-penetrating activities. Equipment operators must understand the locations and types of utilities.
- 5.5.11.2. Prior to the start of any excavation a utility locate service must be contacted. Each state has a different locate service with specific rules outlining their services. It is very important to understand the state or local guidelines in advance of your excavation. Typically locate companies require 2 days advanced notice before performing a locate. Before calling for locate services, the excavation area must be pre-marked with white paint, stakes or flags. In addition, newly constructed work IS NOT covered (i.e. drainage, electrical subcontractor new installations, etc.) and shall be located by other means. The Subcontractor engineer, foreman, or superintendent responsible for this work will be contacted to verify what has been constructed and an appropriate as-built requested. The One Call service can be contacted by calling 811.
- **5.5.12. Utility Color Markings** The following colors and symbols have been adopted by all utilities for marking underground utilities:

Blue Water
Orange Telephone, Railroad, Cable TV
Green Sewer, Storm Drain
Red Street Lighting, Electric, Traffic Signals (may be orange)
Yellow Gas



"Freedom from Danger"

Pink	,
White	Proposed Excavation
	Reclaimed Water, Irrigation, and Slurry Lines

5.4.5. Dig Permits:

5.4.5.1. A <u>Dig Permit</u> is required for all operations which penetrate the original ground surface. The Subcontractor foreman of each operation is responsible for ensuring that the Dig Permit, Job Hazard Analysis (JHA) and Pre-Task Plan (PTP) and all necessary drawings are available at the operation and in the cab of the excavator, backhoe, etc. The operator is ultimately responsible and will be held accountable to ensure the operation does not proceed without a valid Dig Permit. The BNB Management will verify that the Dig Permit has been properly completed.

5.4.5.2. The following documents will be attached before being distributed to the foreman and operator:

- 5.4.5.2.1. A signed copy of the Job Hazard Analysis (JHA).
- 5.4.5.2.2. A Pre-Task Plan (PTP) must be completed by the crew and signed by all members.
- 5.4.5.2.3. The page of the Topography & Utility Plan sheets for the work zone that the permit covers. Any utility relocations that have been completed before the start of the operation must be clearly noted on these drawings.
- 5.4.5.2.4. A copy of the Utility Plan sheets for the work zone the permit covers. Notes and highlights must be made on these drawings to indicate which runs have been installed.

5.4.5.3. Unintentional Uncovering of a Utility (known or unknown utility):

- 5.4.5.3.1. If during the course of excavation, a utility has been exposed, it is the Subcontractors' responsibility to inspect and support these facilities prior to backfilling. If damage of any kind is discovered, or any suspicion of damage exists, call the utility engineer so documentation can take place. The utility engineer will then notify the utility owner.
- 5.4.5.3.2. All unidentified underground utilities that are discovered during the course of excavation activities shall be marked on the As Built Plans and the BNB Project Manager shall be IMMEDIATELY notified.

5.4.6. Reporting Requirements:

5.4.6.1. If a utility strike/hit does occur, several reporting steps are required:

- 5.4.6.1.1. First and foremost, clear and secure the area if there is potential for further exposure to hazardous environments.
- 5.4.6.1.2. Contact the appropriate utility owner to inform them of the damage so they can inspect and repair, if necessary.
- 5.4.6.1.3. Notify the Utility Engineer and BNB Project Superintendent.
- 5.4.6.1.4. The Subcontractor shall complete the Incident Report Form and transmit it to the BNB Project Manager.

5.4.7. Overhead Utilities Procedure:

5.4.7.1. Any equipment having the ability to work under, cross underneath, and/or reach over overhead electrical lines will follow the guidelines set forth by OSHA in 1926.1408, 1926.1411, & 1926.600.



"Freedom from Danger"

- BNB recommends that equipment working in close proximity to overhead electrical lines be equipped with a Proximity Warning Device (PWD) to notify the operator and/or operatives surrounding the equipment of the proximity to the danger zone.
- 5.4.7.2. If working near overhead electrical lines, the Subcontractor will install "DANGER OVERHEAD POWERLINES" signs at all designated equipment crossings. This sign must state the voltage of the overhead line. For all other utilities, the Subcontractor will install "DANGER OVERHEAD UTILITY" signs to warn of the overhead hazard. For all other equipment traveling underneath overhead utilities, to include use of on-road or off-road haul trucks transporting dirt / materials to the project a "NO DUMP ZONE" will be established to eliminate dumping within 50' of either side of the overhead line. The Subcontractor will identify the "NO DUMP ZONE" through the use of signage.
- 5.4.7.3. Subcontractor will provide a full-time spotter(s) whenever any equipment has the ability to work under, cross underneath, and / or reach over overhead utility lines, for example, electrical, cable, phone, fiber-optic, etc. This spotter will assume no other duty and be equipped with air horn, reflective vest, and red flag.
- 5.4.7.4. Subcontractor will limit equipment travel underneath overhead utilities to designated areas only. To prevent equipment from traveling underneath lines, the Subcontractor will install a means of protection. At a minimum, protection will consist of yellow poly rope with red flagging.
- 5.4.7.5. Subcontractor will protect all guy wires and utility poles from contact with equipment operating in the area through the use of barricades (water-filled barricade, temporary concrete barrier, or pipe bollards). If installed on a road project and within the clear zone of an active travel lane all barriers must be installed per the Department of Transportation (DOT) Index & Manual on Uniform Traffic Control Devices (MUTCD).

5.5 Hazards

5.5.1. The accidental exposure to utilities could result in an injury or even fatality. Injury could be caused by explosion, fire, electrical shock, asphyxiation, struck-by hazards, and more.

5.5.2 Hazard Controls

5.5.3.1. If utility conflicts are found, a potential option for hazard elimination would be to change the plans to avoid being in proximity with existing utilities. Effort must be taken to have the utility conflicts related to the scope of work removed or relocated prior to commencing work. If, after contacting the appropriate utility companies, the utility cannot be removed or relocated prior to commencing, then additional means and methods shall be employed following the hierarchy of controls identified below.

5.5.3 Engineering Controls

5.5.3.1. If utilities in proximity of the work cannot be eliminated/relocated, then the next preferred control is to raise the height of overhead utilities or insulate the wires.

5.5.4 Administrative Controls

5.5.4.1. Administrative controls could be the installation of warning signs, use of spotters, use of protective barricades, proximity warning/control devices for equipment, and/or use of technology to visually identify utilities.

5.5.5 Personal Protective Equipment

Health, Safety and Environmental Manual

"Freedom from Danger"

5.5.5.1. Personal Protective Equipment controls could consist of grounded cabs on equipment, insulated/rated gloves, rated face shields, and/or reflective vests.

5.6 Training

5.6.1. BNB Operations personnel and all subcontractor personnel engaged in excavation or work in proximity to overhead lines must be trained on this standard and BNB's Avoidance Policy. Subcontractor employees engaged in excavation activities must be "Dig Safe" trained before working on an excavation operation. This training is also required for personnel involved in the completion of the Dig Permit.

6.0 References

OSHA 1926.1408

OSHA 1926.1411 - Power Line Safety

OSHA 1926.600 - Equipment

7.0 Attachments

Dig Permit

Core Drilling / Saw Cutting Checklist

Subcontractor Requirements

<u>Utility Avoidance - Best Practices</u>

"Freedom from Danger"



Walking and Working Surfaces

1.0 Purpose

1.1. The purpose of this standard is to establish requirements for the design, maintenance, and use of walking and working surfaces and stairs.

2.0 Scope

2.1. This policy applies to walking and working surfaces and stairs at BNB projects and offices.

3.0 Responsibility

3.1 Project Management

3.1.1. BNB Project Management & Supervision are responsible for preplanning walking and working surfaces and stairways for each project. For example, the use of ladders to access work areas on different levels should be identified during preconstruction, so effective controls such as a temporary stair tower may be put in place during construction. During construction, BNB Project Management & Supervision are responsible for inspecting walkways, stairs, and other surfaces to ensure a safe workplace.

3.2 Workers

3.2.1. Workers are expected to maintain all walkways and stairs in a safe condition throughout the workday and report any issues to management. Work areas must be cleaned up at a pace consistent with production and waste-generating activities. If their work will close an emergency exit or walkway, they must work with BNB Project Management & Supervision.

4.0 Definitions

- 4.1. **Debris** Materials, supplies, equipment, trash, etc. that have accumulated during work activities.
- 4.2. **Floor Holes** an opening measuring less than twelve inches but more than one inch in its least dimension in any floor, roof, platform, or surface through which materials but not persons may fall, such as a belt hole, pipe opening, or slot opening.
- 4.3. Floor Openings an opening measuring twelve inches or more in its least dimension in any floor, roof, platform, or surface through which persons may fall.
- 4.4. Unprotected sides and edges means any side or edge (except at entrances to points of access) of a stairway where there is no stair rail system or wall 36 inches (.9 m) or more in height, and any side or edge (except at entrances to points of access) of a stairway landing, or ladder platform where there is no wall or guardrail system 39 inches (1 m) or more in height.
- 4.5. **Unstable Ground –** earth material that because of its nature or the influence of related conditions cannot be depended upon to remain in place without extra support.
- 4.6. Walking and Working Surface any area including, but not limited to, floors, a roof surface, bridge, the ground, and any other surfaces whose dimensions are forty-five inches or more in all directions, through which workers can pass or conduct work.
- 4.7. **Wall opening** an opening at least thirty inches high and eighteen inches wide, in any wall or partition, through which persons may fall, such as an opening for a window, a yard arm doorway, or chute opening.

5.0 Procedure

5.1 General

- 5.1.1. Walkways, stairways and roadways shall be kept clear to allow the safe movement of persons, material and equipment.
- 5.1.2. Electrical cords, hoses, ropes, conduit, pipe and other hazards shall not be placed in walkways, stairways and work areas in such a manner as to create a tripping hazard. Examples of acceptable

BNB

"Freedom from Danger"

- methods for avoiding a tripping hazard include: taping the items down, running the items along the area edge or barricading the area.
- 5.1.3. Impalement protection must be installed on rebar or other similar objects in walkways.
- 5.1.4. Barricades, fencing, and other materials in public areas can't have hardware, locks, protrusions, or irregular surfaces on the public side that a person could strike against, or snag/catch their clothes or body parts on.
- 5.1.5. Fencing shall be secure. Fence bases that have the potential to cause a tripping hazard shall be labeled, coned and secured.
- 5.1.6. Minimum 28-inch wide aisles will be provided at all times
- 5.1.7. Emergency exits and evacuation routes shall be clearly marked and kept clear at all times
 - 5.1.7.1. A clean work area prevents slips, trips and falls and helps safety and production.
 - 5.1.7.2. Clean as you go and at the end of each day.
 - 5.1.7.3. Materials must be stored in an orderly manner.
 - 5.1.7.4. Spills and leaks are to be cleaned up immediately.
 - 5.1.7.5. Round containers can be trip hazards and can be easily kicked off a floor.
 - 5.1.7.6. When a building or structure has only one point of access between levels, that point of access shall be kept clear to permit free passage of employees. When work must be performed or equipment must be used such that free passage at that point of access is restricted, a second point of access shall be provided and used.
 - 5.1.7.7. When a building or structure has two or more points of access between levels, at least one point of access shall be kept clear to permit free passage of employees.

5.1.8 Open Holes

- 5.1.8.1. Floor hole and floor opening covers shall be secured against displacement and adequately marked with the word "Hole" or "Cover".
- 5.1.8.2. All covers must be designed to support without failure 4 times the intended load.
- 5.1.8.3. Hole covers need a tapered/beveled edge to be flush with the existing surface to minimize trip hazards.
- 5.1.8.4. Cover and secure roof/floor openings wider than 2" and never leave them unprotected and/or unattended.
 - 5.1.8.4.1. Guardrails can be used in lieu of covers.
 - 5.1.8.4.2. Equipment should not travel over hole covers—hole covers may be constructed to prevent equipment from being able to travel over the cover.

5.1.9 Cords, hoses, lines, etc.

- 5.1.9.1. Cords, hoses, etc. in public areas must have ADA-compliant covers to protect them from damage and give safe passage to the public.
- 5.1.9.2. Correct tripping hazards such as cords, hoses or debris in work areas or paths of travel.
 - 5.1.9.2.1. Extension cords, hoses, welding leads, etc., must be run safely overhead in all stairs, aisles, and exit areas.

5.1.10 Elevated Walking and Working Surfaces

- 5.1.10.1. When working/walking surfaces are 6' or greater in height, proper fall protection methods must be used.
 - 5.1.10.1.1. BNB will approve perimeter access points for material handling. Personal fall protection must be put in place before cables or rails are taken down, or holes uncovered. Barricade the area, place signage, and leave a spotter.
 - 5.1.10.1.2. Barricades must be a minimum of 10' from edges.

"Freedom from Danger"

- 5.1.10.2. Never remove guardrails or warning barricades without permission from BNB Project Management & Supervision.
- 5.1.10.3. Railings and toe boards shall be provided along all unprotected and open sides, edges, and surfaces 6' above ground levels.

5.1.11 Guardrails

5.1.11.1. Guardrails must be provided at floor openings, open sides, and/or leading edges or personal fall protection must be used.

5.1.11.2. Guardrails or wire cables must follow these requirements:

- 5.1.11.2.1. shall have a vertical height within the range of 42 inches to 45 inches from the upper surface of the top rail to the floor, platform, runway, or ramp level. (Note: the permissible tolerance on height dimensions is one inch).
- 5.1.11.2.2. The maximum deflection for the top rail when a load of 200 pounds is applied in any direction at any point on the top rail shall not exceed 3 inches in any direction.
- 5.1.11.2.3. Mid-rail/cable and toe boards must be installed and able to withstand 150 lbs.
- 5.1.11.2.4. Guardrails or wire cables will not be used for anchoring personal fall arrest/restraint.
- 5.1.11.2.5. Upright supports for a wood guardrail system shall be spaced no greater than every 8 ft. on center.

5.1.12 Stairways

- 5.1.12.1. Temporary stair towers or prefabricated stairs should be used to access different building levels.
- 5.1.12.2. Never use stairs and ramps that are incomplete, incorrectly constructed, improperly installed, or damaged.
- 5.1.12.3. Stairs, ladders, and ramps must be inspected before use.
- 5.1.12.4. A stairway or ladder shall be provided at all personnel points of access where there is a break in elevation of 19 inches or more, and no ramp, runway, sloped embankment, or personnel hoist is provided. Stairways must extend to the uppermost floor that has been planked or decked if steel framed.
- 5.1.12.5. Stair steps must be illuminated with at least 5-foot candles of light
- 5.1.12.6. Stairway openings must be guarded on all sides except the entrance.
- 5.1.12.7. Snow and Ice must be removed from stairs before they are allowed to be used.
- 5.1.12.8. Stairways shall be at least 24 inches in width and shall be equipped with stair rails, handrails, treads, and landings.
- 5.1.12.9. Railings and toe boards shall be installed around stairwells.
- 5.1.12.10. Temporary stairways that will not be a permanent part of the structure on which construction work is being performed shall be at least 24 inches in width. The stairway shall have landings at each floor, or level, of not less than 30 inches in the direction of travel and extend at least 24 inches in width at every 12 feet or less of vertical rise.
- 5.1.12.11. Stairs shall be installed between 30° and 50° from horizontal.
- 5.1.12.12. Unprotected sides and edges of stairway landings shall be provided with railings.
- 5.1.12.13. Metal pan landings and metal pan treads, when used, shall be secured in place before filling with concrete or other material.
- 5.1.12.14. All parts of stairways shall be free of hazardous projections, such as protruding nails.





5.1.12.15. Slippery conditions on a stairway shall be eliminated before the stairway is used to reach another level.

5.1.12.16. Stairways having four or more risers or rising more than 30 inches (76 cm), whichever is less, shall be equipped with:

- 5.1.12.16.1. At least one handrail; and
- 5.1.12.16.2. A stair rail consisting of a top rail and mid-rail along each unprotected side or edge.
- 5.1.12.16.3. The height of stair rails shall be not less than 36 inches from the upper surface of the stair rail to the surface of the tread, in line with the face of the riser at the forward edge of the tread.
- 5.1.12.16.4. Mid-rails shall be located at a height midway between the top edge of the stair rail and the stairway steps.
- 5.1.12.16.5. Screens, mesh, or other material, when used in lieu of mid-rails, shall extend from the top rail to the stairway step, and along the entire opening between top rail supports.
- 5.1.12.16.6. Handrails and the top rails of stair rails shall be capable of withstanding, without failure, a force of at least 200 pounds (890 n) applied within 2 inches of the top edge, in any downward or outward direction, at any point along the top edge.
- 5.1.12.16.7. Stair and handrails shall be so surfaced as to prevent injury to employees from punctures or lacerations, and to prevent snagging of clothing.
- 5.1.12.16.8. Handrails shall provide an adequate handhold.
- 5.1.12.16.9. Except during stairway construction, foot traffic is prohibited on stairways with pan stairs where the treads and/or landings are to be filled in with concrete or other material at a later date, unless the stairs are temporarily fitted with wood or other solid material at least to the top edge of each pan.
- 5.1.12.16.10. Except during stairway construction, foot traffic is prohibited on skeleton metal stairs where permanent treads and/or landings are to be installed at a later date, unless the stairs are fitted with secured temporary treads and landings long enough to cover the entire tread and/or landing area.
- 5.1.12.16.11. Treads for temporary service shall be made of wood or other solid material, shall cover the full width and depth of the stair and shall be supported to prevent undue deflection.

5.1.13 Ramps

- 5.1.13.1. Ramps must have non-skid surfaces.
- 5.1.13.2. Ramps or runways shall be not less than 20 inches in width and shall be secured and supported so as to avoid deflection and springing action.
- 5.1.13.3. Securely fastened cleats or other means shall be used on inclined runways that are sloped two feet in 10 feet or more to improve the footing. Where cleats are used, they shall be eight inches or more in length and not more than 16 inches apart.
- 5.1.13.4. When planks are used for raised walkways, runways, or sidewalks, they shall be secured against displacement. Planks shall be uniform in thickness and all exposed ends shall be provided with beveled cleats to prevent tripping.
- 5.1.13.5. Wheelbarrow ramps over three feet high shall be not less than two feet, six inches wide and secured at each end to prevent ramp from sliding. Platform planks shall be firmly cleated together.

5.2 Hazards



"Freedom from Danger"

5.2.1. Potential hazards associated with inadequate walking/working surfaces and stairs may be trips, slips, falls, electrical shock, damage to equipment, etc.

5.3 Hazard Controls

5.3.1 Engineering Controls

- 5.3.1.1. Personnel should locate their equipment and materials in areas where they will not protrude in walkways.
- 5.3.1.2. Instead of using ladders to access different levels, temporary or permanent stairways can be installed and used.

5.3.2 Administrative Controls

5.3.2.1. Housekeeping must be sufficient throughout the workday and conducted in accordance with Housekeeping. Inspections should be conducted daily to ensure walking and working surfaces are kept in proper condition. Signage may be posted to remind workers to keep walkways clear.

5.3.3 Personal Protective Equipment

5.3.3.1. All personnel must wear sturdy boots with ankle protection and hard soles. No running shoes of any kind are permitted on work sites, NO SAFETY TOE TENNIS SHOES ALLOWED.

5.3.4 Training

5.3.4.1. Personnel will receive site-specific training on walking and working surfaces during New Hire Orientation. In addition, employees who use stairways should receive additional training as necessary.

6.0 References

FED / OSHA 29 CFR 1926 Subpart X

FED / OSHA 29 CFR 1910 Subpart D & I - Walking Working Surfaces and Personal Fall Protection Systems

7.0 Attachments

Fall Protection Plan

Pre-Task Plan

Demolition Permit

Aerial Work Platform Inspection Checklist

Scaffolding Inspection Checklist



"Freedom from Danger"

Welding, Cutting & Hot Work

1.0 Purpose

1.1. Each year numerous deaths from explosions, electrocutions, asphyxiation, falls and crushing injuries are associated with welding activities. In addition, numerous health hazards are associated with exposure to fumes, gases, and ionizing radiation formed or released during welding, cutting, and brazing, including heavy metal poisoning, lung cancer, metal fume fever, flash burns, and welder's flash (burn to eyes). Diligent and proper enforcement of this standard will protect our work, property, and the ongoing operations of our projects.

2.0 Scope

2.1. This standard applies to welding, cutting, grinding, and other hot-work related activities that take place on BNB projects. Hot work activities consist of open flames, heat, arcs, and / or sparks.

3.0 Responsibility

3.1 Project Management

3.1.1. BNB Project Management is to convey the requirements of this program to BNB personnel or subcontractors who engage in hot-work operations prior to the start of their work. Project Management must ensure that adequate HS&E documentation has been submitted, including a Hot-Work Permit, Respirator Fit Testing Data (if applicable), Pre-Task Plan, and any Air Monitoring documentation associated with the work. Project Management must also check with local municipalities pertaining to hot work permitting.

3.2 Supervision

3.2.1. Supervision should understand safe practices and enforce company safety policies and procedures associated with hot-work operations. Supervisors are to ensure a Hot-Work Permit has been completed and reviewed by BNB prior to the start of work. Also, supervision must ensure that hot-work operations are carried out in compliance with the requirements of the Hot-Work Permit.

3.3 Workers

3.3.1. Workers must be responsible for safe work practices related to Hot-Work operations. Shall operations not be performed safely with controlled hazards; workers shall cease all hot work operations. Equipment operators should tag and remove defective equipment. Repairs shall be made only by qualified personnel and in accordance with the manufacturer's recommendations.

4.0 Definitions

- 4.1. **Competent Person** One who can identify existing and predictable hazards in the surroundings or working conditions which are unsanitary, hazardous, or dangerous to employees, and who has authorization to take prompt corrective measures to eliminate them
- 4.2. Hydraulic Back-Pressure Valve / Hydraulic Seal / Hydraulic Flash Arrester / Hydraulic Valve and Backflow Check Valve Terms used interchangeably to mean a device designed and constructed to prevent a flash-back from reaching a fuel gas source, manifold or cylinder and to prevent accidental mixing of fuel gas and oxygen by reserve flow.
- 4.3. Welder and Welding Operator Any operator of electric or gas welding and cutting equipment
- 4.4. **Qualified Person, Attendant or Operator** A person designated by the employer who by reason of training, experience, or instruction has demonstrated the ability to safely perform all assigned duties and, when required, is properly licensed in accordance with federal, state, or local laws and regulations
- 4.5. Fire Watch An individual listed on the Hot-Work Permit with required training on the inspection and use of fire-fighting equipment. The Fire Watch is to continuously monitor the work area during Hot-Work and for 30 minutes after the Hot-Work is completed



"Freedom from Danger"

- 4.6. **Hot Work** Any work involving burning, welding, or similar operations as defined above that is capable of initiating fires or explosions
- 4.7. Hot-Work Permit (HWP) A multi-part form consisting of instructions, identification of who will be involved in the Hot-Work operations, location of the Hot-Work operations, the nature of the Hot-Work operation, and precautions to be taken prior to and during Hot-Work operations

5.0 Procedure

5.1 General Procedures

- 5.1.1. Refer to the <u>Confined Spaces policy</u> for ventilation and other requirements for hot work in confined spaces.
- 5.1.2. Inspect the immediate work area and areas adjacent, beneath and above the immediate work area for combustible and/or flammable materials or liquids.
- 5.1.3. Cover all wood planking, scaffolds, wooden forms, and flammable and/or combustible materials or liquids within 35ft. of the work area that cannot be removed, with approved fire-retardant blankets, pads, curtains, covers and/or shields.
- 5.1.4. When hot work is performed at an elevated location, consider sparks or slag that can fall and land under the hot work operation.
- 5.1.5. At least one fully charged and operable fire extinguisher that is appropriate for the type of possible fire must be immediately available at the hot work location.
- 5.1.6. Adequate ventilation is required for all hot work operations.
- 5.1.7. The floor is swept clean within 35ft. of the work area.
- 5.1.8. Combustible floors are protected with approved fire-retardant blankets, pads, curtains, covers and/or shields.
- 5.1.9. Special precautions should be taken for heating pipes or other metal that is in contact with combustibles, walls, partitions, ceilings, or roofs.
- 5.1.10. Sprinkler heads and/or sensors must be protected if hot work is done in close proximity to an automatic fire detection or suppression system. Systems may need to be placed in test mode during hot work activities.

5.1.11. Hot work is not allowed in the following areas:

- 5.1.11.1. In areas not authorized by BNB Management.
- 5.1.11.2. In the presence of explosive atmospheres (e.g. gases, vapors, liquids, or dusts).
- 5.1.11.3. In areas where explosive atmospheres could potentially develop.
- 5.1.11.4. In areas with an accumulation of combustible dusts.

5.2 Fire Watch Procedures

5.2.1. The fire watch must:

- 5.2.1.1. See <u>Fire Prevention Policy</u> for more information.
- 5.2.1.2. Be familiar with the Project Specific Fire Prevention Plan.
- 5.2.1.3. Be aware of the inherent hazards of the work area and of the hot work.
- 5.2.1.4. Stop hot work operations if unsafe conditions develop and shall notify management and the supervisor for reassessment of the conditions.
- 5.2.1.5. Have fire-extinguishing equipment readily available and is to be trained in its' use.
- 5.2.1.6. Be familiar with the facilities and procedures for sounding an alarm in the event of a fire.
- 5.2.1.7. Watch for fires in all exposed areas.
- 5.2.1.8. Extinguish fires only when the fires are within the capacity of the fire-extinguishing equipment available and sound an alarm according to the Project Specific Fire Prevention Plan.



"Freedom from Danger"

- 5.2.1.9. Follow specific Hot Work Permit instructions.
- 5.2.1.10. Additional fire watch personnel might be necessary when working in close proximity to open shafts, elevated heights, or where sparks can travel through openings.

5.3 Hot-Work Permits (HWPs)

5.3.1. HWPs shall be completed:

- 5.3.1.1. For welding, cutting, grinding, and other hot-work activities.
- 5.3.1.2. Prior to hot work activities commencing.
- 5.3.1.3. For up to one work shift with the exception of exterior construction such as steel erection or reinforcing steel which may be completed for up to one week.

5.3.2. HWP Process

- 5.3.2.1. Personnel who are to engage in hot work obtain a permit from BNB.
- 5.3.2.2. Personnel completes permit section 1.
- 5.3.2.3. Personnel gives completed permit to BNB Supervisor.
- 5.3.2.4. BNB Supervisor verifies adequacy of the permit.
- 5.3.2.5. BNB Supervisor and personnel sign Part 1.
- 5.3.2.6. BNB Supervisor retains Part 1.
- 5.3.2.7. Personnel takes Part 1A and retains it for records.
- 5.3.2.8. Personnel fills out and displays permit at the location of the hot work.
- 5.3.2.9. BNB Supervisor to retain HWP until conclusion of the project.

5.4 Gas Welding and Cutting Operations

5.4.1. Personnel conducting Gas Welding and Cutting Operations must:

- 5.4.1.1. Inspect torches, hoses, valves and cylinders prior to use and immediately remove defective equipment from service.
- 5.4.1.2. Keep oxygen fittings, cylinders, caps, couplings, regulators, hoses, and other apparatus away from and free of oil and grease. Do not handle oxygen cylinders while wearing oily gloves.
- 5.4.1.3. Ensure flashback arrestors/check valves are installed at all oxygen and fuel gas regulator gauges.
- 5.4.1.4. Use only hose couplings that cannot be unlocked or disconnected by means of a straight pull.
- 5.4.1.5. Keep hoses clear of walkways, ladders, and stairways.
- 5.4.1.6. Use a spark lighter (striker) to light torches. Do not use matches and/or lighters.
- 5.4.1.7. Do not strike an electrode against a cylinder to strike an arc.
- 5.4.1.8. Ensure that hot sparks, hot metal or cut pieces do not fall on cylinders, hoses, machinery, combustible material, legs, feet, or persons below.
- 5.4.1.9. Shut off cylinder valves and bleed regulators and hoses at the end of each shift.

5.5 Arc Welding and Cutting Operations

5.5.1. Personnel conducting arc welding and cutting activities must:

- 5.5.1.1. Inspect equipment prior to use and immediately remove damaged equipment from service.
- 5.5.1.2. Use and position screens or shields properly in order to protect workers and the public from arc ray exposure during Arc Welding and Cutting Operations.
- 5.5.1.3. Never overload welding cables or operate with poor connections.



"Freedom from Danger"

- 5.5.1.4. Never strike an electric arc on a gas cylinder.
- 5.5.1.5. Use only properly designed metal electrode holders.
- 5.5.1.6. Never dip hot electrode holders in water.
- 5.5.1.7. Dispose of discarded electrode stubs properly, as they can create a slip/trip/fall hazard.
- 5.5.1.8. Ensure that the frame of the welding machine is properly grounded.
- 5.5.1.9. Welding/cutting/ground cables must be in operable condition with no visible damage.
- 5.5.1.10. Never attach a ground cable to a pipeline containing gases or flammable liquids.
- 5.5.1.11. Keep cables clear of walkways, ladders, and stairways. String all cables overhead with non-metallic hangers if needed.
- 5.5.1.12. Ensure that cables are protected from equipment damage (e.g. forklifts, scissor lifts, etc.).
- 5.5.1.13. Locate grounds as close to the work location as possible to prevent arcing.
- 5.5.1.14. Stop operations if unsafe conditions develop and notify management and the supervisor for reassessment of the conditions.

5.6 Cylinder Handling

5.6.1. Personnel handling cylinders must:

- 5.6.1.1. Store, move or use cylinders in an upright position.
- 5.6.1.2. Close valves, remove regulators, and replace valve safety caps before moving or storing.
- 5.6.1.3. Move cylinders by tilting and rolling them on their bottom edges; by use of a bottle cart; or with motorized equipment. Never lay cylinders on their sides and roll them.
- 5.6.1.4. Store Oxygen cylinders separated from fuel-gas cylinders or combustible materials (especially oil or grease), a minimum distance of 20 feet or by a noncombustible barrier at least 5 feet high having a fire-resistance rating of at least one-half hour.
- 5.6.1.5. Never use cylinders as rollers or supports whether full or empty.
- 5.6.1.6. Never drop cylinders or permit them to strike one another violently, even when empty.
- 5.6.1.7. Use bottle carts, chains, or other steadying devices to keep cylinders from being knocked over while in use.
- 5.6.1.8. Ensure cylinders are marked with the chemical or trade name of the gas.
- 5.6.1.9. Keep storage areas free of debris and other combustible materials.
- 5.6.1.10. Open cylinder valves slowly to prevent damage to the regulator.
- 5.6.1.11. Close and tighten the gland nut when the valve on a fuel gas cylinder is opened and there is a leak around the valve stem. If this action does not stop the leak, the cylinder shall be properly tagged, removed from the work area, and taken outdoors away from personnel and sources of ignition. The supplier shall promptly be notified of the leaking cylinder valve and the supplier's instructions shall be followed.
- 5.6.1.12. Position cylinders where they will not be struck by sparks, hot slag, or flame, and where they cannot become part of an electrical circuit.
- 5.6.1.13. Never take cylinders containing oxygen, acetylene into confined spaces.
- 5.6.1.14. Not use acetylene at a pressure in excess of 15 pounds per square inch gauge pressure.
- 5.6.1.15. Not use oxygen as a substitute for compressed air.
- 5.6.2. Before a regulator to a cylinder valve is connected, the valve shall be opened slightly and closed immediately ("cracking"). The person cracking the valve shall stand to one side of the outlet, not in front of it. Never crack a valve near ignition sources.
- 5.6.3. In the event that fuel gas should leak from the cylinder valve, rather than from the valve stem, and the gas cannot be shut off, the cylinder shall be properly tagged, removed from the work area, and taken

Health, Safety and Environmental Manual

"Freedom from Danger"

outdoors away from personnel and sources of ignition. The supplier shall promptly be notified of the leaking cylinder valve and the supplier's instructions shall be followed.

5.7 Hazards

5.7.1. Hazards related to hot work may consist of uncontrolled ignition of flammable gas, personnel or public injury, property damage, uncontrolled release of high-pressure gases, fire and/or explosion, electrical shock, struck-by, injury to eyes, skin, and lungs, and potential death.

5.8 Hazard Controls

5.8.1. Engineering Controls

- 5.8.1.1. If possible, eliminate the presence of flammable/combustible materials during the design phase at or around planned welding activities to mitigate potential fire hazards during construction.
- 5.8.1.2. Alternate methods to hot work should be considered where practical. For example, repetitive cutting of metal studs may be performed at a central location where no combustibles are present, bolting in lieu of welding, or prefabrication offsite.

5.8.2. Administrative Controls

- 5.8.2.1. Combustibles should be moved to a designated safe distance from the work or have combustibles properly shielded against ignition, if the work cannot be moved.
- 5.8.2.2. If fire hazards cannot be removed, guards or fire blankets should be used to confine the heat sparks and slag and to protect the immovable fire hazards.
- 5.8.2.3. Make sure that the welding area is watched for one-half hour after welding is completed to ensure that no sparks or smoldering fires are present.
- 5.8.2.4. Complete hot work permits and assign fire watch as necessary.

5.9 Personal Protective Equipment

5.9.1. Welders must wear:

- 5.9.1.1. Non-flammable gloves with gauntlets
- 5.9.1.2. Appropriate foot protection
- 5.9.1.3. Aprons (leather) and or shirts that have leather sleeves and collars
- 5.9.1.4. Helmets, hoods, and face shields designed to attach to a standard hardhat
- 5.9.1.5. Eye protection
- 5.9.1.6. Cutting goggles must be worn with oxyacetylene cutting activities
- 5.9.1.7. Respiratory protection:
- 5.9.1.8. Outdoors: Respirators are required for any operation involving stainless steel, beryllium, cadmium, lead, or mercury. For other materials, respirators may be required when natural or mechanical ventilation is insufficient to prevent exposure to airborne contaminants.
- 5.9.1.9. Indoors: Respirators shall be used when local exhaust or mechanical ventilation is not feasible or able to prevent listed exposure limits.
- 5.9.1.10. Enclosed spaces: Supplied-air respirators shall be used when local exhaust ventilation is not an effective means for preventing potentially hazardous exposures.

5.10 Training



"Freedom from Danger"

5.10.1. Only authorized and trained individuals shall be permitted to perform hot work operations.

5.10.2. Fire watch personnel must be trained in the use of fire extinguishing equipment and be familiar with the Project Specific Fire Prevention Plan. Personnel performing hot work activities must have adequate training and experience to perform their duties safely. Personnel operating arc welding equipment and gas-shielded welding equipment must be competent. Personnel handling fuel gas must be instructed on safe practices.

6.0 References

FED / OSHA 1926 Subpart J - Welding and Cutting

FED / OSHA 1910.251-255 - Welding, Cutting, and Brazing

American Welding Society Standards

7.0 Attachments

Hot-Work Permit

Pre-Task Plan

Demolition Permit

Confined Space Entry Permit



Wildfire Smoke & Outdoor Air Quality

1. Purpose

1.1. Air quality can be negatively impacted by wildfires, SMOG, agricultural activities, and other atmospheric emissions. This Policy is intended to provide a guideline to monitor, evaluate and respond to changing conditions as a result of environmental impacts such as wildfires which may affect the Safety and Health of our employees.

2. Scope

2.1. This section applies to workplaces where the current Air Quality Index (AQI) for PM2.5 is 151 or greater in California or 69 or greater in Washington, regardless of the AQI for other pollutants, **and where BNB** should reasonably anticipate that **our** employees may be exposed to atmospheric contaminants such wildfire smoke, SMOG, agricultural activities and other contaminants.

2.2. The following workplaces and operations are exempt:

- **2.2.1.** Enclosed buildings or structures in which the air is filtered by a mechanical ventilation system and the employer ensures that windows, doors, bays, and other openings are kept closed to minimize contamination by outdoor or unfiltered air.
- 2.2.2. Enclosed vehicles in which the air is filtered by a cabin air filter and the employer ensures that windows, doors, and other openings are kept closed to minimize contamination by outdoor or unfiltered air.
- **2.2.3.** BNB demonstrates that the concentration of PM2.5 in the air does not exceed a concentration that corresponds to a current AQI of 151 or greater by measuring PM2.5 levels at the jobsite location.
- 2.2.4. Employees exposed to a current AQI for PM2.5 of 151 or greater for a total of one hour or less during

Responsibility

3.1. Project Management & Supervision

3.1.1. BNB management and supervision will be responsible for relaying AQI information when it is at or exceeds 151 in California or 69 in Washington. Management and supervision are also responsible for ensuring that the monitoring of the current air quality index for PM 2.5 is less than 151 (CA) or 69 (WA). However, if the air quality is at or greater than 151, regardless of the AQI for other pollutants, voluntary respirator use of the N95 or equivalent APF 10 will be provided along with the Voluntary Respirator Use Form.

3.2. Workers

3.2.1. All employees working on a BNB project are highly encouraged to utilize available PPE provided while working during wildfire smoke and other air quality contaminant events and to inform BNB management of air quality hazards at the jobsite. This includes worsening of air quality and any adverse symptoms that may be the result from unhealthy or hazardous air quality such as asthma attacks, difficulty breathing, and chest pain. The "Voluntary Respirator Use Form" must be completed prior to donning any supplied respirator.

4. Definitions

4.1. Current Air Quality Index (Current AQI). The method used by the U.S. Environmental Protection Agency (U.S. EPA) to report air quality on a real-time basis. Current AQI is also referred to as the "NowCast," and represents data collected over time periods of varying length in order to reflect present conditions as accurately as possible.



- **4.2.** Washington Air Quality Advisory (WAQA) The method used by the Washington State Department of Ecology to report air quality on a real-time basis. It represents data collected over time periods of varying length in order to reflect present conditions as accurately as possible.
 - **4.2.1.** The current AQI is divided into six categories as shown in the table below, adapted from Table 2 of Title 40 Code of Federal Regulations, Part 58, Appendix G.

Air Quality Index (AQI)	
Categories for PM2.5	Levels of Health Concern
0 to 50	Good
51 to 100	Moderate
101 to 150	Unhealthy for Sensitive Groups
151 to 200	Unhealthy
201 to 300	Very Unhealthy
301 to 500	Hazardous

- **4.3. NIOSH**. The National Institute for Occupational Safety and Health of the U.S. Centers for Disease Control and Prevention. NIOSH tests and approves respirators for use in the workplace.
- **4.4. PM2.5.** Solid particles and liquid droplets suspended in air, known as particulate matter, with an aerodynamic diameter of 2.5 micrometers or smaller.
- **4.5.** Wildfire Smoke. Emissions from fires in "wildlands," as defined in Title 8, section 3402, or in adjacent developed areas.

5. Procedure

5.1. Atmospheric Monitoring

5.1.1. BNB shall determine employee exposure to PM2.5 for jobsites covered by this section before each shift and periodically thereafter, as needed to protect the health of the employee, by any of the following methods:

5.1.2. California or Other Regions Not Regulated by Local Authorities

- 5.1.2.1. Check AQI forecasts and the current AQI for PM2.5 from any of the following: <u>U.S. EPA AirNow website</u>, U.S. Forest Service Wildland Air Quality Response Program website, California Air Resources Board website, local air pollution control district website, or local air quality management district website; or
- 5.1.2.2. Obtain AQI forecasts and the current AQI for PM2.5 directly from the EPA, California Air Resources Board, local air pollution control district, or local air quality management district by telephone, email, text, or other effective method.

5.1.3. Washington

- 5.1.3.1. Check PM2.5 forecasts and the current PM2.5 from any of the following: Washington Air Quality Advisory website, Air Quality WA mobile app, Washington Smoke Information website, U.S. EPA AirNow website, EPA AirNow mobile app, U.S. Forest Service AirFire website, Local Clean Air Agency website; or
- 5.1.3.2. Obtain PM2.5 forecasts and the current PM2.5 directly from the Department of Ecology, Local Clean Air Agency, U.S. EPA, EPA EnviroFlash.info, or local clean air agency by telephone, email, text, or other effective method; or

"Freedom from Danger"

- 5.1.3.3. Measure PM2.5 levels at the work location in accordance with Appendix A in WAC Chapter 296-62-085.
- 5.1.3.4. If an index such as WAQA or AQI are used, the employer must use following table to find the equivalent WAQA or AQI for PM2.5.

NowCast PM _{2.5} in Micrograms per Cubic Meter (µg/m³)	NowCast Washington Air Quality Advisory (WAQA)	NowCast Air Quality Index (AQI)
20.5μg/m ³	101	69
55.5μg/m ³	173	151

5.2. Communicating to employees

- 5.2.1. BNB Safety Department will disseminate air quality information on a daily basis to effectively communicate the hazards of unhealthy or hazardous air quality to all affected employees. Employees are encouraged to inform BNB supervision of unhealthy or hazardous air quality at the jobsite. The communication shall include the following procedures:
 - 5.2.1.1. Informing employees of the current AQI for PM2.5 prior to the start of work.
 - 5.2.1.2. Provide protective measures to employees to reduce their unhealthy or hazardous air quality exposures.
 - 5.2.1.3. Encouraging employees to inform their employer of worsening air quality; and any adverse symptoms that may be the result of unhealthy or hazardous air quality exposure such as asthma attacks, difficulty breathing, and chest pain.

5.3. Engineering Controls

5.3.1. BNB shall reduce employee exposure to PM2.5 to less than a current AQI of 151 by engineering controls whenever feasible, for instance by providing enclosed buildings, structures, or vehicles where the air is filtered. If engineering controls are not sufficient to reduce exposure to PM2.5 to less than a current AQI of 151, then the BNB shall reduce employee exposures as much as feasible. In Washington this will be considered and encouraged at AQI 69, and mandatory at 151.

5.4. Administrative Controls

5.4.1. Whenever engineering controls are not feasible or do not reduce employee exposures to PM2.5 to less than a current AQI of 151, BNB shall implement administrative controls, if practicable, such as relocating work to a location where the current AQI for PM2.5 is lower, changing work schedules, reducing work intensity, or providing additional rest periods. In Washington this will be considered and encouraged at AQI 69, and mandatory at 151.

5.5. PPE

5.5.1. When required by this policy a N95 respirator equivalent APF 10 or higher shall be provided for voluntary use. (See Voluntary Respirator Use Form)

5.6. Training

- **5.6.1.** As required in our "Freedom from Danger", BNB shall provide employees with effective training and instruction.
 - 5.6.1.1. For California employees training requirements shall be in accordance with <u>CSO 5141.1</u> <u>Appendix B</u>
 - 5.6.1.2. For Washington employees training requirements shall be in aligned with the WAC 296-62-085 Appendix B

Health, Safety and Environmental Manual

"Freedom from Danger"

- **5.6.2.** Training topics for all employees will include, at a minimum:
 - 5.6.2.1. The health effects of wildfire smoke
 - 5.6.2.2. The right to obtain medical treatment without fear of reprisal
 - 5.6.2.3. How employees can obtain the current concentration of PM2.5 in the air
 - 5.6.2.4. The requirements of WAC 296-62-085 wildfire smoke rule (for projects in Washington)
 - 5.6.2.5. The employer's methods to protect employees from wildfire smoke
 - 5.6.2.6. The importance, limitations, and benefits of using a respirator when exposed to wildfire smoke
 - 5.6.2.7. How to properly put on, use, and maintain the respirators provided by the employer
- **5.6.3.** Supervisor Training will be provided to all supervisors prior to supervising employees performing work that exposes the worker to PM 2.5 that exceed their respective region's threshold for implementing worker protections (AQI 151/69). Supervisors will be trained in the following topics:
 - 5.6.3.1. The procedures the supervisor must follow to implement the applicable provisions of WAC 296-62-085 Wildfire Smoke or CSO 5141.1
 - 5.6.3.2. he procedures the supervisor must follow if an employee exhibits adverse symptoms of wildfire smoke exposure, including appropriate emergency response procedures; and
 - 5.6.3.3. Procedures for moving or transporting employees to an emergency medical service provider, if necessary. Local emergency facilities are located in each projects Site Specific Safety Plan and Crisis Management Plan.

5.7. Medical procedures in place for treatment of related symptoms

- **5.7.1.** If an employee has any of the following symptoms stated below that may be related to the exposure of unhealthy or hazardous air quality, they will need to report such symptoms their immediate supervisor:
 - 5.7.1.1. Irritation to the lungs
 - 5.7.1.2. Persistent coughing
 - 5.7.1.3. Phlegm, wheezing, or difficulty breathing
- **5.7.2.** Upon notification of symptoms from an employee, the supervisor will monitor the employee to determine if medical attention is necessary. If medical attention is necessary, the supervisor will implement the BNB Crisis Management Plan reporting and response procedures and facilitate the appropriate medical attention. Employees will not be penalized for seeking medical attention.

5.8. Notifications and Responses

5.8.1. Supervisors will report directly to the assigned BNB safety professional if they have an employee report symptoms related to wildfire smoke exposure.

References

CFR29 1926 Subpart D - Occupational Health and Environmental Controls

7. Attachments

- 7.1. BNB Respiratory Protection Program
- 7.2. Air Quality Guide for Particle Pollution
- 7.3. Voluntary Respirator Use Form

"Freedom from Danger"

Working over Water

1.0 Purpose

1.1. This policy provides guidelines and recommendations for construction work carried out on, adjacent to or over water where hazard to personnel exists.

2.0 Scope

2.1. This policy applies to all BNB projects where personnel are potentially exposed to hazards while working over water.

3.0 Responsibility

3.1 Project Management

- 3.1.1. BNB Project Management & Supervision are responsible for conducting a preconstruction risk assessment to identify work tasks that may be adjacent to or over water where hazards to personnel exists. Control measures must be identified and followed up with to ensure implementation in the field. It is the responsibility of BNB Project Management & Supervision to ensure that these conditions are satisfied to prevent unprotected working over water.
- 3.1.2. It is the responsibility of BNB Project Management & Supervision to ensure that personnel potentially exposed to working over water have and follow an adequate Site-Specific Working over Water Plan (WOW Plan). Submittals that must be received and reviewed by BNB Project Management & Supervision consist of:
 - 3.1.2.1. Site-Specific Working over Water Plan
 - 3.1.2.1.1. Job/Activity Hazard Analysis (JHA)
 - 3.1.2.1.2. Pre-Task Plan (PTP)
 - 3.1.2.1.3. Competent Person
 - 3.1.2.1.4. Responsibilities
 - 3.1.2.1.5. Rescue equipment and procedures
 - 3.1.2.1.6. Lifesaving equipment to be used
 - 3.1.2.1.7. Fall protection measures
 - 3.1.2.1.8. Proof of training on:
 - 3.1.2.1.8.1. The employer's safety programs and procedures
 - 3.1.2.1.8.2. Fall awareness for working over water
 - 3.1.2.1.8.3. Equipment to be used (use, installation, maintenance, storage, etc.)
 - 3.1.2.1.8.4. Competent person
 - 3.1.2.1.8.5. OSHA 30
 - 3.1.2.1.8.6. CPR and First Aid
 - 3.1.2.1.8.7. Site-specific hazards
 - 3.1.2.1.8.8. Rescue equipment and procedures
 - 3.1.2.1.8.9. Lifesaving and personal protective equipment
 - 3.1.2.2. Lastly, BNB Project Management & Supervision must "inspect what we expect" by monitoring field conditions to ensure that Working over Water Plans are adequate and appropriately followed.

3.2 Workers

Health, Safety and Environmental Manual

"Freedom from Danger"

3.2.1. Workers engaged in working over water are responsible for following their employer's safety program, procedures, and WOW Plan. Foremen are responsible for ensuring JHAs and daily pre-task plans are conducted, understood, and followed by their crew members. Competent persons are responsible for ensuring that their WOW Plan is adequate, amended as needed, communicated, and followed by crew members.

4.0 Definitions

- 4.1. **Barge** An unpowered, flat bottom, shallow draft vessel including scows, car floats and lighters. For purposes of this section, the term does not include ship shaped or deep draft barges.
- 4.2. Body harness Straps which may be secured about the employee in a manner that will distribute the fall arrest forces over at least the thighs, shoulders, chest and pelvis with means for attaching it to other components of a personal fall arrest system.
- 4.3. **Bulwark –** The side of a ship above the upper deck.
- 4.4. **Coamings -** A raised border around an opening in a deck, roof, or floor, designed to prevent water from running below.
- 4.5. **Competent Person** Purposes of this part means a person who is capable of recognizing and evaluating employee exposure to hazardous substances or to other unsafe conditions and is capable of specifying the necessary protection and precautions to be taken to ensure the safety of employees as required by the particular regulation under the condition to which it applies.
- 4.6. **Gangway** Any ramp-like or stair-like means of access provided to enable personnel to board or leave a vessel including accommodation ladders, gangplanks and brows.
- 4.7. **Gunwale** The upper edge of the side or bulwark of a vessel.
- 4.8. **Jacob's ladders** A hanging ladder having ropes or chains supporting wooden or metal rungs or steps.
- 4.9. **Lifeline** A component consisting of a flexible line for connection to an anchorage at one end to hang vertically (vertical lifeline), or for connection to anchorages at both ends to stretch horizontally (horizontal lifeline), and which serves as a means for connecting other components of a personal fall arrest system to the anchorage.
- 4.10. Lower levels Those areas or surfaces to which an employee can fall. Such areas or surfaces include but are not limited to ground levels, floors, ramps, tanks, materials, water, excavations, pits, vessels, structures, or portions thereof.
- 4.11. Personal fall arrest system a system used to arrest an employee in a fall from a working level. It consists of an anchorage, connectors, body belt or body harness and may include a lanyard, a deceleration device, a lifeline, or a suitable combination of these. As of January 1, 1998, the use of a body belt for fall arrest is prohibited.
- 4.12. Positioning device system A body belt or body harness system rigged to allow an employee to be supported at an elevated vertical surface, such as a wall or window, and to be able to work with both hands free while leaning.
- 4.13. **Qualified person** A person who by possession of a recognized degree or certificate of professional standing, or who, by extensive knowledge, training, and experience, has successfully demonstrated the ability to solve or resolve problems related to the subject matter and work.
- 4.14. Restraint (tether) line A line from an anchorage, or between anchorages, to which the employee is secured in such a way as to prevent the employee from walking or falling off an elevated work surface. Note: A restraint line is not necessarily designed to withstand forces resulting from a fall.
- 4.15. **Rope grab** A deceleration device which travels on a lifeline and automatically, by friction, engages the lifeline and locks so as to arrest the fall of an employee. A rope grab usually employs the principle of inertial locking, cam/level locking or both.
- 4.16. **Skiff** A flat-bottomed open boat of shallow draft, having a pointed bow and a square stern and propelled by oars, sail, or motor.
- 4.17. Vessel Every description of watercraft or other artificial contrivance used, or capable of being used, as a means of transportation on water, including special purpose floating structures not primarily designed for or used as a means of transportation on water.

5.0 Procedure

5.1 Protection against drowning



"Freedom from Danger"

- 5.1.1. When work is being carried out in an exposed position where there is a foreseeable risk of falling into water and it is impracticable to provide guardrails at the edges over water, personnel must wear a lifejacket or use a buoyancy aid. Rescue equipment should be provided.
- 5.1.2. Guardrails and toeboards should be installed at edges where persons are liable to fall from height or into water. The guardrails should have adequate strength and should be securely fixed to a height between 39-45 inches above the ground or floor.
- 5.1.3. A minimum of two workers is required for operations when water is entered.

5.1.4 Elevated Work Platforms

5.1.4.1. The design, construction, and use of elevated work platforms should comply with Scaffolds. Every edge of an elevated work platform from which a person might fall into water should be guard railed.

5.1.5 Mobile Equipment

- 5.1.5.1. If equipment is used on a site near water, concrete barricades should be installed at the water's leading edges whenever practicable.
- 5.1.5.2. During earth filling work (e.g. reclamation work) in which installation of concrete barricades is impracticable, equipment should not get near the edge of a temporary earth slope. The distance between any wheel of the equipment and the edge of the slope should not be less than ten feet. The fill materials deposited by the equipment should be spread and compacted by crawler track-mounted equipment, such as a bulldozer.
- 5.1.5.3. When crawler track-mounted equipment works at the edge of a permanent slope, overhanging of any part of the crawler track should not be permitted.
- 5.1.5.4. When operating aerial work platforms near or over water, lift occupants are not required to tie off because in the event that an error occurred that resulted in the employees being in the water, being tied-off would exacerbate the drowning hazard.

5.1.6 Concrete Barricades

5.1.6.1. When concrete barricades are required, they should be substantially constructed to a height at least 42 inches above the working surface, at a distance of at least ten feet from the edge near water.

5.1.7 Edges over water (i.e., leading edges, wall/floor openings, unprotected edges)

5.1.7.1. Every edge over water where a person is liable to fall from height or into water, should be provided with guardrails and toeboards. Please reference Walking and Working Surfaces and Fall Protection for additional information.

5.1.8 Safety Nets

- 5.1.8.1. Provisions to eliminate the risk of falling should always be the first consideration. However, if this is not practicable, use of suitable and adequate safety nets, harnesses, and lanyards attached continuously to a suitable and secure anchorage should be considered.
- 5.1.8.2. A safety net should be installed as close as possible to the working level and in compliance with the level specified by the manufacturer. Manufacturer's recommended procedures must be followed for assembly and disassembly.

5.1.9 Safe means of access and egress



"Freedom from Danger"

- 5.1.9.1. Every means of access and egress should be kept safe. Every edge from which a person might fall from height or into water should be provided with guardrails and toeboards. The means of access and egress should also be clear of any cargo lifting area and so located that no suspended load passes over it.
- 5.1.9.2. Every opening affecting safe use of the means of access and egress should either be fenced or be securely covered. If a means of access has been rendered unsafe for any reason, a controlled access zone must be established (i.e., physical barriers should be erected and warning notices prohibiting its use should be posted at every approach).
- 5.1.9.3. The means of access and egress and its immediate approaches should have non-slippery surfaces and should so far as is reasonably practicable be gritted. It should be kept free from any slippery material, obstruction or hazard caused by projecting fixtures or fittings. If such fixtures or fittings cannot be removed immediately, it should be suitably fenced off, painted or marked to alert users of the access and egress.
- 5.1.9.4. The means of access and egress should be kept in position as long as it is required. It should be well lit and properly maintained. At least two satisfactory means of escape should be available for use in an emergency.

5.1.10 Access to and from Vessels, Wharves, Floats, Barges, and/or Boats

- 5.1.10.1. Ramps for access of vehicles to or between barges shall be of adequate strength, provided with side boards, well maintained, and properly secured.
- 5.1.10.2. Unless employees can step safely to or from the wharf, float, barge, or river towboat, either a ramp or a safe walkway shall be provided.
- 5.1.10.3. When dredge discharge pipelines are used as walkways, they shall be provided with a flat surface walkway at least 12 inches wide, anchored to the pipeline to prevent displacement. A railing providing at least a single rail or taut rope 42 to 45 inches high shall be provided along one side. When rope is used, it shall be at least as strong as 3/4-inch diameter Manila or at least 3/8-inch diameter wire rope, or equivalent.
- 5.1.10.4. Catwalks or platforms shall be at least 20 inches wide with railings provided at all locations over bodies of water more than 4 feet deep. Planks for such use at those locations subject to immersion shall be rough sawn and treated to resist rot. Railings shall be installed.
- 5.1.10.5. When the upper end of the means of access rests on or is flush with the top of the bulwark, substantial steps properly secured and equipped with at least one substantial hand rail not less than thirty-four (34) inches or more than thirty-eight (38) inches above the tread nosing shall be provided between the top of the bulwark and the deck.
- 5.1.10.6. Obstructions shall not be laid on or across the gangway, ramp, catwalk or other means of access. The means of access shall be adequately illuminated for its full length.
- 5.1.10.7. Jacob's ladders shall be of the double rung or flat tread type. They shall be well maintained and properly secured. A Jacob's ladder shall either hang without slack or be pulled up entirely.

5.1.11 Working Surfaces of Barges

- 5.1.11.1. Employees shall not be permitted to walk along the sides of barges with coamings more than 5 feet high unless there is a 3-foot clear walkway or a grab or a taut hand line is provided.
- 5.1.11.2. Decks and other working surfaces shall be maintained in a safe condition.
- 5.1.11.3. Employees shall not be permitted to pass fore and aft, or over, or around deck loads, nor shall employees be permitted to walk over deck loads from rail to coaming, unless there is a safe passage.

Health, Safety and Environmental Manual

"Freedom from Danger"

5.1.11.4. If it is necessary for an employee to stand at the outboard or inboard edge of the deck load where less than 36 inches of bulwark, rail, coaming, or other protection exists, the employee shall be provided with a suitable means of protection against falling from the deck load.

5.1.12 Rescue Procedures

- 5.1.12.1. A rescue team should be organized to deal with emergency situations, such as incidents. Every member of the team should be trained in rescue and emergency procedures. At least one of the members should be certified in CPR and First Aid.
- 5.1.12.2. First aid supplies, a stretcher, and a portable AED should be provided and kept readily accessible for emergency use.
- 5.1.12.3. Notices in English and the predominant language should be posted in prominent positions, especially at edges near water, stating the following:

5.1.12.3.1.	the locations and types of the rescue and life-saving equipment;
5.1.12.3.2.	the location of the room, if any, for treatment of injuries;
5.1.12.3.3.	the names of members of the rescue team; and
5.1.12.3.4.	the means of communication.

5.1.13 Emergency procedure

5.1.13.1. Emergency procedures should be identified in <u>BNB's Crisis Management Program</u> and the WOW plan.

5.1.13.2. The procedures should be expressed clearly in writing and should at least include the following:

5.1.13.2.1.	sounding the alarm for emergency including calling the police by dialing '911';
5.1.13.2.2.	activating the rescue team;
5.1.13.2.3.	dealing with emergency situations;
5.1.13.2.4.	providing and using emergency and first aid facilities;
5.1.13.2.5.	stating routes for rescue operation if necessary; and
5.1.13.2.6.	sending rescued persons to hospital for medical treatment due to immersion in
water (p	possibly polluted) or injury.

- 5.1.13.2.7. BNB's Crisis Management Plan and the WOW plan's emergency procedures should be posted in prominent locations.
- 5.1.13.2.8. All personnel should be trained on the emergency procedures. Drills and practices should be held regularly so as to ensure that all personnel are familiar with the emergency procedures.
- 5.1.13.2.9. The emergency procedures should be updated regularly so as to suit the progress of construction work. Drills and practices held can also help to identify the areas of weakness for improvement.

5.1.14 Rescue equipment

- 5.1.14.1. The following safety devices shall be provided for and used by employees at those locations where the danger of drowning exists. EXCEPTION: Where employees are 100% protected by railings, nets, personal fall arrest, etc.
- 5.1.14.2. Employees shall be required to wear U. S. Coast Guard approved personal flotation devices that are marked or labeled Type I PFD, Type II PFD, or Type III PFD, or a U.S. Coast



"Freedom from Danger"

- Guard approved Type V PFD that is marked or labeled for use as a work vest for commercial use or for use on vessels.
- 5.1.14.3. U. S. Coast Guard approved 30-inch ring buoys with at least 150 feet of 600-pound capacity line shall be readily available for emergency rescue operations. Distance between ring buoys shall not exceed 200 feet.
- 5.1.14.4. One or more lifesaving boats, either manually or power-operated, shall be provided and readily accessible at all times. Lifesaving boats shall be properly maintained, ready for emergency use and equipped with oars and oarlocks attached to the gunwales, boathook, anchor, ring buoy with 50 feet of 600-pound capacity line and two life preservers. Oars are not required on boats that are powered by an inboard motor.
- 5.1.14.5. Where, because of swift current, lifeboats cannot be used, a line shall be stretched across the stream with tag lines or floating planks trailing in the water at intervals not to exceed 6 feet. If this is impracticable, some other arrangement for providing effective lifelines near the water surface shall be provided.
- 5.1.14.6. The employer shall ensure that there is in the vicinity of each barge in use at least one portable or fixed ladder which will reach from the top of the apron to the surface of the water. If the above equipment is not available at the pier, the employer shall furnish it during the time that the barge is in use.
- 5.1.14.7. All items of rescue equipment provided should be checked daily so as to ensure that they are in their proper locations and in good serviceable condition. All personnel should be informed of the functions and limitations of each item of equipment and be trained on how to use it properly.
- 5.1.14.8. Buoyant lifelines should be fiber ropes made of polypropylene with nominal diameter not less than 5/16" (8mm).
- 5.1.14.9. Grab lines should be provided where practicable, for the purpose of giving a person in water something to grab onto in emergency. The grab line provided should be of buoyant type and of sufficient length to accommodate high and low tides. A marker float at the free end of the grab line should be provided and trailing ends of undue length should be avoided so as to prevent the boats nearby from coming in contact with the grab line.
- 5.1.14.10. Lifebuoys, each fitted with a buoyant lifeline should be set at suitable locations but not exceeding 165 feet (50m) intervals along the edges over water where work is being carried out. Each buoyant lifeline should be knotted at every 10 feet (3m) to assist handhold and have a length of about 100 feet (30m).
- 5.1.14.11. The lifebuoys should be constructed of either cork with canvas covering, or of polyurethane foam with a rigid PVC cover. It is normally of 30 inches (760mm) outside diameter and 18 inches (455mm) inside diameter. For night work, a self-activating light should be fitted to it.
- 5.1.14.12. Rescue lines should be provided where practicable. Each rescue line should at least consist of a buoyant lifeline and a floatation device. Throwing the device out to a person in water can allow the person to grab the lifeline and he/she can be hauled to safety.
- 5.1.14.13. To achieve the best result, a lifebuoy or rescue line should be thrown as near as possible to a person in the water. If a tide is running, it should be thrown on the upstream side.
- 5.1.14.14. At least one rescue boat should be provided and kept ready for immediate use whenever personnel are employed to work over or adjacent to turbulent or tidal water where rescue of them would have to be carried out by boat. The rescue boat may be a rigid or an inflatable vessel. It should be properly maintained so that it is operational at any time and in good condition.
- 5.1.14.15. The rescue boat should be power-driven with a fixed self-starting engine. Effective two-way radio communication should be set up between the rescue boat and the management on the shore. If night work is to be carried out, a powerful swivel-mounted spotlight should be installed on the rescue boat so that any person fallen into water can be spotted easily.



"Freedom from Danger"

- 5.1.14.16. The rescue boat should be fitted with grab lines and provided with at least one lifebuoy fitted with a minimum 50 feet (15m) long buoyant lifeline. For a large rescue boat, it should also be provided with an overside boarding ladder or equivalent means to help rescue any unconscious person from the water.
- 5.1.14.17. The rescue boat should be marked clearly to show its intended use and it should not be permitted to use as a working vessel or an ordinary means of transport. First aid equipment including a bulb syringe for clearing a person's airway and blankets for covering the rescued person should be provided. The first aid equipment should be suitably protected from getting wet.
- 5.1.14.18. The rescue boat should be manned by competent boatmen who should be trained in rescue and emergency procedures and should have completed a course in CPR/first aid. The boatmen should be competent in swimming, and they should be at least equipped with buoyancy aids while they are patrolling on board. So far as is reasonably practicable, there should be at least two boatmen on a rescue boat so that one is always free to rescue the person in water.

5.2 Hazards

5.2.1. The following is a list of construction scopes where water may be a potential hazard:

- 5.2.1.1. Bridge building
- 5.2.1.2. Marine works (i.e., wharfs, barges, decks, etc.)
- 5.2.1.3. Machinery or pipework installations over water
- 5.2.1.4. Dams, dykes, retaining walls, etc.

5.2.2. "Water" does not have to be just seawater, either. It can include any work on, over, or adjacent to:

- 5.2.2.1. Rivers or streams
- 5.2.2.2. Lakes or lagoons
- 5.2.2.3. Water storage areas
- 5.2.2.4. Sewage processing plants and pipelines
- 5.2.2.5. Sediment ponds
- 5.2.2.6. Etc.
- 5.2.3. The one major hazard involved in any of these examples is the possibility of a fall into the water, and drowning. Work on wastewater systems or locations (i.e., sewage plants, outlets, etc.) also presents health hazards which must be recognized.
 - 5.2.3.1. Work over stagnant water, sewage ponds, or in fact any contaminated water, presents special hazards. Should it be necessary, personnel will be inoculated against the several diseases which can be prevalent in these conditions, before starting on the job. ANY injury where the skin is broken, no matter how slight, MUST be treated with disinfectant immediately. Water quality even in rivers cannot be guaranteed.
 - 5.2.3.2. Hazards also exist in the use of machinery on barges, wharfs, decks, etc. where stability becomes a major issue. A barge (unless it is a jack-up type) makes an unstable base, especially when operating machinery. Be careful of loading, and watch weight distribution. In these conditions, personnel MUST be aware of the hazards created with water swell.
 - 5.2.3.3. Working on any site will usually involve wearing a tool belt and often heavy clothing, all of which will weigh a person down and make getting back to the surface very difficult.



Health, Safety and Environmental Manual

"Freedom from Danger"

- 5.2.3.4. Several areas along the coast have large tidal rises and falls. This can mean a carefully planned work sequence is needed to ensure that nobody gets trapped by a rising tide. NOAA (National Oceanic and Atmospheric Administration), local newspapers, etc. have detailed tide tables.
- 5.2.3.5. Especially at rivers and earth-bank canals, erosion can create hazards by undercutting and washing away the banks. What may have been a safe working area one day, could be hazardous after overnight rain.
- 5.2.3.6. Heavy rain in the catchment/basin area of a river can lead to river levels rising suddenly, and the water flow speeding up dramatically. This can apply quite some distance from the rain area, and with little warning.
- 5.2.3.7. (This can also affect falsework, scaffolding and temporary structures!)
- 5.2.3.8. Working alongside or over sea water can expose personnel and their equipment to the effects of salt spray. This can have a serious effect on skin and clothing, metal tools, and especially electrical equipment. Skin care is essential, as is clean and dry clothing and footwear.
- 5.2.3.9. Tools and metal items will need regular cleaning, and protection with a spray such as WD40 or similar lubricant. Salt can severely corrode and rust metals.
- 5.2.3.10. Tidal surges and boat wakes can create trapping hazards when working on barges or working platforms alongside piles, wharves, fixed access ladders, etc.
- 5.2.3.11. Any work where water and electricity have the potential to mix, require careful planning and operation.
- 5.2.3.12. The power supply to the job will have been determined to provide the safest possible conditions, and personnel MUST use any protective systems provided such as ground fault circuit interrupter, etc. Pay special attention to cord insulation and wrap cord connections with a waterproofing medium.
- 5.2.3.13. Use a tether device with power tools to stop them from falling into the water if they are dropped. NEVER use a power tool near any breaking waves.
- 5.2.3.14. Personnel must be aware that working over water can make footing slippery and hazardous. Be prepared for these conditions and ensure that personnel are always using the necessary safety equipment.
- 5.2.4. Potentially hazardous or unfavorable site conditions which will likely affect the safety of the workplace should be considered in the planning and design of the construction project.

5.2.4.1. These may include the following:

- 5.2.4.1.1. sites with strong tides, winds or waves;
- 5.2.4.1.2. sites which are too remote from the city center or hospitals;
- 5.2.4.1.3. sites which have restricted space for maneuvering, such as those for temporary storage;
- 5.2.4.1.4. the activities of other contractors including sub-contractors within the sites;
- 5.2.4.1.5. adjacent maritime activities; and
- 5.2.4.1.6. emission of noise, toxic gases, harmful chemicals or dust from processes on or around the sites.
- 5.2.5. Weather conditions that could have an adverse effect on the work over water include rain, high wind or typhoon, and those causing poor visibility, such as fog, marine layer, mist or glare.

5.3 Personal Protective Equipment



Health, Safety and Environmental Manual

"Freedom from Danger"

- 5.3.1. Life vests are required when personnel are within six feet of the water's edge except when 100% fall protection is in place (i.e., guardrails, personal fall arrest systems, etc.) or when personnel are inside of equipment/machinery.
- 5.3.2. Footwear with non-slippery soles should be worn while at work near water.
- 5.3.3. Employees working over or near water, where the danger of drowning exists, shall be provided with U.S. Coast Guard-approved life jacket or buoyant work vests. Prior to and after each use, the buoyant work vests or life preservers shall be inspected for defects which would alter their strength or buoyancy. Defective units shall not be used.
- 5.3.4. Personnel who have a foreseeable risk of falling into water should wear a lifejacket. Buoyancy aids are considerably inferior in performance to lifejackets. Use of a buoyancy aid will only be appropriate if the wearer is a proficient swimmer working close to the shore and he/she will unlikely be incapacitated by the environment. Instructions on the suitability of the equipment for specific situations should be sought from the manufacturers.
- 5.3.5. A lifejacket or buoyancy aid should fit the wearer and should allow the wearer freedom in action and movement. It should not unduly restrict his/her vision, hearing or breathing, nor contain any component causing injury to the wearer in normal use.
- 5.3.6. The lifejacket or buoyancy aid should have distinctive and easily visible color. Retro-reflective material should also be affixed on its surface which is normally above the water when it is in use. Its protective cover should be made of robust material which is resistant to abrasion, puncture and molten metal splash.
- 5.3.7. The lifejacket or buoyancy aid should preferably be provided with a whistle (for day work) and/or a self-activating light (for night work) which can aid in locating the wearer to facilitate rescuing.
- 5.3.8. The lifejacket or buoyancy aid should be properly maintained in a good serviceable condition. Prior to and after each use, it should be checked by the user for defect which might alter its strength or buoyancy. Any defect observed should be reported to the appropriate supervisor. Defective units should not be used.

5.4 Training

5.4.1. All employees who are placed in a work situation where there is potential exposure to working over water must be trained on the PTP / JHA related to the work. Employees must have also gone through the Site-SpecificOrientation.

6.0 References

FED/OSHA 29 CFR 1926.106 Subpart E - Personal Protective and Life Saving Equipment

7.0 Attachments

<u>JHA</u>

Pre-Task Plan

Fall Protection Work Plan



Attachments



HIGH-LIFT POLICY

Eode #	Oper-19A
Rev.	0
Date	June-2018
Original Date	June-2018

Aerial Work Platform (Scissor Lift/Boom Lift) Inspection	Aerial	Work	Platform	(Scissor	Lift/Boom	Lift)	Inspection
--	--------	------	----------	----------	-----------	-------	------------

Company Name	Contact Number
Type of Lift	Model or Equip Number

DATE		MON	TUE	WED	THU	FRI	SAT	SUN
Initia	ds of person performing inspection		1					
Has t	he operator been instructed in the safe operation of this type of lift?	YVN	YAN	Y/N	Y7N	Y/N	YIN	Y/N
	ection Item & Description Fail Status	P/F	P/F	P/F	P/F	P/F	P/F	P/F
1	Operating and emergency controls are in proper working condition EMO button or Emergency Stop Device.						1	
2	Upper drive control interlock mechanism is functional (i.e., foot- pedal, spring lock, or two hand controls).			7				
3	Emergency lowering function operates properly							
4	Lower operating controls successfully over-ride the upper controls.		E	E = 3				
3	Both upper and lower controls are adequately protected from inadvertent operation.	1						
6	Control panel is clean & all buttons/switches are clearly visible (no fire proofing, paint over spray, etc.)			= =	= =			
7	All switch & mechanical guards are in good condition and properly installed.							
- 8	All Safety Indicator lights work.		Y	Y = =				
9	Drive controls function properly & accurately labeled (up, down, right, left, forward, back).							
10	Motion alarms are functional.							
-11	Safety decals are in place and readable.		-	5				
12	All guardrails are sound and in place, including basket chains,		t	2 - =	= =			
13	Work platform & extension slides are clean, dry, & clear of debris.		7	25 3				
14	Work platform extension slides in and out freely with safety locking pins in place to lock setting on models with extension platforms.	EI	Jeni Jeni Jeni Jeni Jeni Jeni Jeni Jeni	-			$\equiv 1$	
15	Inspect for defects such as cracked welds, fuel leaks, hydrautic leaks, damaged control cables or wire harness, etc.		7 = 1					
16	Tires and wheels are in good condition, with adequate air pressure if pneumatic.		TIT!	T I	E			
17	Braking devices are operating properly.		$\rangle = i$	72.3				
18	The manufacturer's operations manual is stored on unit.							

Workplace Assessment

Survey work area for potential hazardous operating conditions prior to use of lift. Ensure all the hazards identified are addressed in pre task planning with sufficient strategies to mitigate the hazards and or risks			Are Conditions Present					
Floor conditions: Drop offs, holes, uneven surfaces, sloped floors, etc.	0	-0	0	0	0	0	0	
Housekeeping: debris, floor obstructions, cords, construction material/ supplies, etc.	0	0	0	0	0	0	0	
Hazardous Energy: Electrical power cables or panels, chemical lines, gas lines, drain lines, utilities, etc.	o.	0	0	O	o	0	0	
Overhead obstructions; tight working conditions, adjacent structures, pipe racks, ceiling grids, etc.	0	0	Ö	0	0	0	Ó	



Alternative Methods Documentation Form

-	Cod: Op	er-9C
	Rev.0	Dec-18

Use with Chapter 296-809 WAC, Confined Spaces

Location of the Space			
Entry Date:	Entry Duration:		
List of Entrants			
			-
List of Physical Hazards in the space	List of (Potential or Actual) Atm space	ospheric Haza	ards in the
List each action taken to eliminate	physical and atmospheric hazard	ls in the space	
Action:	Description:		
	Ventilation		
Is forced air ventilation required?		1	
If "Yes", specify the type of ventilation (I.E. Local exhaust). Are multiple units required?	Amount of ventilation (CFM or A	YES AC/Hr)	NO
	Air Monitoring		

B	N	B
BWI	(u)	ers

Alternative Methods Documentation Form

7	Cod: Op	er-9C
١	Rev.0	Dec-18

Substance Monitored:	Unit:	Unit: Permissible Levels:		Monitoring Results:		
				Initial Test:	Peak Reading During Entry:	
Instruments used for Model Number or T			Calibration	Calibratio	on Check	
Additional Notes abo	ut the space an	d entry (including wh	nether evacuatio	on was necess	ary)	
Person Responsible	for Ensuring t	he Space is Safe to	Enter:			
Name: Job Title:			itle:			
Signature:		2				

ASSURED GROUNDING POLICY

Project:	
Electrical sub responsible:	
Competent Person:	

The person above shall be designated as the competent person, pursuant to WAC 296-155-447. This person shall be capable of identifying hazards relating to grounding and shall have the authority to see that any corrections are made. The procedure described is suitable for compliance with the requirements of WAC 296-155-447. It is BNB's to establish and implement an Assured Grounding Conductor Program to test for continuous circuitry on:

- (a) Cord sets and receptacles NOT a part of the permanent wiring of buildings or structures.
- (b) All electrical equipment and tools used in processes of construction or alterations.

POLICY

Ground Fault Circuit Interrupters (GFCI) are required by the codes for all 120 volt, single phase, 15-20 ampere receptacle outlets which are not a part of the permanent wiring of a building on a construction project. As an alternative to the Ground Fault Circuit Interrupter requirement, it will be the policy of the BNBuilders to instruct employees **NOT** to use any equipment that does not meet the requirements of the Assured Grounding Program.

PROCEDURE

All equipment to be used shall be tested, identified and coded using the following procedures, with the exception of the "double insulated" system, which need not be tested.

TESTING

- All equipment shall be tested before first use for grounding and continuity of the circuitry.
- Equipment returned to service following repairs shall be tested for continuity before being used.
- Tests shall be done quarterly, at intervals not exceeding one every three months.
- Tested equipment shall be identified by use of color-coding. Two (2) colors shall be used. First color
 to identify the quarter and the second to identify the month within the quarter.
- Equipment shall be visually inspected before use each day for external defects, including deformed or missing pins, insulation damage and indication of possible internal damage. Equipment shall not be used until repaired, retested and recorded.

RECORDING

The tests shall be recorded on the safety inspections scheduled and retained at the jobsite!

EMPLOYER CP___

1st Quarter - White - White/Yellow /Blue

2nd Quarter – Green - Green/Yellow /Blue

3rd Quarter - Red - Red/Yellow/Blue

4th Quarter - Orange - Orange/Yellow/Blue

ASSURED GROUNDING COLOR CODING SCHEME

Month/ Quarter	Quarterly	Monthly
JANUARY	WHITE	WHITE
FEBRUARY		YELLOW
MARCH		BLUE
APRIL	GREEN	GREEN
MAY		YELLOW
JUNE		BLUE
JULY	RED	RED
AUGUST		YELLOW
SEPTEMBER		BLUE
OCTOBER	ORANGE	ORANGE
NOVEMBER		YELLÓW
DECEMBER		BLUE

Assured Grounding Program

Policy:

Ground Fault Circuit Interrupters (GFCI) are required by the captioned codes for all 120 volt, single phase, 15-20 ampere receptacle outlets which are not a part of the permanent wiring of a building or structure of/ or on a construction project. As an alternative to the Ground Fault Circuit Interrupter requirement, it will be the policy of the undersigned to instruct employees **not** to use any equipment that does not meet the requirements of the Assured Grounding Program.

Procedure:

All equipment to be used on the construction site shall be tested, identified and coded using the following procedures, with the exception of the "double insulated" system, which need not be tested.

Testing:

- ☑ All Equipment shall be tested before first use for grounding and continuity of the circuitry.
- ☑ Equipment returned to service following repairs shall be tested for the continuity before being used.
- ☑ Tests shall be done quarterly, at intervals not exceeding one every three months.
- ✓ Tested equipment shall be identified by way of color-coding. Two (2) colors shall be used. First color to identify the quarter and the second to identify the month within the quarter.
- ☑ Equipment shall be visually inspected before use each day for external defects, including deformed or missing pins, insulation damage and indication of possible internal damage. Equipment shall not be used until repaired, re-tested and results recorded.

All tests shall be recorded and attached to the site-specific schedule and retained at the job site.

ASSURED EQUIPMENT GROUNDING CONDUCTOR PROGRAM TRACKING FORM

COMPANY NAME:_				
COMPETENT PERS	ON:			
JOB NAME OR NUM	IBER			
				_
LOCATION	DATE TESTED	ACTION, IF ANY	REASON- A-B-C-D	TESTED BY CP

*REASON FOR TEST:	A.	BEFORE FIRST USE.

- B. BEFORE EQUIPMENT IS RETURNED TO SERVICE FOLLOWING ANY REPAIRS
- C. MONTHLY INSPECTION OR AFTER INCIDENT
- D. QUARTERLY TESTING/INSPECTION

COMPANY AUTHORIZED SIGNATURE:

DIND		CONFINED SPA	CE ENTRY PE	RMIT			Cod: Oper-9B	
SHEGHERY.			27.7				Rev.1	Dec-18
Company			Project			Date		0 . =
	Confined Space			7.6		Time		
ntry Superv						Signature		
	ant(s) Name(s)							
Authorized E	ntrant(s) Name(s)							
	If 'NO' to all questions	n Step 1 (below), ti		ie entered using the	Alternate	Entry Procedure	s (Sign below)	
Vame			Signature					
	- KARA-		STLP 1 - IDU	NTIEV HAZAROS				
	HAZARD		YES	NO	1	HAZARD	YES	NO
Hazardous Al	tmosphere (including	the potential)			Pre-Oper	ning Hazards		
sloping or co	nverging walls or floor	S			2 /	oles / Fire		
ngulfment /	Entrapment				Toxic Ga	ses / Corrosive	## = ##	
Any other ser	rious safety hazard				Hazardo	us Energy		
Type of serio	us hazard			1	Conditio	ns Outside		
VES' to THE	question in section A (al	nount the senses our	et he elsewhied	SE DEPART		lling Objects		
	question in section A (a) her serious safety hazar				Lighting .			
	ely to occur if specific co			A DESCRIPTION OF THE PROPERTY		Il Hazards		
and the second second second	and the street of				Other			
			STEF 2-10EN	ITIFY CONTROLS				
	PRE-ENTRY AIR TES	ring	PR	OCEDURE	DONE	PROCE	DURE	DONE
GAS	ACCEPTABLE	READING	Pre-Entry 0	hecklist		Lighting / Hear		()
Oxygen	19.5-23.5%		Oxygen Pre-	Entry Reading		Thermal Prote	ction	
LEL	<10%		Chemical C	leanout Electrical		Hydraulic Prote	ection	
Toxics	<pel td="" tlv<=""><td></td><td>Ventilation</td><td>Purge Time</td><td></td><td>Radiation Prot</td><td>ection</td><td></td></pel>		Ventilation	Purge Time		Radiation Prot	ection	
Other			Lock out/1	ag out		Traffic Control /	Barricading	
Date of last c	alibration		Mechanica	lisolation		Pneumatic Isol	ation	
Test Instrum	ent and #		Fall Protect	tion		Hot Work		
		5111	S JULINTIEY F	COLURED EQUIPA	MEIVT		No. of Concession, Name of Street, or other Persons, Name of Street, or ot	
EC	QUIPMENT	REQU	IRED	EQUIPM	ENT		REQUIRED	
Ventilator				PPE				
Kenthator				Body Prote	ection			
Respirator				Hearing pro	tection			
	Monitor			Spark-proo	ftools			
Respirator								
Respirator Atmospheric				Ladder/ Safe				
Respirator Atmospheric Blocking devi Harness					access			
Respirator Atmospheric Blocking devi Harness	rgency Escape			Ladder/ Safe	access uisher			
Respirator Atmospheric Blocking devi Harness Fripod - Eme Ground Fault	rgency Escape			Ladder/ Safe Fire Exting	access uisher			
Respirator Atmospheric Blocking devi Harness Fripod - Eme Ground Fault	rgency Escape Provided	STEP 4 - VERIEY	ACCEPTABLE (Ladder/ Safe Fire Exting Lightin	e access uisher ng	PLACE		
Respirator Atmospheric Blocking devi Harness Fripod - Eme Ground Fault	rgency Escape Provided	STEP 4 - VERIEYV	ACCLI TABLL E	Ladder/ Safe Fire Exting Lightin Othe	e access uisher ng r vs age in	PLACI UIPMENT		T DONE
Respirator Atmospheric Blocking devi Harness Fripod - Eme Ground Fault ntrinsically s	rgency Escape Provided afe radio / phone			Ladder/ Safe Fire Exting Lightin Othe NTRY CONDITION	e access uisher IB r VS ARE IN EQI	UIPMENT		DONE
Respirator Atmospheric Blocking devi Harness Fripod - Eme Ground Fault Intrinsically s Review Perm	rgency Escape Provided afe radio / phone ACTION			Ladder/ Safe Fire Exting Lightin Othe	e access uisher Ig r VS ARE IN EQ	UIPMENT		DONE
Respirator Atmospheric Blocking devi Harness Fripod - Eme Ground Fault Intrinsically s Review Permit	rgency Escape Provided afe radio / phone ACTION it with Attendant and	Entrant		Ladder/ Safe Fire Exting Lightin Other OTHER CONDITION All Safety Equip MSDSs Review	e access uisher IB r VS ARIE IN EQI pment Avi ed	UIPMENT ailable		DONE
Respirator Atmospheric Blocking devi Harness Fripod - Eme Ground Fault Intrinsically s Review Permit Preparation /	rgency Escape Provided afe radio / phone ACTION at with Attendant and Posted at Portal Isolation Procedures	Entrant		Ladder/ Safe Fire Exting Lightin Other OTHER All Safety Equip MSDSs Review Pre-Opening H	e access uisher ug r VS ARIE IN EQ pment Ava ed azards Elia	UIPMENT ailable		DONE
Respirator Atmospheric Blocking devi Harness Fripod - Eme Bround Fault Intrinsically s Review Permit Preparation / Fraffic Contro	rgency Escape Provided afe radio / phone ACTION fit with Attendant and Posted at Portal Isolation Procedures of / Barricading Done	Entrant Done		Ladder/ Safe Fire Exting Lightin Othe NTRY CONDITION All Safety Equip MSDSs Review Pre-Opening H Employees Tas	e access uisher ug r NS ARE IN EQ pment Ava ed azards Elin k Trained	UIPMENT ailable minated		DONE
Respirator Atmospheric Blocking devi Harness Fripod - Emel Ground Fault Intrinsically s Review Permit Preparation / Fraffic Contro	rgency Escape Provided afe radio / phone ACTION fit with Attendant and Posted at Portal Isolation Procedures of / Barricading Done otrant Communication	Entrant Done		Ladder/ Safe Fire Exting Lightin Other Other All Safety Equit MSDSs Review Pre-Opening H Employees Tas Atmospheric To	e access uisher IIB VS ARIE IN EQI pment Avi ed azards Elii k Trained ests Satisf	uiPMENT ailable minated	Hazards	DONE
Respirator Atmospheric Blocking devi Harness Fripod - Emel Ground Fault Intrinsically s Review Permit Preparation / Fraffic Contro	rgency Escape Provided afe radio / phone ACTION fit with Attendant and Posted at Portal Isolation Procedures of / Barricading Done otrant Communication	Entrant Done Tested	DONE	Ladder/ Safe Fire Exting Lightin Other Other All Safety Equip MSDSs Review Pre-Opening H Employees Tas Atmospheric To	e access uisher NS ANE IN EQI pment Avi ed azards Eli k Trained ests Satisf s Free From	uiPMENT ailable minated factory Vapors and Other	Hazard5	DONE
Respirator Atmospheric Blocking devi Harness Fripod - Eme Ground Fault Intrinsically s Review Permit Preparation / Fraffic Contro Attendant/Er Emergency S	rgency Escape Provided afe radio / phone ACTION at with Attendant and Posted at Portal Isolation Procedures at / Barricading Done attrant Communication ervices	Entrant Done Tested STUP 5 - PERF	DONE	Ladder/ Safe Fire Exting Lightin Other Other All Safety Equip MSDSs Review Pre-Opening H Employees Tas Atmospheric To Surrounding Area:	e access uisher IB r VS ARE IN EQ pment Ava ed azards Elia k Trained ests Satisf s Free From	UIPMENT ailable minated factory Vapors and Other		
Respirator Atmospheric Blocking devi Harness Fripod - Eme Ground Fault Intrinsically s Review Permit Preparation / Fraffic Contro Attendant/Er Emergency S GAS	rgency Escape Provided afe radio / phone ACTION at with Attendant and Posted at Portal Isolation Procedures of / Barricading Done attrant Communication ervices ACCEPTABLE	Entrant Done Tested	DONE	Ladder/ Safe Fire Exting Lightin Other Other All Safety Equip MSDSs Review Pre-Opening H Employees Tas Atmospheric To Surrounding Area:	e access uisher IB r VS ARE IN EQ pment Ava ed azards Elia k Trained ests Satisf s Free From	uiPMENT ailable minated factory Vapors and Other	Hāžārds TIME	DONE
Respirator Atmospheric Blocking devi Harness Fripod - Eme Ground Fault Intrinsically s Review Permit Preparation / Fraffic Contro Attendant/Er Emergency S GAS Oxygen	rgency Escape Provided afe radio / phone ACTION it with Attendant and Posted at Portal Isolation Procedures of / Barricading Done ntrant Communication ervices ACCEPTABLE 19.5-23.5%	Entrant Done Tested STUP 5 - PERF	DONE	Ladder/ Safe Fire Exting Lightin Other Other All Safety Equip MSDSs Review Pre-Opening H Employees Tas Atmospheric To Surrounding Area:	e access uisher IB r VS ARE IN EQ pment Ava ed azards Elia k Trained ests Satisf s Free From	UIPMENT ailable minated factory Vapors and Other		
Respirator Atmospheric Blocking devi Harness Fripod - Eme Ground Fault Intrinsically s Review Permit Preparation / Fraffic Contro Attendant/Er Emergency S GAS Oxygen LEL	rgency Escape Provided afe radio / phone ACTION it with Attendant and Posted at Portal Isolation Procedures of / Barricading Done intrant Communication ervices ACCEPTABLE 19.5-23.5% <10%	Entrant Done Tested STUP 5 - PERF	DONE	Ladder/ Safe Fire Exting Lightin Other Other All Safety Equip MSDSs Review Pre-Opening H Employees Tas Atmospheric To Surrounding Area:	e access uisher IB r VS ARE IN EQ pment Ava ed azards Elia k Trained ests Satisf s Free From	UIPMENT ailable minated factory Vapors and Other		
Respirator Atmospheric Blocking devi Harness Fripod - Eme Ground Fault Intrinsically s Review Permit Preparation / Fraffic Contro Attendant/Er Emergency S GAS Oxygen	rgency Escape Provided afe radio / phone ACTION it with Attendant and Posted at Portal Isolation Procedures of / Barricading Done ntrant Communication ervices ACCEPTABLE 19.5-23.5%	Entrant Done Tested STUP 5 - PERF	DONE	Ladder/ Safe Fire Exting Lightin Other Other All Safety Equip MSDSs Review Pre-Opening H Employees Tas Atmospheric To Surrounding Area:	e access uisher IB r VS ARE IN EQ pment Ava ed azards Elia k Trained ests Satisf s Free From	UIPMENT ailable minated factory Vapors and Other		



CORE DRILLING/SAW CUTTING CHECKLIST

	AUTHORIZATION VALID FOR	ON	1	1	_ONLY.
	IDENTIFY LIVE UTILITY/PT CABLES				
ор	his core drilling/saw cutting checklist is required to be complete peration(s). Identify utilities in the area (Electrical, Sprinkler Supply itc.). Applicable Job Hazard Analysis (JHA) and/or Pre-Task Plan, m	, Gas, Water Supply, Sanita	ary/Sto	rm Sewe	r, Process Pipe
Pro	roject:				
Loc	ocate/Scanner Receipt/Ticket # Date Scanned:	I = I			
o	Has the core or saw cutting location been reviewed and appro	ved by the structural engin	neer or	architec	t?
	If available, have As-Builts and other drawings been reviewed	to determine utility/drop l	beam/F	.T. cable	locations?
	Has imaging been done by 3 rd party to locate P.T. cables and o ray/Other)	ther utilities (in house scar	nning o	nly is NO	IT allowed)? (GPR/
	Did BNB supervisor accompany scanner during scanning proce	55?			
П	Does imaging need to be conducted from the underside of slat	b? If so, did markings get !	transfe	red to th	ne top side?
u	Is penetration laid out the correct distance away from PT cable	e? (at least 3-inches away)			
	Is penetration the correct distance away from rebar? (1-inch a	way, or approval from eng	ineer t	o cut reb	par)
	Is penetration the correct distance away from electrical condu	it? (at least 3-inches away)		
	Penetrations in slab greater than %-inch have been scanned by	y 3 rd party (This includes ro	oto-han	imering	for anchors)
	If there is electrical in the slab, has it been de-energized by the	e electrician, locked and ta	gged o	ut?	
00	Is there a JHA and/or Pre-Task plan for scope of work?	erside of the slab you need	d to pro	tect?	
	그 그 그렇게 하지 않게 되어 이렇게 잃었어 목표하면 뭐 보여 생각이 되었다면 사람들이 어떻게 하는 것이 하셨다				
ũ	그는 사람들이 아니라 아니라를 하시면 하는 사람들이 아니라를 가게 하고 있다. 그 모든 아니라는 아니라는 아니라는 아니라는 아니라는 아니라는 아니라는 아니라는	:t?			
		rol in prace per OSHA's Ta	ble 17		
	A Company of the Comp				
	The state of the s	ent equipment from ruoni	ng nya	the ede	1027
ō					
Act	ctivity Start Time:Schedule Com	ipletion Time:			
Co	ontractor Competent Person Assigned to Task (printname):				
BN	NBuilders site supervisor has reviewed work plan (BNB Signature	e):			
	NBuilders PM or Foreman has reviewed (Signature):	V			
	ectrical Supervisor has performed lockout tagout if necessary:				
	ate Reviewed: / / Reviewed with whom				



CORE DRILLING/SAW CUTTING CHECKLIST

Contractor Signature:		Date:
	e Drilling/Saw Cutting Checklist and understand this document, including the attached Job Ha	that I am required to carry out the above-described zard Analysis (JHA), and Pre-Task Plan.
Print Name	Signature	Company

If there is <u>ANY conflict</u> with the core or saw cut, **STOP**, and bring it to BNB's attention. This core or saw cut location should be reviewed with the engineer and architect before continuing. Options that may need to be discussed include but are not limited to; moving the core location, re-routing the system a different way, or surface mounting that particular system. All crews involved in the coring and saw cutting process shall review this document before they start their operations.



Crane Pick Plan

Description of Load Project Name Project Address Date of Pick Crane Provider Owner Owner' Owner's Representative BNB Superintendent (Site Supervisor) BNB Project Manager Contractor Responsible Contractor Superintendent Contractor Project Manager Lift Director A/D Director (Mobile Crane) A/D Director (Tower Crane) Narrative Complete a detailed description of the pick plan.		7.077.C. S. C.	
Project Address Date of Pick Crane Provider Owner Owner's Representative BNB Superintendent (Site Supervisor) BNB Project Manager Contractor Responsible Contractor Superintendent Contractor Project Manager Lift Director A/D Director (Mobile Crane) A/D Director (Tower Crane) Narrative Complete a detailed description of the pick plan.	Description of Load		
Project Address Date of Pick Crane Provider Owner Owner's Representative BNB Superintendent (Site Supervisor) BNB Project Manager Contractor Responsible Contractor Superintendent Contractor Project Manager Lift Director A/D Director (Mobile Crane) A/D Director (Tower Crane) Narrative Complète a detailed description of the pick plan.	Project Name		
Date of Pick Crane Provider Owner Owner's Representative BNB Superintendent (Site Supervisor) BNB Project Manager Contractor Responsible Contractor Project Manager Lift Director A/D Director (Mobile Crane) A/D Director (Tower Crane) Narrative Complete a detailed description of the pick plan.			
Owner Owner's Representative BNB Superintendent (Site Supervisor) BNB Project Manager Contractor Responsible Contractor Superintendent Contractor Project Manager Lift Director A/D Director (Mobile Crane) A/D Director (Tower Crane) Nametive Complete a detailed description of the pick plan.	part of the control o		
Owner's Representative BNB Superintendent (Site Supervisor) BNB Project Manager Contractor Responsible Contractor Project Manager Lift Director A/D Director (Mobile Crane) A/D Director (Tower Crane) Narrative Complete a detailed description of the pick plan.	Crane Provider		
Owner's Representative BNB Superintendent (Site Supervisor) BNB Project Manager Contractor Responsible Contractor Project Manager Lift Director A/D Director (Mobile Crane) A/D Director (Tower Crane) Narrative Complete a detailed description of the pick plan.	Dwogs		
BNB Superintendent (Site Supervisor) BNB Project Manager Contractor Responsible Contractor Project Manager Lift Director A/D Director (Mobile Crane) A/D Director (Tower Crane) Narrative Complète a detailed description of the pick plan.	The state of the s		
Contractor Responsible Contractor Superintendent Contractor Project Manager Lift Director A/D Director (Mobile Crane) A/D Director (Tower Crane) Narrative Complète a detailed description of the pick plan.			
Contractor Responsible Contractor Superintendent Contractor Project Manager Lift Director A/D Director (Mobile Crane) A/D Director (Tower Crane) Namelive Complete a detailed description of the pick plan.		4	
Contractor Superintendent Contractor Project Manager Lift Director A/D Director (Mobile Crane) A/D Director (Tower Crane) Narrative Complete a detailed description of the pick plan.	BNB Project Manager	-	
Contractor Superintendent Contractor Project Manager Lift Director A/D Director (Mobile Crane) A/D Director (Tower Crane) Narrative Complete a detailed description of the pick plan.	Contractor Responsible		
Contractor Project Manager Lift Director A/D Director (Mobile Crane) A/D Director (Tower Crane) Narrative Complete a detailed description of the pick plan.			
A/D Director (Mobile Crane) A/D Director (Tower Crane) Name ove Complete a detailed description of the pick plan.			
A/D Director (Mobile Crane) A/D Director (Tower Crane) Narrative Complete a detailed description of the pick plan.	I DE POLICE LA CO		
A/D Director (Tower Crane) Narrative Complete a detailed description of the pick plan.	to all the collection in the Collection of the c	\(\frac{1}{2}\)	
Narrative Complete a detailed description of the pick plan.		-	
Complete a detailed description of the pick plan.	A/D Director (Tower Crane)	9	
Complete a detailed description of the pick plan.		Macentina	
	ar combrate a moneta acceptante and shipper		

Pick Permit

	Pick P	lan Weights	
Load Block Ball Spreader Bar	lbs lbs lbs lbs	Wire Rope Rigging Deduction of Jib	lbs lbs
		Total Load	0 lbs
Has load weight been verified?		Yes	No
How? Is this a tandem pick?		Yes	No

	Crane Information		
Serial #	Outrigger Extension:	Full	
Crane Capacity		Half	·
Boom Radius		N/A	
Boom Height		_	·
Boom Angle	Lift Will Be:	Side	
Boom Length		Front	
Counterweight		Rear	·
Parts of Line		_	
Line Capacity	On Crawlers	Extended	
		Retracted	
Wind Speed Shutdown		N/A	
		-	
	Crane Picks on Rubber Tires Are Not Allowed!		

Capacity Verification							
Total Load		0	lbs				
Crane Capacity			lbs				
Lifting Percentage of Crane (Capacity:	#DIV/0!					
Pick Classification:	Normal Lift Critical Lift Engineered Lift	0% - 74% 75% - 89% 90% - 100%					
Permit Completed By:							

Site Logistics

Location of Pick					
Site Logistics Map Included?	Yes		No		
Crane Set Up On:	Soil		Asphalt		Concrete
Soil Bearing Pressure Max Load On Individual Outrigger	1				
Are Underground Utilities Present?		Yes		No	
List Utilities					
_					
Are Overhead Utilities Present? List Utilities		Yes		No	
Proximity of Overhead Utilities to Picl	k				
Skatch Man of Disk if Not Included					
Sketch Map of Pick if Not Included					

Rigging Information

	Shackles		
Capacity	Qty	Weight	Total Weight
	Sha	ackle Weights	0
	Capacity	Capacity Qty	

		Synthet	ic Straps/S	Slings	
Type/Color yellow	Configuration	Capacity	Qty	Weight	Total Weight
blue					
				Synthetic Weights	0

		Wire Rope		
Type	Capacity	Qty	Weight	Total Weight
		Wire	e Rope Weights	0

		Chains		
Type	Capacity	Qty	Weight	Total Weight
		C	hain Weights	0

		Spreader Bars		
Type	Capacity	Qty	Weight	Total Weight
		Spread	der Bar Weights	0

Total Rigging Weight	0
----------------------	---





Rigging Diagram	
Is a Rigging Diagram included? Yes Sketch Rigging Diagram if not included(Site plan and vertical)	No





	Sign - Off	
Contractor Responsible		
Contractor Superintendent	-	
Contractor Project Manager	-	
Contractor Safety Manager (If Required)		
BNB		
BNB Superintendent		
BNB Project Manager		
Safety Director		
(If Required)		

On-Site Pre-Pick Meeting Lift Director		
Crane Operator	-	
A/D Director (Mobile Crane)		1
A/D Director (Tower Crane)		-
Certified Rigger/Signal Person		
Crew Members		
14	_	
	_	
	_	
14 -		
	_,	====



Crane Pick Plan Checklist



BNB	/es	No	N/A	Water
Live Utility Map				
Underground Structures				
Soil Bearing Pressure		14-4		
Overhead Utilities		152.11		
Barricade and Signage Required?	1			
Building Heights				

Responsible Contractor	Ves	No	N/A	Workes
Detailed Narrative				
Load Weight Verification		1		= -1
Site Logistics				
Crane Layout				
Rigging Diagram		1 1 1 1		
Identify Load Pick Points				
Does Load Include Oil/Coolant?		*		
JHA Complete?		1 1 1 1	1 == == X	
Engineering for Multiple Crane Pic		-5 2 1		= 1
Hoisting Over Occupied Spaces?				
Hoisting in Close Proximity to Powe				
Hoisting Long Lead or High Value Ite				
Engineered Pick? - Stamped Calcs In	-			
Fall Protection Plan				

Crane Provider	Yes	No	N/A	Wones
Annual Crane Cert.				
Is Customer Named on Insurance Ce				
Crane Serial Number				
Crane Capacity				
Load Charts				
Crane Configuration				
Boom Height/Angle	-	1	1	
Crane Radius				
Load Over Any Outrigger		100	1 - 4 -	
Crane Mats/Blocking/Steel Plates		1 2 2 11		
Certified Crane Operator NCCCO Ca				
Certified Rigger Card		7 7 = 74		
Communication System?		1 7 1		
Lattice Boom Crane		1		
Erection/Dismantle Plan		11 - 11		
1 - 1 - 1 - 1 - 1 - 1 - 1				



DEMOLITION PERMIT

		Street Use Permit?
		Noise Variance Permit?
		Abatement Permit?
		Does Demo Require City Permit?
		Required Permits
		Need Industrial Hygienist?
		Noise Concerns in Neighborhood?
		Noise / Vibration Concerns within Building?
		Is Building Safe for Equipment Weights? Structural Engineer to Review
		HAZMAT Concerns?
		Measures and/or Destressing Plan
		**If Demo of Post Tension Concrete - Need to Verify Preventatative
		Building Structure Type
		Demo Methods - Labor, Heavy Equipment, Handtools?
		Lab/Specialty Equipment - Biohazards, Chemicals, Hazmat?
		Structural Demo - Concrete, Roof, Steel, Wood?
		Select Non Structural Demo?
		Type of Demolition
		PCB ballasts and fluorescent light bulb disposal Required?
		Are There Specific Areas That Are Unsafe to Enter?
		Is the Building Safe to Enter?
		Have We Sent Copy of Information to Subs / Employees?
		**Lab Equipment - Do We Have Documentation That It is Clean?
		If Not, Need to Complete Material Sampling/Testing
		If Yes, Does It Satisfy Our Requirements?
		Did We Receive a Good Faith Survey?
		Good Faith Survey
Comments	RESP.	Project: Date:

Emergency Evacuation Plan in Place?
Is There a Need for an L&I Consultation?
Existing Equipment Decommissioned (Tanks, HVAC Chemicals, Light Ballasts?)
Lockout Tag Out Program in Place?
**Hot Work Permits Required?
**Shutdowns Require MOP?
**Coordinated Shutdowns with Building Owner/Tenant?
**Fire Sprinkler Drained? Fire Watch Required?
**Fire Alarm System Shutdown or Put in Test?
**Electrical Sub Confirm Work Area Safe'd Off?
**Identified MEP Systems to Remain - Marked in Field?
JHA, PPE Assesment and Pretask Plans Completed?
Logistics Plan Completed?
Site Conditions Reviewed By BNB Safety Representative?
Site Specific Safety Plan Completed?
If Using Demo Subcontractor - Do We Have Sub Demo Work Plan?
Work Area
**Includes Identifying Any Electrical or Mechanical Room Outside of
**Need to Pot Hole to Confirm?
**Includes Utility Locates (Exterior & Interior) Subs to Call Dig Alert #?
**Includes Review of As-Builts & Tenant / Building Owner
**Includes Locations of All Shutoff Valves for Utilities
Live Utility Plan Completed and Reviewed with Subs?
Completed BNB Plumbing/Piping Demo Checklist? Separate Document
Completed BNB HVAC Demo Checklist? Separate Document
Completed BNB Electrical Demo Checklist? Separate Document
Internal checklist
Specialty PPE: High Visiblity Clothing, Kevlar Sleeves?
Shoring & Support Scaffold?
Temp Protection: Interior / Exterior, Safety Rails, Signage
Air Quality Plan: Air Sniffers, Fans, Fresh Air Supply, Exhaust?
Specialty Tools & Plans

Required Training 2 Hr. Asbestos Awareness Training? Lead Awareness/RRP Training? Mold Awareness Training?
2 Hr. Asbestos Awareness Training? Lead Awareness/RRP Training? Mold Awareness Training?
Lead Awareness/RRP Training? Mold Awareness Training?
Mold Awareness Training?
In The sea Associated No. and a district Designation
Is there any Other Training Needed for this Project?
Sign off on Demolition Signature Date
BNB Safety Director or General Superintendent
Site safety representative
Foreman in charge
Site Superintendent



Electrical Demolition Work Plan

The steps below are required to perform Make Safe Activities for demolition:

- Identify <u>all</u> electrical circuits feeding into or passing through the area / room if any conduit cannot be identified, bring it to the attention of BNB/ Owner for further review.
- Identify all electrical items and conduit for Lock Out Tag Out (LOTO) noted on the demolition plan
- 3. Submit LOTO circuit list to facilities (CMC)
- Facilities & electrical contractor to LOTO all identified circuits (two locks)
- 5. Verify Zero Energy
 - Identify required PPE
 - Arc Flash Protection Electrical contractor to identify OSHA PPE requirements based on activities
 - Shock Protection Hard hat, safety glasses, face shield, long sleeves,
 leather gloves, pants, work boots no high vis vest or polyester clothing
 - Use Muti Meter at final termination verify zero reading
 - A Primary Authorized Person (PAP) and a separate reviewer (BNB) must witness the zero energy reading
 - Fill out and sign BNB's LOTO portion of the Electrical Demo Sign Off Check
 List
- Once zero energy is verified at the termination point, mark/ label within 6" in green tape or paint indicating demo.
- 7. Continue through all remaining LOTO circuits repeating steps 5 & 6
- 8. Open all 'J' boxes or pull boxes on circuits/ conduit to demo leave boxes open
- Perform a redundant test using a pen type inductance tester where applicable –
 examples including but not limited to: 'J' boxes, pull boxes, found conductors, etc.,
 verifying each conductor again for zero energy shock protection PPE required
- 10. Label/ mark each conduit leg within 6" of the box green for demo or red to stay.
- 11. Pull conductors or wires as directed by the demo drawings. If wiring is to be coiled up for later use, label/ Tag the end of the wires with the corresponding LOTO information.
- Label/ mark conduits to demo every 15' and at both sides of the wall as required per demo drawings
- 13. Make a 6" visual cut or separation at both sides of walls as required.
- 14. A ring system must be utilized for the demo of the conduits. The ring slides forward along the conduit as demo progresses. Only the conduits with the ring may be cut.
- Once complete, fill out remaining portion of the BNB's Electrical Demo Sign off Check
 List and submit it to the superintendent.
- 16. Post Demo signs in area Green is Go (demo), Red is Stay, No label STOP!
- Demo all green labeled electrical items.



ELECTRICAL DEMO SIGN OFF CHECK LIST

PROJECT NAME:

DISCIPLINE:	CONTRACTOR	RESPONSIBLE PERSON (Print Clearly)	DATE
ideir Live:	CONTRACTOR	RESPONSIBLE PERSON (Print Cleany)	DATE
lectrical - greater than 50V			
List circuits affected, Panels, MQCs, etc.			
Lock Out Tag Out Complete			
Witness			
Verification of Zero Energy in the field			
Witness			
Electrical - greater than 50V complete			
Electrical - less than 50V			
Security System			
Cameras			
Access Control			
Fire Alarm			
Smake Detectors			
Duct Detectors			
HVAC Controls			
Telecom / Date			
Equipment Alarms / Monitoring Devices			
Miscellaneous			
Electrical - Less than 50V complete			
NB Quality Control			
ALL UTILITY LAYOUT/ LABELING MUST BE COMPLETE	GREEN is GO (demo)	RED is STAY Use rad danger tape to identity energiced lines. Red Markings are required every 16 year.	

BY SIGNING THIS DOCUMENT YOU AGREE THAT YOU HAVE INSPECTED YOUR WORK IN THIS ROOM AND YOUR WORK IS COMPLETE AND PERFORMED CORRECTLY PER CONTRACT DRAWINGS, SPECIFICATIONS AND DEMO REQUIREMENTS. ALL SAFE OFF ACTIVITIES HAVE BEEN COMPLETED.

Green multi-ron are required every 15 had



HVAC Demolition Work Plan

The steps below are required to perform Make Safe Activities for demolition:

- 1. Identify all HVAC systems feeding into or passing through the area / room
- 2. Verify all Fume exhaust ductwork has been cleaned and no hazardous chemicals are present
 - Obtain a written copy of proof from BNB
- Identify all systems to demo for Lock Out Tag Out (LOTO) from the demolition plan
- 4. Submit LOTO list to facilities (CMC)
- Facilities (CMC) & HVAC contractor to LOTO all identified systems (two locks)
- 6. Continue through all remaining LOTO of systems, repeating steps 5, 6 and 7.
- 7. Perform cut and capping activities.
- 8. If a Hot Work permit is needed:
 - Verify approval and obtain a hot work permit
 - · Verify the fire alarm is on test
 - Using a dedicated fire watch (see BNB/CMC's Fire Watch requirements)
 - Use a 20 lb dedicated fire extinguisher
- 9. Label/ mark each end of the HVAC duct to be demo'd green for demo and red to stay.
- Label/ mark HVAC duct and equipment to demo every 15' and at both sides of the wall as required per demo drawings
- Make a 6" visual cut or separation at both sides of walls or equipment as required.
- Once complete, fill out remaining portion of the BNB's HVAC Demo Sign off Check List and submit it to the superintendent.
- 13. Post Demo signs in area Green is Go (demo), Red is Stay, No label STOP!
- 14. Demo all green labeled HVAC items.



HVAC DEMO SIGN OFF CHECK LIST

PROJECT NAME:

ISCIPLINE:	CONTRACTOR	RESPONSIBLE PERSON (Print Clearly)	DATE
VAC			
Supply		7.4	
Lock Our Tag Out Complete for each system		10	
Witness			
All HVAC Supply Cut and Cap/ Isolation/ Make Safe activities are complete			
Exhaust			
Lock Out Tag Out Complete for each system		7	
Witness			
All HVAC Exhaust Cut and Cap/ Isolation/ Make Safe activities are complete			
Fume Exhaust		3	
Lock Out Tag Out Complete for each system		2	
Witness			
All HVAC Fume Exhaust Cut and Cap/ Isolation/ Make Safe activities are complete			
All HVAC Cut and Cap / Isolation/ Make Safa activities are complete			
NB Quality Control		5 1	
ne adding control			
ALL UTILITY LAYOUT/ LABELING MUST BE COMPLETE	GREEN is GO (demo)	RED is STAY	
COMPLETE	Violale severación al walls and systema la remain Secun markings ere required every 15 feet	Use you danger laps to identify systems to remain Hed Markings are required every 15 feet	

BY SIGNING THIS DOCUMENT YOU AGREE THAT YOU HAVE INSPECTED YOUR WORK IN THIS ROOM AND YOUR WORK IS COMPLETE AND PERFORMED CORRECTLY PER CONTRACT DRAWINGS, SPECIFICATIONS AND DEMO REQUIREMENTS. ALL SAFE OFF ACTIVITIES HAVE BEEN COMPLETED.

CC:

BNB File Subcontractors



Plumbing / Piping Demolition Work Plan

The steps below are required to perform Make Safe Activities for demolition:

- Identify <u>all</u> plumbing/ piping systems feeding into or passing through the area / room if any plumbing or piping cannot be identified, bring it to the attention of BNB/ CMC for further review.
- 2. Verify all piping has been cleaned and no hazardous chemicals are present
 - Obtain a written copy of proof from BNB
- 3. Identify all systems for Lock Out Tag Out (LOTO) noted on the demolition plan
- 4. Submit LOTO list to facilities (CMC)
- 5. Facilities (CMC) & plumbing/ piping contractor to LOTO all identified systems (two locks)
- 6. Verify Zero Energy
 - Identify required PPE
 - Is line breaking involved? If so, follow CMC's Line breaking procedures
 - Drain systems
 - A Primary Authorized Person (PAP) (CMC) will verify drain down of each system
 - Fill out and sign BNB's LOTO portion of the Plumbing / Piping Demo Sign Off Check
 List
- 7. Once system is drained, mark/ label cut and cap and valve locations with Red Danger Tape
- 8. Continue through all remaining LOTO of systems, repeating steps 5, 6 and 7.
- 9. Perform cut and capping or valve installation activities.
- 10. If a Hot Work permit is needed:
 - Verify approval and obtain a hot work permit
 - Verify the fire alarm is on test
 - Using a dedicated fire watch (see BNB/CMC's Fire Watch requirements)
 - Use a 20 lb dedicated fire extinguisher
- 11. Label/ mark each end of the plumbing/ piping run to be demo'd green for demo and red to stay.
- Label/ mark plumbing/ piping to demo every 15' and at both sides of the wall as required per demo drawings
- 13. Make a 6" visual cut or separation at both sides of walls or equipment as required.
- 14. A ring system must be utilized for the demo of the plumbing and piping. The ring slides forward along the plumbing or piping as demo progresses. Only the plumbing or piping with the ring may be cut.
- 15. Once complete, fill out remaining portion of the BNB's Plumbing/ Piping Demo Sign off Check List and submit it to the superintendent.
- Post Demo signs in area Green is Go (demo), Red is Stay, No label STOP!
- 17. Demo all green labeled plumbing and piping items.



PLUMBING / PIPING DEMO SIGN OFF CHECK LIST

PROJECT NAME: ZONE - ROOM - NAME - LOCATION: DISCIPLINE: CONTRACTOR RESPONSIBLE PERSON (Print Clearly) DATE Plumbing List all systems affected Lock Out Tag Out Complete for each system Vertilication of Zero Energy in the field Missellaneous All Plumbing Make Safe activities are complete Piping List all systems affected Lock Out Tag Out Complete Witness Venilication of Zero Energy in the field Witness Miscellaneous. All Piping Make Safe activities are complete **BNB Quality Control** GREEN is GO **RED is STAY** ALL UTILITY LAYOUT/ (demo) LABELING MUST BE COMPLETE Use red danger tage to identify systems to remain Visible seouration at walls

BY SIGNING THIS DOCUMENT YOU AGREE THAT YOU HAVE INSPECTED YOUR WORK IN THIS ROOM AND YOUR WORK IS COMPLETE AND PERFORMED CORRECTLY PER CONTRACT DRAWINGS, SPECIFICATIONS AND DEMO REQUIREMENTS. ALL SAFE OFF ACTIVITIES HAVE BEEN COMPLETED.

Kud Markings are required every 16 local

Cream markings are required usery 15 feet

PS IV PS	DETERMINATION OF FONEINED FRACE	Cod: C	per-9A
SHE Ollows	DETERMINATION OF CONFINED SPACE		Apr-17
	CONFINED SPACE DETERMINATION		
1	is the space large enough and so configured to allow bodily entry?	Yes	No
2	Is it not designed for human occupancy?	Yes	No
3	Does the space have limited or restricted means of entry and exit?	Yes	No
rine answer Proceed to n	to ALL THREE questions above is YES, the space is considered a Confined Space. ext step PERMIT REQUIRED CONFINED SPACE DETERMINATION		
And the second second	ext step		
the state of the s	PERMIT REQUIRED CONFINED SPACE DETERMINATION	Yes	No
Proceed to n	PERMIT REQUIRED CONFINED SPACE DETERMINATION Does the space contain or have the potential to contain a hazardous atmosphere?	Yes Yes	No.
roceed to no	PERMIT REQUIRED CONFINED SPACE DETERMINATION	-	7.7
Proceed to no 4 5	PERMIT REQUIRED CONFINED SPACE DETERMINATION Does the space contain or have the potential to contain a hazardous atmosphere? Does the space contain or have the potential for engulfment or entrapment?	Yes	No



DIG PERMIT

Code#	Oper-12A	
Rev.	0	
Date	Jun-2018	

AUTHORIZATION DATE:\\\ CONTRACTOR:				
	ny type of excavation including, trenching, concrete cutting or ground penetration of any kind, is planned for a jobsite a Dig Permit will be ted. The following information will be addressed and authorized by site Superintendent and Project Manager prior to any excavation.			
SECTIO	ON1			
Project:				
One Call	l (811) Ticket # Date Called: / / 20 Past 45 days? Yes No			
	locates and/or radar imaging (GPR) are required if dig/cut is located within property lines or building. Additional radar imaging required after e has been removed to ensure no utilities exist under slab location.			
Excavati	ion Checklist			
	Area of work is marked in white paint and marked on a copy of site Live Utility Map and dated (Attached)			
	Area has been located by 811 and/or Private Locates (Private Locate Company/Contact:)			
	Review area, Locates and mark-up with BNB Superintendent or Project Manager			
	Review Live Utility Map posted in BNB Trailer			
	JHA completed by subcontractor and reviewed by BNB supervision			
D.	All employees involved in excavation have signed attached attendance sheet.			
	If NO utilities are within 10° of proposed excavation proceed to section 3 below.			
SECTIO	281.2			
	litional requirements outlined below are required for any work operation taking place within 10 feet of any live utility (Electrical, Sprinkler ster Supply, Sanitary/Storm Sewer, Unknown, Etc.). This includes, but is not limited to trenching, excavating, and boring.			
	Pot Hole / Hand Dig to Positively Find Utility			
☐ YES	NO Hole cover protection required? If YES, Describe Method of Protection:			
	Spotter/Observer must be used if using mechanized digging equipment within Tolerance Zone (only after potholing)			
	Identify location of shut offs for utilities, water, gas, etc. and marked on a copy of the site Live Utility Map. (Attached)			
Ö	JHA complete by subcontractor and reviewed by BNB supervision			
	Affected crew reviewed locates/radar imaging, and JHA the day of proposed excavation with BNB Supervision.			
	2 Section described the state of define and a second section of the second of the seco			
	All employees involved in excavation have signed attached attendance sheet (See page 2).			
	Description:			
Mitigation	on (How are you not going to hit or cause disruption?):			
Phone n	numbers of utilities within 10' of excavating activities:			
SECTIO	ON 3			
Activity	Start Date/Time: Schedule Completion Date/Time:			
	for dig: Depth of dig:			
0	Locate on site Live Utility Map			
Subcont	tractor and Competent Person Assigned to Task:			
BNBuild	lers Representative (To be ansite during work):			
This Live	e Utility Awareness Work Authorization and associated JHA, Locates, Live Utility Map have been reviewed and authorized by:			
	Project Superintendent Date			
-				



DIG PERMIT

Code #	Oper-12A
Rev.	0
Date	Jun-2018

I have reviewed this Live Utility Awareness Work Authorization and understand that I am required to carry out the above-described works in accordance with this document, including the attached Job Hazard Analysis and MOP if within 10' of any live utility.

Authorized Participants: (Attach additional Authorized Participants on separate sheet if necessary)

Print Name	Signature	Company
Print Name	Signature	Company
Print Name	Signature	Company
Frint Name	Signatore	Company
Frint Name	Signature	Сотрапу
Frint Name	Signature	Company
Print Name	Signature	Company



DRONE SURVEYING CHECKLIST

Miss	ion Planning	Pref	ight Inspection
0	Check Airspace restrictions		Check Airframe
	Check for TFR's		Check batteries for damage
	Check weather forecast		Propellers(bendable,not cracked)
	Obtain authority to fly over site		Motor area (clear?)
	Obtain BNB Drone Permit		Camera & Gimbal (cleaned & free)
	Check system for updates		Controller (antenna extended)
O.	Create flight path		
	Save flight path offline		
		Fligh	t Prep
Pack	ing Checklist	u	Power on controller & aircraft
	Aircraft		Ensure SD card has enough space
	Flight batteries (charged)	0	Check overall status (green Bar DJI App
	Controller (charged)	i i	Select autopilot mission (map Pilot App)
	Tablet (charged)		Ensure altitude is right for terrain
	Memory cards	ū	
	Propellers		and the second second
	Tablet cables	1	Zests
	Operation checklists	After	Flight
Site	Prep	u	Power down & stow all equipment
	Check site for obstructions		Log flight information in flight logs
-	(trees, power lines, elevation change)		Download data
0	그래, 그리고 아이는 이렇게 되었다면서 그를 먹는데 하나 그를 하는데 하나		
	(wind speed, temperature, visibility)		
	Verify Line of Sight(LOS) can be		
	achieved		
D	Brief Forward Observer, maintain		
	comms & eye communication		
	Set ground control points		
	Survey ground control points as needed		



Dropped Object Prevention Evaluation

Complete this evaluation to ensure overhead work is safely conducted. Immediate concerns should be addressed on the spot and documented. For jobs under construction, but not yet above-grade, review this evaluation with the project team to plan ahead and eliminate risk from falling materials.

Project Name:	
Name of Evaluator:	
	100 00000
Critical Tieres	Yes, No, N/A
Is overhead protection free of gaps to prevent falling objects?	
Are Controlled Access Zones (CAZs) established below overhead work?	
Are tools tethered when working at height near the exterior/leading edge of a structure, shaft stairway?	
Do personnel working at leading edges only have the required tools in their tool belts, bags etc?	
Are persons authorized to work in CAZs (i.e., dismantling a scaffold or concrete deck form) paying attention to what is going on above them and using spotters when needed?	
Are materials hoisted overactive work areas controlled? (i.e., loose pieces of material are secured, the workforce is warned via horn/whistle and they pay attention to the warning, operators avoid flying loads over personnel, etc).	
Do rigging/tag lines clear obstructions before operators are instructed to "take it away"?	
Do ground-floor entrances in and out of buildings or setbacks have adequate overhead protection?	
Are CAZs maintained with physical barriers and signage that identify who is controlling/restricting the area?	
If danger tape is used for a CAZ, is it only put up while the area is restricted and then taken down when the risk is removed? Is a spotter used to enforce CAZ when danger tape barricade system is not being used?	
Is good housekeeping in effect to prevent loose materials within 8 feet of open edges? Perimeter deck landings kept clear at all times?	
Non-Critical Items	Yes, No, N/A
Are trades scheduling work to prevent working over one another?	

Comments:	 	 	
·			

During weekly toolbox meetings, is dropped object prevention addressed?

Are JHAs for subcontractors reviewed to ensure provisions for dropped-object protection?

Do PTPs address overhead protection/dropped object prevention? Is BNB staff reviewing these PTPs?

Are all employees on crew trained in

Date of Evaluation:



Equipment Use Agreement and Indemnification

Project Name ("Project"):	
Date:	
Company:	

WHEREAS, the Parties to this Equipment and Use Agreement and Indemnification ("Agreement") hereby acknowledge that BNBuilders, Inc. ("BNB"), as General Contractor, will have, located on the Project site, various types of equipment to be used for the construction of the Project referenced above, including without limitation, tools, temporary structures, special cranes, hoists, forklifts, and lifts (together with any and all accessories, attachments, or similar items connected thereto, the "Equipment").

WHEREAS, the Parties to this Agreement hereby acknowledge that the Company stated above will, on occasion, use the Equipment provided by BNB. This Agreement supplements/supersedes any existing agreement between the parties with regard to Company's use of the Equipment.

IT IS AGREED AS FOLLOWS:

Article I - Approval

- 1.1 Use of the Equipment will be permitted only with the specific and written prior approval of BNB's Project Superintendent.
- 1.2 If written approval is granted. Company agrees not to loan, assign, or allow any third-party to use any Equipment without the specific and written approval of BNB's Project Superintendent. In such instances, any such third-party shall release, defend, and indemnify BNB to the same extent and for the same duration as Company is required to release, defend, and indemnify BNB under the terms of this Agreement.
- 1.3 BNB reserves the right to remove any operator from the Equipment or take possession of the Equipment at any time and at its sole discretion.
- 1.4 BNB reserves the right to terminate this Agreement at any time and at its sole discretion.

Article 2 - Inspection

- 2.1 Upon signing this Agreement or using any Equipment. Company agrees to complete a full inspection of the Equipment by a qualified individual or individuals and will promptly report any problems or defects that it knows or reasonably should have known to BNB's Project Superintendent. Said report shall be in writing and signed by an authorized representative of Company.
- 2.2 At the moment Company, through any of its agents or employees, begins using any of the Equipment, it agrees that it has satisfied itself to the condition of the Equipment, accepts the Equipment "as is", and waives any and all rights to any claims or causes of action whatsoever as they may relate to defects or deficiencies with the Equipment.

Article 3 - Operation

3.1 Company shall: (i) use the Equipment solely in the conduct of its independent business activities; (ii) use and preserve the Equipment in a careful, proper, and lawful manner; (iii) at its own expense, keep the Equipment in good repair, condition, and working order, and (iv) not make any alterations to the Equipment.

- 3.2 Company agrees that the use of the Equipment will only be done by individuals that are employees of Company, have been trained in the use and operation of the particular piece of Equipment, and have been authorized to use the Equipment by BNB's Project Superintendent.
- 3.3 Company, through its agents and employees, agrees to abide by all of the safety rules, requirements, and instructions related to the Equipment being used.

Article 4 - Damage or Repairs

- 4.1 Company accepts responsibility for any damages or repair costs caused by the Company, its agents, employees, suppliers, or sub-company. Company shall bear the entire risk of loss, theft, damage or destruction of the Equipment from any cause whatsoever (a "Casualty Loss"), whether intentional or unintentional, during the term of this Agreement. In the event of a Casualty Loss, Company shall immediately notify BNB, and, at BNB's option: (i) repair or replace the Equipment with identical property in good condition with clear title thereto in BNB, at Company's sole expense; or (ii) pay to BNB the full value of the Equipment.
- 4.2 If damage to the Equipment or reconditioning costs are required for the Equipment and it is difficult to ascertain or assign to any specific user the cause of such Casualty Loss, then Company agrees to pay its pro-rata share of repair/reconditioning costs with any other users of the Equipment. The amount of the pro-rata share will be determined by BNB.

Article 5 - Waiver / Limitation of Liability

- 5.1 Company acknowledges that the Equipment subject to the terms of this Agreement is being provided at the Project site by BNB for the convenience of the Company. Company is not obligated in any way to use said Equipment. As such, Company agrees to waive any and all claims or causes of action whatsoever against the Owner or BNB that relate in any way to Company's use of Builder's' equipment.
- 5.2 In no event shall BNB be liable or responsible to Company or any other party for: (i) any loss, damage, or injury caused by, resulting from or in any way connected with the Equipment, its operation or its use, or (ii) any incidental, consequential, punitive, or special damages. Company acknowledges and assumes all risks inherent in the operation, use and possession of the Equipment from the time the Equipment is delivered to Company until the Equipment is returned to BNB and will take all necessary precautions to protect all persons and property from injury or damage from the Equipment.

Article 6 - Indemnification

- Washington State (the following provision shall apply in the State of Washington): To the fullest extent permitted by law, Company shall release, defend, indemnify and hold harmless the Owner, its agents and employees, and BNB, its agents and employees, from, for, and against all claims, damages, losses, actions proceedings, taxes, penalties, injuries, deaths, liabilities, and expenses, direct or indirect (including but not limited to costs and attorney's fees incurred on such claims, whether or not suit is initiated, and in proving the right to indemnification) ("Loss"), arising out of or resulting from Company, its agents and employees and anyone directly or indirectly employed by them, using and/or operating and/or accessing in any way the Equipment. Such obligation shall not be construed to negate, abridge, or reduce other rights or obligations of indemnity which would otherwise exist. For the purposes of the foregoing indemnification provision only and to the fullest extent allowed by applicable law, Borrower specifically waives immunity it may be granted under the Washington State Industrial Insurance Act, RCW Ch. 51.04 or other employee benefit acts. This indemnity shall survive the expiration, termination, or cancellation of this Agreement.
- 6.2 Washington State (the following provision shall apply in the State of Washington): To the extent a court of competent jurisdiction determines this indemnity provision is subject to RCW 4.24.130, then Company's obligation to defend and indemnify BNB shall be limited as follows: with regard to the indemnity and defense obligations under Section 6.1 arise out of bodily injury to persons or damage to property, such indemnity and defense obligations shall arise regardless of whether such Loss is caused in part by the concurrent or partial negligence of BNB; however, Company shall not be liable to BNB for that portion of any such Loss for bodily injury to persons or damage to property incurred by BNB to the extent of BNB's negligence.
- 6.3 California State (the following provision shall apply in the State of California): To the fullest extent permitted by law, Company shall release, defend, indemnify and hold harmless the Owner, its agents and employees, and BNB, its agents and employees (collectively, the "Indemnified Parties"), from, for, and against all claims, damages, losses, actions proceedings, taxes, penalties, injuries, deaths, liabilities, and expenses, direct or indirect (including but not

limited to costs and attorney's fees incurred on such claims, whether or not suit is initiated, and in proving the right to indemnification) ("Loss"), arising out of or resulting from Company, its agents and employees and anyone directly or indirectly employed by them, using and/or operating and/or accessing in any way BNB's Equipment. Such obligation shall arise regardless of whether such claim, damage, loss, or expense is caused in part by the concurrent or partial negligence of an Indemnified Party; provided, however, to the extent required by Civil Code section 2782.05, Company's obligations hereunder shall not apply to the extent the Loss arises out of, pertains to, or relates to the active negligence or willful misconduct of an Indemnified Party. Such obligation shall not be construed to negate, abridge, or reduce other rights or obligations of indemnity which would otherwise exist. The defense and indemnity shall survive the expiration, termination, or cancellation of this Agreement.

Article 7 - Miscellaneous

- 7.1 Assignment. Without BNB's prior written consent, Company shall not: (i) assign, encumber, or in any way dispose of any interest in this Agreement or the Equipment, or (ii) allow the Equipment to be used by anyone other than agents or employees of Company in accordance with the terms of this Agreement.
- 7.2 Ownership: The Equipment is, and shall remain, personal property, owned by BNB, and Company has no rights in the Equipment except as set forth herein.
- 7.3 Use in Independent Activities. Nothing in this Agreement shall be construed to provide for retention by BNB of any right to control, direct, supervise, or otherwise oversee the manner or method by which Company is utilizing the Equipment in its independent business activities or responsibility for the means, methods, techniques, sequences or procedures, or for the safety precautions and programs in connection with the work and services provided by Company.
- 7.4 Entire Agreement. This Agreement (i) represents the entire agreement between Company and BNB with respect to the subject matter covered, (ii) supersedes any prior understandings with respect to that subject matter and (iii) may only be amended in a writing duly executed by both Company and BNB.

Company:	BNBuilders, Inc.
By:	By:
Name:	Name:
Title:	Title:
Date:	Date:



Date Plan Prepared:

BNB Project Name:

BNB Project Address:

Employer Company Name:

Description of Scope of Work:

Site-Specific Fall Protection Work Plan Template

- Fall protection plans shall be prepared by a qualified person and developed specifically for the site where
 the construction work is being performed.
- 2. The plan must be maintained up to date and any changes shall be approved by a qualified person.
- 3. A current copy of the fall protection plan shall be maintained at the job site,
- 4. The implementation of the fall protection plan shall be under the supervision of a competent person.
- In the event of a fall or incident, a member of the BNB (enter site name) Project Team must be immediately notified. This plan must be adjusted as applicable.

le		tilication of Kespu	insibilities	for this Pla	n			
	Name			Phone #		Signature	Date	
alified Person								
mpetent Person								
reman								
HA 30 Trained Person								
her				1				
her								
	-	Potential fall ha	zard(s) in	the work a	rea			
		onventional fall pr	entaction c	nurhomer to b	o wad			
ne of Lauinment (i.e. h.		Manufacturer	Model	yatema to t		hazard to be used for (from		
Type of Equipment (i.e., harness)		Mattatactore	Mone				Clor (IIOI)	
Se of edolbilicitalities (in	unite say	Mollaractorial	Model				ove table)	



Assembly:

Site-Specific Fall Protection Work Plan Template

1. Description of methods for fall protection system(s)...


	٠	Disassembly:	
	٠	Inspection and maintenance:	
	2.	Description of procedures for tools, equipment, materials, etc Handling:	
	٠	Storage:	
	÷	Securing:	
	3.	Description of methods for overhead protection for personnel a	nd the public as applicable:
	4.	Other considerations:	
		Rescue Plan and Equipment	
Y	ne a	and name of equipment to be used for rescuing fallen personnel	Location of rescue equipment
			11



Site-Specific Fall Protection Work Plan Template

Emergency/Incident Contact Information									
Role	Name	Phone #							
Emergency Medical Services									
On-Site CPR & First Aid Provider									
BNB Site Safety Manager		1 11 1							
BNB Superintendent									
BNB Project Manager	3								

Diagram of fall hazards and staging of fall protection systems:



Sample Diagram (Please delete this one and place your diagram here)



Restricted Editing: Password BNB

FALL PROTECTION TRAINING GUIDE FOR EMPLOYEES

Safety Belt, Harness and Lanyard Inspection and Maintenance

ANSI Classification:

Class I Body belts – used to restrain a person from falling. (High Voltage Electrical Only)
Class II Chest harness – used for restraint purposes (NOT for vertical free fall hazards).
Full body harness – used for fall arrest purposes. Can also be used for fall restraint.

Class IV Suspension/position belt – used to suspend or support the worker. If a fall arrest hazard

exists this must be supplemented by use of a safety harness.

II. Inspection Guidelines:

To maintain their service life and high performance, all belts and harnesses must be inspected prior to each use for mildew, wear, damage and other deteriorations. Visual inspection before each use is just common sense. Periodic tests by a trained inspector for wear, damage or corrosion should be part of the safety program. Inspect your equipment daily and replace it if any of the defective conditions in this manual are found.

Belt inspection: High Voltage Electrical ONLY

- Beginning at one end, holding the body side of the belt toward you, grasp the belt with your hands six to eight inches apart. Bend the belt in an inverted "U". The resulting surface tension makes damaged fibers or cuts easier to see.
- Follow this procedure the entire length of the belt or harness. Watch for frayed edges, broken fibers, pulled stitches, cuts, or chemical damage.
- Special attention should be given to the attachment of buckles and Dee Rings to webbing. Note any unusual wear, frayed or cut fibers, or distortion of the buckles or Dees.
- Inspect for frayed or broken strands. Broken webbing strands generally appear as tufts on the webbing surface. Any broken, cut, or burned stitches will be readily seen.
- Rivets should be tight and immovable with fingers. Body side rivet base and outside rivet burr should be flat against the material. Bent rivets will fail under stress.
 - Especially note condition of Dee Ring rivets and Dee Ring metal wear pads (if any). Discolored, pitted or cracked rivets indicate chemical corrosion.
- 6. The tongue, or billet, of the belt receives heavy wear from repeated buckling and unbuckling. Inspect for loose, distorted, or broken grammets. Belts using punched holes without grammets should be checked for torn or elongated holes, causing slippage of the buckle tongue.



Safety Belt, Harness and Lanyard Inspection and Maintenance cont'd

7. Tonque Buckle:

Buckle tongues should be free of distortion in shape and motion. They should overlap the buckle frame and move freely back and forth in their socket. Roller should turn freely on Irame. Check for distortion or sharp edges.

Friction Bucklet

Inspect the buckle for distortion. The outer bars and center bars must be straight. Pay special attention to corners and attachment to points of the center bar.

9. Sliding Bar Buckle:

Inspect buckle frame and sliding bar for cracks, distortions, or sharp edges.

Sliding bar should move freely. Knurled edge will slip if worn smooth. Pay special attention to corners and ends of sliding bar.

Lanyard inspection:

When inspecting lanyards, begin at one end and work to the opposite end. Slowly rotate the lanyard so that the entire circumference is checked. Spliced ends require particular attention. Hardware should be examined under procedures also detailed below, i.e., Snaps, Dee Ring, and Thimbles.

1. Steel

While rotating the steel lanyard, watch for cuts, frayed areas, or unusual wearing patterns on the wire. Broken strands will separate from the body of the lanyards.

Webbing

While bending webbing over a pipe or mandrel, observe each side of the webbed lanyard. This will reveal any cuts or breaks. Swelling, discolorations, cracks, and charring are obvious signs of chemical or heat damage. Observe closely for any breaks in stitching.

3. Rope

Rotation of the rope lanyard while inspecting from end to end will bring to light any fuzzy, worn, broken, or cut fibers. Weakened areas from extreme loads will appear as a



Restricted Editing: Password BNB noticeable change in original diameter. The rope diameter should be uniform throughout, following a short break-in-period.

FALL PROTECTION TRAINING GUIDE FOR EMPLOYEES

Fall Protection System Considerations

Below are guidelines for worker protection where fall arrest or fall restraint systems are used. Some of this material may be suitable for adding to the written fall protection work plan specified in WAC 296-880-10020.

Selection and use considerations:

The kind of personal fall arrest system selected should match the particular work situation, and any possible free fall distance should be kept to a minimum. Consideration should be given to the particular work environment. For example, the presence of acids, dirt, moisture, oil, grease, etc., and their effect on the system, should be evaluated. Hot or cold environments may also have an adverse affect on the system. Wire rope should not be used where an electrical hazard is anticipated. As required by the Unified Safety Standards for Fall Protection WAC 296-880, the employer must plan to have means available to promptly rescue an employee should a fall occur, since the suspended employee may not be able to reach a work level independently.

Where lanyards, connectors, and lifelines are subject to damage by work operations such as welding, chemical cleaning, and sandblasting, the component should be protected, or other securing systems should be used. The employer should fully evaluate the work conditions and environment (including seasonal weather changes) before selecting the appropriate personal fall protection system. Once in use, the system's effectiveness should be monitored. In some cases, a program for cleaning and maintenance of the system may be necessary.

2 Testing considerations:

Before purchasing or putting into use a personal fall arrest system, an employer should obtain from the supplier information about the system based on its performance during testing so that the employer can know if the system meets this standard. Testing should be done using recognized test methods. WAC 296-880-510 Appendix C; contains test methods recognized for evaluating the performance of fall arrest systems. Not all systems may need to be individually tested; the performance of some systems may be based on data and calculations derived from testing of similar systems, provided that enough information is available to demonstrate similarity of function and design.

3. Component compatibility considerations:

Ideally, a personal fall arrest system is designed, tested, and supplied as a complete system. However, it is common practice for lanyards, connectors, lifelines, deceleration devices, and body harnesses to be interchanged since some components wear out before others. The employer and employee should realize that not all components are interchangeable. For instance, a lanyard should not be connected between a body harness and a deceleration device of the self-retracting type since this can result in additional free fall for which the system was not designed. Any substitution or change to a personal fall arrest system should



Restricted Editing: Password BNB

be fully evaluated or tested by a competent person to determine that it meets the standard, before the modified system is put in use.

FALL PROTECTION TRAINING GUIDE FOR EMPLOYEES

Fall Protection System Considerations cont'd

Employee training considerations;

Thorough employee training in the selection and use of personal fall arrest systems is imperative. As stated in the standard, before the equipment is used, employees must be trained in the recognition of hazards related to a fall and the procedures to minimize those hazards along with the safe use of the system. This should include the following: Application limits; proper anchoring and tie-off techniques; estimation of free fall distance, including determination of deceleration distance, and total fall distance to prevent striking a lower level; methods of use; and inspection and storage of the system. Careless or improper use of the equipment can result in serious injury or death. Employers and employees should become familiar with this material, as well as manufacturer's recommendations, before a system is used. Of uppermost importance is the reduction in strength caused by certain tie-offs (such as using knots, tying around sharp edges, etc.) and maximum permitted free fall distance. Also, to be stressed are the importance of inspections prior to use, the limitations of the equipment, and unique conditions at the worksite which may be important in determining the type of system to use.

5 Instruction considerations:

Employers should obtain comprehensive instructions from the supplier as to the system's proper use and application, including, where applicable:

- The force measured during the sample force test;
- The maximum elongation measured for lanyards during the force test;
- The deceleration distance measured for deceleration devices during the force test;
- d. Caution statements on critical use limitations;
- e. Application limits;
- f. Proper hook-up, anchoring and tie-off techniques, including the proper dee-ring or other attachment point to use on the body harness for fall arrest;
- a. Proper climbing techniques:
- Methods of inspection, use, cleaning, and storage; and
- Specific lifelines that may be used. This information should be provided to employees during training.

6 inspection considerations:

Personal fall arrest systems must be regularly inspected. Any component with any significant defect, such as cuts, tears, abrasions, mold, or undue stretching; alterations or additions which might affect its efficiency; damage due to deterioration; contact with fire, acids, or other corrosives; distorted hooks or faulty hook springs; tongues unfitted to the shoulder of buckles; loose or damaged mountings; nonfunctioning parts; or wearing or internal deterioration in the ropes must be withdrawn from service immediately, and should be tagged or marked as unusable, or destroyed.



Fall Protection System Considerations cont'd

7 Rescue considerations:

When personal fall arrest systems are used, the employer must assure that employees can be promptly rescued or can rescue themselves should a fall occur. The availability of rescue personnel, ladders or other rescue equipment should be evaluated. In some situations, equipment that allows employees to rescue themselves after the fall has been arrested may be desirable, such as devices that have descent capability.

8. Tie-off considerations:

- a. One of the most important aspects of personal fall protection systems is fully planning the system before it is put into use. Probably the most overlooked component is planning for suitable anchorage points. Such planning should ideally be done before the structure or building is constructed so that anchorage points can be incorporated during construction for use later for window cleaning or other building maintenance. If properly planned, these anchorage points may be used during construction, as well as afterwards.
- b. Employers and employees should at all times be aware that the strength of a personal fall arrest system is based on its being attached to an anchoring system which does not significantly reduce the strength of the system (such as a properly dimensioned eye-bolt/snap-hook anchorage). Therefore, if a means of attachment is used that will reduce the strength of the system, that component should be replaced by a stronger one, but one that will also maintain the appropriate maximum arrest force characteristics.
- c. Tie-off using a knot in a rope lanyard or lifeline (at any location) can reduce the lifeline or lanyard strength by 50 percent or more. Therefore, a stronger lanyard or lifeline should be used to compensate for the weakening effect of the knot, or the lanyard length should be reduced (or the tie-off location raised) to minimize free fall distance, or the lanyard or lifeline should be replaced by one which has an appropriately incorporated connector to eliminate the need for a knot.
- d. Tie-off of a rope lanyard or lifeline around an "H" or "I" beam or similar support can reduce its strength as much as 70 percent due to the cutting action of the beam edges. Therefore, wire core leading edge lifeline should be used around the beam; or the lanyard or lifeline should be protected from the edge with leading edge softeners; or free fall distance should be greatly minimized.



Fall Protection System Considerations cont'd

- e. Tie-off where the line passes over or around rough or sharp surfaces reduces strength drastically. Such a tie-off should be avoided or an alternative tie-off rigging should be used. Such alternatives may include use of a snap-hook/dee-ring connection, wire rope tie-off, an effective padding of the surfaces, or an abrasion-resistance strap around or over the problem surface. Consider the leading edge lifelines for these applications.
- f. Horizontal lifelines may, depending on their geometry and angle of sag, be subjected to greater loads than the impact load imposed by an attached component. When the angle of horizontal lifeline sag is less than 30 degrees, the impact force imparted to the lifeline by an attached lanyard is greatly amplified. For example, with a sag angle of 15 degrees, the force amplification is about 2:1 and at 5 degrees sag, it is about 6:1. Depending on the angle of sag, and the line's elasticity, the strength of the horizontal lifeline and the anchorages to which it is attached should be increased a number of times over that of the lanyard. Extreme care should be taken in considering a horizontal lifeline for multiple tie-offs. The reason for this is that in multiple tie-offs to a horizontal lifeline, if one employee falls, the movement of the falling employee and the horizontal lifeline during arrest of the fall may cause other employees to also fall. Horizontal lifeline and anchorage strength should be increased for each additional employee to be tied-off. For these and other reasons, the design of systems using horizontal lifelines must only be done by qualified persons. Testing of installed lifelines and anchors prior to use is recommended.
- g. The strength of an eye-bolt is rated along the axis of the bolt and its strength is greatly reduced if the force is applied at an angle to this axis (in the direction of shear). Also, care should be exercised in selecting the proper diameter of the eye to avoid accidental disengagement of snap-hooks not designed to be compatible for the connection.
- b. Due to the significant reduction in the strength of the lifeline/lanyard (in some cases, as much as a 70 percent reduction), the sliding hitch knot should not be used for lifeline/lanyard connections except in emergency situations where no other available system is practical. The "one-and-one" sliding hitch knot should never be used because it is unreliable in stopping a fall. The "two-and-two," or "three-and-three" knot (preferable), may be used in emergency situations; however, care should be taken to limit free fall distance to a minimum because of reduced lifeline/lanyard strength.

Vertical lifeline considerations.

As required by the standard, each employee must have a separate lifeline when the lifeline is vertical. The reason for this is that in multiple tie-offs to a single lifeline, if one employee falls, the movement of the lifeline during the arrest of the fall may pull other employees' lanyards, causing them to fall as well.



Fall Protection System Considerations cont'd

10. Snap-hook considerations:

- a. Required by this standard for all connections, locking snap-hooks incorporate a positive locking mechanism in addition to the spring loaded keeper, which will not allow the keeper to open under moderate pressure without someone first releasing the mechanism. Such a feature, properly designed, effectively prevents roll-out from occurring.
- b. The following connections must be avoided (unless properly designed locking snap-hooks are used) because they are conditions which can result in roll-out when a nonlocking snap-hook is used:
 - Direct connection of a snap-hook to a horizontal lifeline.
 - Two (or more) snap-hooks connected to one dee-ring.
 - Two snap-hooks connected to each other.
 - A snap-hook connected back on its integral lanyard.
 - A snap-hook connected to a webbing loop or webbing lanyard.
 Improper dimensions of the dee-ring, rebar, or other connection point in relation to the snap-hook dimensions which would allow the snap-hook keeper to be depressed by a turning motion of the snap-hook.

11 Free fall considerations:

The employer and employee should at all times be aware that a system's maximum arresting force is evaluated under normal use conditions established by the manufacturer, and in no case using a free fall distance in excess of 6 feet (1.8 m). A few extra feet of free fall can significantly increase the arresting force on the employee, possibly to the point of causing injury. Because of this, the free fall distance should be kept at a minimum, and, as required by the standard, in no case greater than 6 feet (1.8 m). To help assure this, the tie-off attachment point to the lifeline or anchor should be located at or above the connection point of the fall arrest equipment to harness. (Since otherwise additional free fall distance is added to the length of the connecting means (i.e., lanyard).) Attaching to the working surface will often result in a free fall greater than 6 feet (1.8 m). For instance, if a 6-foot (1.8 m) lanyard is used, the total free fall distance will be the distance from the working level to the body harness attachment point plus the 6 feet (1.8 m) of lanyard length. Another important consideration is that the arresting force that the fall system must withstand also goes up with greater distances of free fall, possibly exceeding the strength of the system.



Fall Protection System Considerations cont'd

Elongation and deceleration distance considerations.

Other factors involved in a proper tie-off are elongation and deceleration distance. During the arresting of a fall, a lanyard will experience a length of stretching or elongation, whereas activation of a deceleration device will result in a certain stopping distance. These distances should be available with the lanyard or device's instructions and must be added to the free fall distance to arrive at the total fall distance before an employee is fully stopped. The additional stopping distance may be very significant if the lanyard or deceleration device is attached near or at the end of a long lifeline, which may itself add considerable distance due to its own elongation. As required by the standard, sufficient distance to allow for all of these factors must also be maintained between the employee and obstructions below, to prevent an injury due to impact before the system fully arrests the fall. In addition, a minimum of 12 feet (3.7 m) of lifeline should be allowed below the securing point of a rope grab type deceleration device, and the end terminated to prevent the device from sliding off the lifeline. Alternatively, the lifeline should extend to the ground or the next working level below. These measures are suggested to prevent the worker from inadvertently moving past the end of the lifeline and having the rope grab become disengaged from the lifeline.

Obstruction considerations:

The location of the tie-off should also consider the hazard of obstructions in the potential fall path of the employee. Tie-offs that minimize the possibilities of exaggerated swinging should be considered.

14. Other considerations:

Because of the design of some personal fall arrest systems, additional considerations may be required for proper tie-off. For example, heavy deceleration devices of the self-retracting type should be secured overhead in order to avoid the weight of the device having to be supported by the employee. Also, if self-retracting equipment is connected to a horizontal lifeline, the sag in the lifeline should be minimized to prevent the device from sliding down the lifeline to a position that creates a swing hazard during fall arrest. In all cases, manufacturer's instructions should be followed.



Forklift Pre-Use Inspection

Mod	elt			Equipment Number:				
lom	pany:			Hour Meter	r			
	DATE:		7					
	Initials of person performing inspection:						-	
he sa and a	he operator been instructed in afe operation of this type of lift re they certified?	Y/N	Y/N	Y/N	V/N	Y/N-	Y/N	Y/N
	ection Item &	P/F	P/F	P/F	P/F	P/F	P/F	P/F
Desc	cription (Pass / Fail)		246		- (4	r /r	1/1	17.5
	PRESTART		-					
1	Fork Assembly Structure		1			I		
2	Mast/Boom		1					
3	Hydraulic Lines**							
4	Wheels/Tires**							
5	Axles/Under Carriage		-	1	-			
6	Placards (legible)							
7	Roll Cage - Structural							
8	Operator's Manual		Į.					
9	Engine Compartment							
10	All Fluid Levels							
11	Belts		2					
12	Winng					7 7 1		
13	Leaks/Hoses**		, , , , , , , , , , , , , , , , , , , ,					
	START-UP							
1	Seat Belt**		L -					
2	All Gauges							
3	Warning Signs/Placards							
4	Steering (loose)**		c' -				1	
5	Levers/Switches							
6	Lights/Backup Alarm*							
7	Hom**							
	FUNCTION CHECK							
1	Lift up/down**							
2	Telescope in/out**							
3	Tilt in/out **							
5	Outriggers Dealers Dealers Dealers*							-
_	Brakes, Parking Brake** If any Item(s) are found to be	missing or i	defective, the	equipment is t	o he repaired	serviced prior	to use.	L'
	efects Reported			- 1			20,720	
0:_				Date			_	
in T	aken Out of Service	☐ Yes		□ No	0/		-3-	
R	epairs Made							
Ву:				Date	si.			

WARNING

HOT WORK IN PROGRESS

WATCH FOR FIRE!

Permit is not valid until signed by authorized BNB Supervisor Complete form and return to BNB for signature Hot Work Supervisor must verify precautions on check list IN CASE OF EMERGENCY CALL 911 INSTRUCTIONS:

Approved Permit must be visibly posted in vicinity of hot work

Hot Work Done By:		Explosive atmosphere in are
Employee:		Floors swept clean. Trash p
Company:		Combustible floors wet dow
Date:		Remove all combustible mar
Project:		Protect combustibles with F
Location (bldg/fir):		All wall, floor, conduits and
Work Description:		Fire-resistive tarps suspende
		WORK ON WALL OR CEILINGS
rexa avey Teyt Ajpav	I verify that I have examined the above location and ensured all the precautions	Construction is noncombust
indicate	indicated on the Hot Work Permit have been taken	Combustibles on other side
	to prevent fire	WORK ON ENCLOSED EQUIPM
Hat Wark Supervisor		Enclosed equipment cleared
Signature		Containers purged of flamat
		Are respirators or ventilation
it bawaiyar ayad i	I have reviewed this Permit request and authorize the work to proceed	FIRE WATCH/HOT WORK AREA
for as long	for as long as permit is valid and the conditions stated	FW will be provided during a
	in permit are maintained	FW Trained in use of extings
BNB Supervisor		FW Supplied with proper fin
Signature		
Permit Expires	Required Fire Watch Duration After Hot Work	
Date	30 min 60 min 120 min	Work area was monitored for
Time: AM/PM	Other	following not work and found fire safe

Sign

30 min

60 min

120 min



HOT WORK PERMIT

Code: Oper-20A

Rev. 1

Date: Jun -19

BEFORE INITIATING HOT WORK, CAN HOT WORK BE AVOIDED?

or producing heat and/or sparks. This includes, but is not limited to: Brazing, Cutting, Grinding, This Hot Work Permit is required for any operation involving open flames Soldering, Thawing Pipe, Torch Applied Roofing & Welding.ss

FW Supplied with proper fire extinguishers, hoses, spray cans and equipment.
FW Trained in use of extinguishing equip, and in sounding fire atarms.
FW will be provided during and for the time specified after hotwork
WATCH/HOT WORK AREA MONITORING
Are respirators or ventilation required?
Containers purged of flamable, liquids/vapors.
Enclosed equipment cleared of combustibles.
ON ENCLOSED EQUIPMENT
Combustibles on other side of walls moved away.
Construction is noncombustible and w/o combustible covering or insulation
WORK ON WALL OR CEILINGS
fire-resistive tarps suspended beneath work.
All wall, floor, conduits and pipe openings are covered.
Protect combustibles with fire-resistive tarps or metal shields
Remove all combustible material if possible (wood, cardboard, etc)
Combustible floors wet down, covered with damp sand or fire-resistive blankets.
Floors swept clean. Trash picked up.
Explosive atmosphere in area eliminated.
Identity sprinkler/Gas lines in work area to PROTECT!
REQUIREMENTS WITHIN 35FT OF WORK
Venify if local codes or client have stricter requirements
Hotwork equipment inspected and in good condition.
Available sprinklers, hose streams and extinguishers are serviced/operable.


DIVI	K	10	CIDE	NT DE	000	-			Cod: INC	-01B
nanntine.	"	IIN	ICIDE	NT RE	PUK				Rev. 1	5ep-19
NCIDEN	NT INFORMA	TION						7	*	
DATE	6/16/2020	TIME		AM	PM		s the employe	e doing just		
ROJECT		SUPERINT	ENDENT				d the inciden	ncour?		
NCIDEN	UT TVDE	Mine transmitted	Mari	vice i	NG.				Machine 26	i i i i i i
NCIDEN	NT TYPE	Non-Recordable	ivear	Miss	Prio	perty Dam	age	Onsite First ald	Worker's	comp
Submit	PTP and photos	DSHA Recordable	Medical 1	Freatment	M	odified Wo	rik .	Lost time	# Days:	
Any Emerge Police, etc.)		ed? If yes, who (EMS.			Wasa	post Incide	nt drug & alco	ahol test performed?		
		R INVOLVED IN	INCIDE	TV		7				
lame				Employer				Supervisor Name		
, and				1				1		
litle				Time wor	king on			Years of experience		
		Constant		project				Approx. cost of		
Jamaged	property (If app	ilicable)						damages		
SPECIFIC	C PART(S) O	F BODY INJURED) (includ	le locatio			r, etc.)			
	C PART(S) O	F BODY INJURED) (includ	le locatio	on-rigi N/A		er, etc.)			
YPE OF	FINJURY	h - 11 - 15	O (includ	le locatio	N/A		r, etc.)	Amputation		
YPE Of aceration ye injury	FINJURY	Fra St	cture rain	le locatio	N/A Con	-	r, etc.)	Amputation Other		
YPE Of aceration ye injury	F INJURY	Frai St S Check all that	cture rain apply		N/A Con Bi	tusion urns		Other		
YPE OF accration ye injury MMED	F INJURY IATE CAUSE Unsafe Acts	Frai St S Check all that Check	cture rain apply Unsi	afe conditi	N/A Con Bi	tusion	Relate	Other d to Supervision / C		Yes/N
YPE OF acceration ye injury MMED iy-passing	F INJURY INJURY INTE CAUSE Unsafe Acts g safety devices	Frai St S Check all that Check	cture raiñ opply Uns i Congester	afe conditi d work are:	N/A Con Bi	tusion urns	<i>Relate</i> . Was the En	Other		100
YPE OF aceration ye injury MMED My-passing orug or ale	IATE CAUSE: Unsafe Acts g safety devices cohol use	Frai St S Check all that Check	cture rain apply Uns Congester Defective	afe conditi d work area tools/equi	N/A Con Bi	tusion urns	Relate Was the En	Other d to Supervision / Comployee performing	an scheduled	N/A
YPE OF acceration ye injury MMED by-passing brug or all excess equ	FINJURY INTERPORT OF THE PROPERTY OF THE PROP	Frai St S Check all that Check	cture rain apply Unsi Congester Defective Excessive	afe conditi d work area tools/equi noise	N/A Con Bi ons a pment	tusion urns	Relate Was the En task? Was a PTP	Other d to Supervision / Comployee performing completed for this 1	an scheduled	N/A
TYPE OF acceration ye injury MMED By-passing Orug or ale excess equal	IATE CAUSE: Unsafe Acts g safety devices cohol use	Frai St S Check all that Check	cture rain apply Unsi Congester Defective Excessive Fire/explo	afe conditi d work area tools/equi noise osion hazar	N/A Con Bo ons a pment	tusion urns	Relate Was the En task? Was a PTP If PTP comp	Other d to Supervision / Comployee performing completed for this toleted, did it accura	an scheduled ask? tely account for,	N/A N/A
TYPE OF acceration ye injury MMED By-passing orug or ale excess equallure to atigue	FINJURY INTERPORT OF SECURE INTERPORT OF SECURE	Frai St S Check all that Check	cture rain opply Unsi Congester Defective Excessive Fire/explo	afe condition d work area tools/equi noise osion hazar s substance	N/A Con Bo ons a pment	tusion urns	Relate Was the En task? Was a PTP If PTP comp and plan m	Other d to Supervision / Comployee performing completed for this toleted, did it accurating action for, the ha	an scheduled ask? tely account for,	Yes/N N/A N/A
aceration ye injury MMED by-passing orug or ale access equ atigue ack of for	FINJURY INTECAUSE: Unsafe Acts g safety devices cohol use uipment speed warn or secure	Frai St S Check all that Check	cture rain opply Unsi Congester Defective Excessive Fire/explo Hazardou	afe condition d work erectools/equitools/equitoolse posion hazar s substance storage	N/A Con Bi ons a pment d	tusion urns	Relate Was the En task? Was a PTP If PTP comp and plan in with the ta	Other d to Supervision / Comployee performing completed for this to bleted, did it accurating action for, the hask?	an scheduled ask? tely account for, zards associated	N/A N/A N/A
TYPE OF acception to the control of	FINJURY INTERPORT OF THE PROPERTY OF THE PROP	Frai St S Check all that Check	cture rain opply Unsi Congester Defective Excessive Fire/explo Hazardoul Improper	afe condition If work area tools/equivalence toolse tool/equip	N/A Con Bi ons a pment d es	tusion urns	Relate Was the En task? Was a PTP If PTP comp and plan in with the ta-	Other d to Supervision / Comployee performing completed for this to bleted, did it accurating allows for, the hask?	an scheduled ask? tely account for, zards associated	N/A N/A
TYPE OF acceration ye injury MMED or alcohold access equally equ	INJURY INTERPORT OF THE PROPERTY OF THE PROPE	Frai St S Check all that Check	cture rain opply Unsi Congester Defective Excessive Fire/explo Hazardoul Improper Improper	ofe condition If work area tools/equinoise posion hazar s substance storage tool/equip te fall prote	N/A Con Bi ons a pment d es	tusion urns	Relate Was the En task? Was a PTP If PTP comp and plan in with the ta Was approj	Other d to Supervision / Comployee performing completed for this to bleted, did it accurating at long the hask? private training provides this task?	an scheduled ask? tely account for, zards associated ded to	N/A N/A N/A
aceration ye injury MMED By-passing Orug or ale excess eque aligue ack of foo	INJURY INTERPORT OF THE PROPERTY OF THE PROPE	Frai St S Check all that Check	cture rain opply Unsi Congester Defective Excessive Fire/explo Hazardoul Improper Improper Inadequat	ofe condition If work area tools/equitousion hazar s substance storage tool/equip te fall prote te guarding	N/A Con Bi ons a pment d es	tusion urns	Relate: Was the Entask? Was a PTP If PTP compand plan in with the ta: Was approj accomplish	Other d to Supervision / Comployee performing completed for this to be to be the completed for the bask? private training provides the complete training provides the complete training to be the complete training training to be the complete training training to be the complete training trainin	an scheduled ask? tely account for, zards associated ded to	N/A N/A N/A
TYPE OF acceration acceration by injury immediately access equally access equally access equally access for access	PPE or PPE not	Frai St S Check all that Check	cture rain opply Unsi Congester Defective Excessive Fire/explo Hazardou Improper Improper Inadequat Inadequat	ofe condition If work area tools/equitous noise sison hazar s substance storage tool/equip te fall prote te guarding te ventilation	N/A Con Bi ons a pment d es	tusion urns	Relate Was the Entask? Was a PTP If PTP compand plan in with the ta Was approlactomplish Was there required ta	Other d to Supervision / Comployee performing completed for this to be to be the completed for the half of the half of the half of the half of the training provides the training provides task? adequate staffing to sk(s) or operation?	an scheduled ask? tely account for, zards associated ded to perform the	N/A N/A N/A
aceration ye injury MMED By-passing Orug or ale excess equivalent actique ack of focus ack of focus mproper mproper mproper	INJURY INSUFE CAUSE Unsafe Acts g safety devices cohol use uipment speed warn or secure out used lifting / loading loading PPE or PPE not work technique	Frai St S Check all that Check	cture rain apply Unsi Congester Defective Excessive Fire/explo Hazardou Improper Improper Inadequat Inadequat Insufficien	ofe condition d work area tools/equinoise osion hazar s substance storale tool/equip te fall prote te guarding te ventilation	N/A Con Br ons a pment d es ment ection g on	tusion urns	Relates Was the Entask? Was a PTP If PTP compand plan in with the paraccomplish Was there required ta Were there	Other d to Supervision / Comployee performing completed for this I bleted, did it accura itigation for, the hask? priate training provi this task? adequate staffing to sk(s) or operation? adequate policies,	an scheduled ask? tely account for, zards associated ded to perform the or other written	N/A N/A N/A N/A
TYPE OF aceration Eye injury MMED By-passing Orug or alc excess equivalence to adjure to adjure to adjure to more for fore more fore fore more fore fore fore fore fore fore fore fore	PPE or PPE not	Frai St S Check all that Check	cture rain apply Unsi Congester Defective Excessive Fire/explo Hazardou Improper Improper Inadequat Inadequat Insufficien	ofe condition d work area tools/equip noise osion hazar s substance storal/equip te fall prote te guarding te ventilation t lighting	N/A Con Br ons a pment d es ment ection g on	tusion urns	Relates Was the Entask? Was a PTP If PTP compand plan in with the paraccomplish Was there required ta Were there	Other d to Supervision / Comployee performing completed for this to betted, did it accurating according to the hask? printe training provides task? adequate staffing to sk(s) or operation? I adequate policies, stor the required task.	an scheduled ask? tely account for, zards associated ded to perform the or other written	N/A N/A N/A

Other:					within the past week?							N/A	
TYPE OF INCIDENT Describe	e details												
Struck or Injured by			Striking Ag On	ainst or Stepping		Cut, Pu	ınctı	ıre	, Scrape I	njury By			
Strain or Injury By			Caught In o	or Between	Foreign	Foreign body in eye							
Fall or Slip Injury	or Slip Initiry			Other: Vehicle incidnt									
POTENTIAL OUTCOME													
SEVERITY		Choose b	etween 1-5	PROBABILITY What is the chance of		se between 1-5		Calculate Potential Outcome Severity * Probability					e
How bad could the accident hav	e been?		1	the accident happening again?		4				Calculate Potential Outcome Severity * Probability MEDIUM FETY AND HEALTH RISK MA SEVERITY 2 3 4 MEDIUM HIGH LOW MEDIUM VERY LOW LOW MI			
-								E	BNB SAFE			ISK M	ATRIX
 Noticeable: Minor first aid. F 	roperty l	ioss <\$5K		 Practically impossi 	ble			_			ERITY		
								Ц	1	2	3	4	5
2. Serious: Medical treatment. Property loss \$5K-\$50K 3. Very serious: Work restrictions ≤6 weeks. Property Loss			50K	2. Very unlikely				5 4	MEDIUM	ню	GH CRIT		CRITICAL
3. Very serious: Work restrictions ≤6 weeks. Property Loss \$50K-\$100K			rty Loss	3. Unusual but possible			ABILI	3	row	MEDIUM	HIGH		
4. Critical: Partial disability. Los \$100K-\$1MM	it time >6	i weeks. Pr	operty loss	4. Quite possible			PROB	2		LOW	MEDIUM	7	nign
5. Catastrophic: Total permane loss >\$1MM	nt disabi	lity. Death.	Property	5. Almost certain				1	VERY LOW	VERY LOW	LOW	,	MEDIUM
truck or Injured by Striking Against or Stepping On Cut, Puncture, Scrape Injury By train or Injury By Caught In or Between Foreign body in eye Burn or Exposure to Heat/Cold Other: Vehicle incidnt Choose between 1-5 PROBABILITY What is the chance of the excident hove been? 1 PROBABILITY What is the chance of the excident hove been? 1 PROBABILITY What is the chance of the excident hove been? 1 Practically impossible BNB SAFETY AND HEALTH RISK MATRIX SEVERITY Serious: Medical treatment. Property loss <\$5K. Serious: Work restrictions <6 weeks. Property Loss 3. Unusual but possible Catastrophic: Total permanent disability. Lost time >6 weeks. Property loss 5. Almost certain Cut, Puncture, Scrape Injury By Catastrophic incidnt Calculate Potential Outcome Severity * Probability Footstant Again to Severity * Probability Calculate Potential Outcome Severity * Probability Again to Severity * Probability BNB SAFETY AND HEALTH RISK MATRIX SEVERITY 1 2 3 4 5 MEDIUM HIGH CHITICAL VERY LOW MEDIUM WERLIUM LOW MEDIUM WERLIUM LOW MEDIUM WERLIUM LOW MEDIUM WERLIUM LOW MEDIUM MEDIUM MEDIUM WERLIUM LOW MEDIUM WERLIUM LOW MEDIUM MEDIUM MEDIUM WERLIUM LOW MEDIUM WERLIUM LOW MEDIUM WERLIUM LOW MEDIUM MEDIUM MEDIUM WERLIUM LOW MEDIUM WERLIUM LOW MEDIUM WERLIUM LOW MEDIUM MEDIUM MEDIUM WERLIUM LOW MEDIUM MEDIUM MEDIUM WERLIUM LOW MEDIUM WERLIUM LOW MEDIUM WERLIUM LOW MEDIUM WERLIUM LOW MEDIUM MEDIUM MEDIUM WERLIUM LOW MEDIUM WERLIUM LOW MEDIUM MEDIUM MEDIUM WERLIUM LOW MEDIUM MEDIUM LOW MEDIUM MEDIUM LOW MEDIUM WERLIUM LOW MEDIUM MEDIUM LOW MEDIUM LOW MEDIUM MEDIUM LOW MEDIUM LOW MEDIUM MEDIUM LOW M													
Det	tails			Deadl	ine				Re	esponsible	;		Complete
Prepared by													



Health, Safety, and Environmental Manual

"Freedom from Danger"



Job Hazard Analysis



					WORK ACTIVITY SEQUENCE			DESCRIPTION OF WORK:		ACTIVITY:
	*	* * 4		* 3 *	POTENTIAL HEALTH & SAFETY HAZARDS					
* * *	* * *	***	* * *	* * *						
					HAZARD CONTROLS	REVIEW FOR LATEST USE:	REVIEWED BY:	SITE SUPERVISOR:	PROJECT:	DATE:



SASSTY DESIGNED'S PRINTED NAME	SUPERVISOR'S PRINTED NAME						EMPLOYEE PRINTED NAME
SAFETY DEFICED'S SIGNATION	SUPERVISOR'S SIGNATURE						EMPLOYEE SIGNATURE
DATESTIME	DATE/TIME						DATE/TIME



RNR	NEAD MICE	NEAR MISS REPORT			
SNBuilders	NEAR MISS H	VEAR MISS REPORT		May-18	
a slippery surface, et	completed by an employee who wi c. The completed form should be t thout injury to person or damage t	urned in to the project supervisi		height, slip	
Date/Time:	Project:	Exact location:			
Root Causes					
LESSONS LEARNED				-	
What could be done	to prevent future occurrences	A			
2					

Title

Reported by

Subcontractor employee Employer Vate Written Warning Toject Removal from site Permane Granture Oreman Termination Name Employer Written Warning Days # Permane Granture (Only BN
roject Days # mployee ignature Oreman Tarmination (Only BN
mployee granture Removal from site Permane (Only BN
ignature Conly BN
oreman Tarmination (Only BA
ignature employe
Pescription (1997)

Distribution of signed copies: Subcontractor: CC to PM for subcontractor

BNB: CC to HR

BNB	DAILY PRE-TASK PLAN	h	0000	AHEA
Company	Project / Job	Date	Rev. 0	Jul-16

	Hazarde	Even ?	Harards-	Extent/7
		165 190		Yes No
Falls			Noise	
From Height			Vibration	
On to hazard			Fire	1 11 11 1
Of objects			Flammables / Combustibles	
(Other)			Ignition Sources	
Electric Shock			(Other)	
Overhead, Buried, H	lidden Lines		Chemicals	
Cords / Leads			Dust	
Power Sources			Fumes / Gases / Vapors	
(Other)			Toxic / Allergenic	
Caught Between			Acid / Caustic	
Swinging / Rotating	Equipment		Explosive / Reactive	
Pinch Points	Egophich		(Other)	
Materials			Buildings / Systems	
Cave in			Charged systems	
(Other)			Hazardous Energy	
Struck by			Stored Energy	
Dropped Objects / L	nade		Hazardous Materials / Chemicals	
Flying Material / De			Confined Spaces	-10-10-
Equipment / Traffic	UIIS		Structural	
Unstable Materials			(Other)	
(Other)			Location	
Walking / Working:	Conference			
	Surfaces		Occupied Space Public at Risk	
Slips / Trips Holes / Uneven Surf	222			
	aces		Asbestos / Lead Mold	- 14
Access / Egress				
(Other)			Hazardous Waste	
Material Handling			Medical Waste	
Overexertion / Strai	ns .		(Other)	- 11 11 11 11 -
Cuts / Punctures			Weather / Environment	
Storage / Stacking			Heat / Cold	
Mechanical Equipm	ent		Lightning	
Hoisting	SIZE		Wind	
Hauling / Road Tran	sport		Visibility	
Floor Loading			(Other)	
(Other)				
THE STATE OF THE S		Landith and Marchite	A POLICE DE LA COLONIA DE LA C	
Head	Hard Hat (Type I, G)	Type II Hat (side impact)		
Eyes	Glasses (ANSI Z87)	The second secon	lined (dust) / Welding / Laser	
Body / Arms	Shirt w/ 4" sleeve		ire / Chemical / Arc Flash / Cut resistant	2
Knees / Legs	Long Pants	Knee Pads / Chaps / chen		
Hands	Light Duty Gloves		Resistant / Chemical / Welding / Therma	
Feet	Sturdy Work Boots		Metatarsal / Electrical / Booties	
Face			Face Shield / Welding Mask	
Ear		Plugs / Muffs / Double		
Breathing		Dust Mask / Filtering Res	pirator / Supplied Air	
Other		14		



DAILY PRE-TASK PLAN

Job / Task Description		

Basia Joli Steps	Hazards	Controls / Work Practices
Describe major tasks in order. What will you be doing? What equipment and tools are needed?	Identify the hazards of each step. What could go wrong? What could cause an accident?	Decide what controls are needed. What safe work practices must be used for each hazard? What training is required?
Preysoned by:	Crew Member Signatures	Ours / Time:
		=======================================
Ì		
12		

BNB	Análisis Previo al T	rabajo	Crebre	CONC. NO.
Contratista	Proyecto	Fecha	Rev. 0	Jul-16

	Riesgos	Sins	e7	Riesgos	Eniste
		3.	No.		5 1
Caldas				Ruido	
De altura				Vibracion	
A mismo nivel				Fuego	4
De objetos				Inflamables / Combustibles	
(Otra opción)				Fuentes de ignición	10 20
Chaque Eléctrico	2000			(Otra opción)	
Líneas aéreas / enti	erradas		1 3	Quimicos	
Cordones / Cables /	/Alambre			Polvo	
Fuentes de energía	T			Humos/Gases/Vapores	
(Otra opción)				Tóxico / Alergénico	
Atrapamiento entr	8			Ácido / Cáustico	
Equipo giratorio/ro	tatorio			Explosivo / Reactivo	
Puntos de atrapam	iento			(Otra opción)	
Materiales				Edificios / Sistemas	
Derrumbe				Sistemas cargados	
(Otra opción)				Energia peligrosa	
Golpeado por				Energía almacenada	
Caídas de objetos /	Cargas			Materiales peligrosos / Químicos	
Material suelto / Es	combros		0 - 1	Espacios confinados	
Equipo / Tráfico				Estructural	
Material inestable		11-1		(Otra opción)	
(Otra opción)			100	Uhicación	
Pasadizos/ Platafor	rmas de trabajo			Espacio ocupado	
Resbalones / Tropie			1.31	Riesgos para el público	
Huecos / Superficie	desnivelada		1.70	Asbesto / Plomo	
Acceso / Salida			170	Moho	
(Otra opción)				Residuos peligrosos	
Manejo de materia	les			Residuos médicos	
Fatiga / Esguince m				(Otra opción)	=======================================
Cortes / Pinchazos				Clima / Ambiente	
Almacenamiento /	Apilado			Calor / Frio	1
Equipo mecánico	OR HENRY			Relámpago/Rayo	
Levantamiento				Viento	
Transporte/ Transp	orte por carretera	1 1		Visibilidad	
Carga sobre el suel				(Otra opción)	
(Otra opción)				Comment of the state of the sta	
(sansi opcion)	1909 Repumber	Saura administration	i lime	n)	
Cabeza	Casco (Tipo I, G)			eral) / Tipo E (protección eléctrica)	
Ojos	Lentes (ANSI Z87)			forrada / Soldadura / Láser	
Cuerpo / brazos	Camisa de mangas 4"			eco / Fuego / Químico / Resistente al corte	
Rodillas / Piernas	Pantalones largos	Rodilleras / Chaps /			
Manos	Guantes ligeros			ente al corte / Químico / Soldadura / Protec	ción térmica
Pies	Botas de trabajo			acero / Metatarsiano / Electrica / Cubiert	
Cara	pores de trabalo				
2			_	Protector facial de malla / Máscara soldado	Ira
Orejas	+	Tapones / Orejeras			and the state of t
Respiración Otra opción	4	Mascara de polvo /	Kespi	rador purificador de aire / Respirador de al	re suministrado

n	AT	n
ĸ	N	ĸ
-	•••	_

Análisis Previo al Trabajo

Descripción del trabajo / tarea

Pasos de trabajo	Riesgos	Metados de control
Describa los pasos en orden. Qué va a hacer usted? Qué clase de equipos y herramientas son nécesarias?	Identifica los riesgos de cada paso. Qué podria salir mai? Que podria causar un accidente?	Cómo protegemos a los trabajadores? Cuáles son las practicas seguras de cada paso? Qué capacitación es necesaria?
Neparado por		Fechs / Marai
	Firma de los trabajadore	s
		1.0

Synthetic Web and Roundsling Inspection Form

Company:	1,7		H	Date				Ţ		7 2 7
o o o				major oy.					Medi	
Туре	Size	Serial #	Ok	Manufactured By:	Scrap	Carista File de Adrasion	Misirifical Hole Space Chee Conse	Still Hear	Other Other	Comments
	Ħ							Ħ	Ħ	
		H _U	Ï							
		0.4								
		ŕ								
		-								
								9		
									4	
		+								
		5		0						
			-					-		



DAILY SCAFFOLD CHECKLIST

Code #	Oper-27A
Rev	0
Date	October-2017

Company:	Inspected By:
Location:	Supervisor:

The following items should be visually checked prior to working from any scaffolding (daily).

1.	Is the footing of the scaffolding sound and rigid, capable of supporting the weight. (Bricks or blocks are not acceptable)	Yes	No	N/A
2.	Did a competent person erect, dismantle or move the scaffold?			
3.	Are all the scaffold components the same manufacturer and type?			
4.	is a complete guardrail system in place? i.e. top rail (42"), midrail (22"), and toe boards (2x4 min.).			
51	Were damaged scaffold components repaired or replaced?			
6.	Is the maximum span for 2"x12" planks 8 ft.			
7	Is all planking or platforms overlapped by a minimum of 12", and secured from movement?			
8.	Is there an access ladder, stairs or other safe means of access?			
9.	Do the scaffold planks extend over their end supports 6" but not more than 12"?			
10.	Is there overhead protection provided for people on scaffold exposed to overhead hazards?			
11.	Is fall protection feasible to use when erecting scaffold?			
	Are the poles, legs, or uprights of the scaffold, plumb and rigidly braced to prevent swaying and displacement?			
13.	Is the scaffold properly braced by cross-bracing or diagonal braces, or both, for securing vertical timbers together?			
14.	Where uplift may occur, are vertical members locked together by pins or other equivalent suitable means?		1.0.0	
15.	is scaffold level and plumb?	-		
	Are sills properly placed and adequate size?			
17,	Have screw jacks been used to level and plumb scaffold, instead of unstable objects (concrete blocks, bricks, etc.)?			
18.	Are base plates and/or screw jacks secured to sills and frame?			
	s the scaffold securely guyed or tied to a building or structure, when the the exceeds four times its minimum base dimension?			
_	Has scaffold been tied to structure at least every 30 feet in length and 26 feet in height?			
21.	is each work deck fully planked?	= =		
	is handrail netting or covered walkway installed if workers pass through or under the scaffold?			
21,	Have workers on scaffold been trained on scaffold safety?			



SHAFT WORK ENTRY PERMIT

Code #	Oper-14B
Rev.	O.
Date	Jan-2018
Original Date	Jan-2018

NOTICE: Wark in the Shaft Requires a JHA and Pre-Task Plan to be completed and all Hazards identified must be mitigated before any work begins. Please attach JHA and PTP to permit.

Company Performing Work:				-
Description of Work:				
Supervisor of Crew in Shaft:	Trade:	Pho	ne Number:	
Complete the below checklist:				
Is the Shaft a Permit Required Confined Sp confined space work permit,	pace? If yes, please complete a	Yes	No	NA .
Tools, materials, and PPE are secured to p the shaft.	revent them from falling down			-
Is each working level with an exposed sha guardrails with installed toe boards, mid- on all levels are closed and secured? Is ver edge to prevent falling materials?	ails and handrails? All Openings			
Lower levels are delineated as necessary v communication?	with a spotter and radio			
Are other crews or trades working next to above floors? If yes, please coordinate wo beginning. Radio communication must be Comments:	rk with the other crew before			
is there adequate lighting to complete rec	uired task?			
Is Hot Work being performed? If yes, please	se complete a Hot Work Permit.		-	1
Is there proper access and egress to work	locations?			
Comments:				



SHAFT WORK ENTRY PERMIT

Code #	Oper-14B
Rev.	0
Date	Jan-2018
Original Date	Jan-2018

Authorized Participants: (Attach additional Authorized Participants on separate sheet if necessary)

Print Name	Signature	Company
Print Name	Signature	Company

This Shaft Entry Permit and associate JHA and Pre-Task Plans have been reviewed and authorized by:	
BNBuilders Superintendent:	
BNBuilders Project Manager:	

315					Code #: Oper-31B
Silica Exposure Control	Project:		Start Date:		Rev. 1
	N. S. C.				Date: Nov-2018
Prepared by (Work Supervisor):		Reviewed by (BNB Competent Person):	ompetent Person):		
Passaka Task	Duration	Controls (See reverse side for	Controls e side for examples)	Respiratory	Inside/Outside
Describe Task	(Hours)			Protection	Building
Constitution of the second	(riours)	Engineering	Administrative	(Per Table 1)	Building
Examples: Drilling 5/8" dowel holes with roto-hammer	s with	Shroud, hollow drill bits, dustless attachment	Body positioning	Respirator APF 10 required	Outside
Housekeeping Practices: (See reverse side for examples)					



Engineering controls	Administrative controls
Exhaust fan	Barricades / Signs
LEV (Local Exhaust Ventilation – HEPA)	Work Scheduling
Wetting	Worker Rotation
Partial enclosure	Body Positioning
Full enclosure	Good Hygiene Practices
Shroud	Employee Training
Barriers	Other:
Sweeping Compound	
Other:	
Respiratory Protection Guide	Housekeeping and Hyglene
APF 10 = Any half mask particulate respirator equipped with an N95, R95, or P95 filter, including filtering facepieces. N99, R99, P99, N100, R100, P100 filters may also be used.	Protective Work Glothing
APF 25 = Any powered, air-purifying respirator with a high-efficiency particulate filter, or Any supplied-air respirator operated in a continuous-flow mode	Handwashing before drinking, eating or smoking
APF 50 = Any air-purifying, full-facepiece respirator with an N100, R100, or P100 filter, or Any powered, air-purifying respirator with a tight-fitting facepiece and a high-efficiency particulate filter	Proper dust bag handling and disposal
APF 1000 = Any supplied-air respirator operated in pressure-demand or positive-pressure mode	Other



CONTROLLING SILICA EXPOSURE

BNBuilders

Source: Laborers' Health & Safety Fund of North America, https://www.lhstna.org/Index.cfm/controlling-silica-exposure/lifiber

EQUIPMENT OR TASK	ENGINEERING AND WORK PRAI CONTROL METHODS	CTICE	RESPIRATOR REQUIREMENTS AND MINIMUM ASSIGNED PROTECTION FACTOR (APF) FOR 0-4 HOURS	RESPIRATOR REQUIREMENTS AND MINIMUM ASSIGNED PROTECTION FACTOR (APF) FOR 4+ HOURS
Stationary masonry saws	 Use saw equipped with integrated water system that continuously feeds water to Operate and maintain tool in accordant manufacturer's instructions to minimize dust emissions. 	the blade. ce with	No additional protection required	No additional protection required
Handheld power saws 'Any blade diameter	Use saw equipped with integrated water delivery system that continuously feeds water to the olade. Operate and maintain tool in accordance with manufacturer's instructions to minimize dust.	Indoors / in an enclosed area:	APF 10 required	APF 10 required
	ėmissions.	Outdoors:	No additional protection required	APF 10 required
Handheld power saws for cutting fiber-cement board 'blade diameter of eight (8) inches or less	For tasks performed outdoors only: • Use saw equipped with commercially a collection system. • Operate and maintain tool in accordan manufacturer's instructions to minimize dust emissions. • Dust collector must provide the airflow recommended by the tool manufacture and have a filter with 99% or greater effects.	ce with	No additional protection required	No additional protection required
Walk-behind saws	Use saw equipped with integrated water delivery system that continuously feeds water to the blade. Operate and maintain tool in accordance with manufacturer's	Indoors / in an enclosed area:	APF 10 required	APF 10 required
	instructions to minimize dust emissions.	Outdoors:	No additional protection required	No additional protection required
Rig-mounted core saws or drills	Use tool equipped with integrated water system that supplies water to cutting so Operate and maintain tool in accordant manufacturer's instructions to minimize dust emissions.	urface. ce with	No additional protection required	No additional protection required

Source: Laborers' Health & Safety Fund of North America, https://www.lhsfra.org/index.cfm/controlling-silica-exposure/#fiber

EQUIPMENT OR TASK	ENGINEERING AND WORK PRAC CONTROL METHODS	TICE	RESPIRATOR REQUIREMENTS AND MINIMUM ASSIGNED PROTECTION FACTOR (APF) FOR 0-4 HOURS	RESPIRATOR REQUIREMENTS AND MINIMUM ASSIGNED PROTECTION FACTOR (APF) FOR
Handheld and stand-mounted drills 'including impact, rotary hammer drills	 Use drill equipped with commercially a shroud or cowling with dust collection s Operate and maintain tool in accordange manufacturer's instructions to minimize dust emissions. 	system. ce with	No additional protection required	No additional protection required
	 Dust collector must provide the airflow recommended by the tool manufacture and have a filter with 99% or greater ef filter-cleaning mechanism. 	ficiency and a	0	0
Jackhammers and handheld powered chipping tools	Use a HEPA-filtered vacuum when cleated use tool with water delivery system that supplies a continuous stream or spray of water at the point of impact. OR - Use tool equipped with commercially	indoors / in an enclosed area:	APF 10 required	APF 10 required
	available shroud and dust collection system. Operate and maintain tool in accordance with manufacturer's instructions to minimize dust emissions.	Outdoors:	No additional protection required	APF 10 required
	 Dust collector must provide the airflow recommended by the tool manufacturer, or greater, and have a litter with 99% or greater efficiency and a filter-cleaning mechanism. 		0	
Handheld grinders for mortar removal *for tuckpointing, etc.	 Use grinder equipped with commercial shroud and dust collection system. Operate and maintain tool in accordant manufacturer's instructions to minimize dust emissions. 	ce with	APF 10 required	AFP 25 required
	 Dust collector must provide 25 cubic for (cfm) or greater of airflow per inch of wand have a filter with 99% or greater at cyclonic pre-separator or filter-cleaning 	heel diameter ficiency and a		0
Walk-behind milling machines and floor grinders	 Use machine equipped with integrated w system that continuously feeds water to t surface. 		No additional protection required	No additional protection required
	Operate and maintain tool in accordance with manufacturer's instructions to minimize dust emissions. OR - Use machine equipped with dust collection system recommended by manufacturer.			0
	Operate and maintain tool in accordance with manufacturer's instructions to minimize dust emissions.		0	0
	 Dust collector must provide airflow recormanufacturer, or greater, and have a filte greater efficiency and a filter-cleaning m 	r with 99% or		
	 When used indoors or in an enclosed are HEPA-filtered vacuum to remove loose d passes. 			

Source: Laborers' Health & Safety Fund of North America, https://www.ihstna.org/index.cfm/controlling-silica-exposure/#fiber

EQUIPMENT OR TASK	ENGINEERING AND WORK PRAC CONTROL METHODS	CTICE	RESPIRATOR REQUIREMENTS AND MINIMUM ASSIGNED PROTECTION FACTOR (APF) FOR 0-4 HOURS	RESPIRATOR REQUIREMENTS AND MINIMUM ASSIGNED PROTECTION FACTOR (APF) FOR
the second secon				4+ HOURS
Handheld grinders for uses other than mortar removal	The substantial experience of the s	the grinding	No additional protection required	No additional protection required
	manufacturer's instructions to minimize of Use grinder equipped with commercially available shroud and dust collection system. Operate and maintain tool in accordance with manufacturer's	indoors / in	No additional protection required	APF 10 required
	instructions to minimize dust emissions. Dust collector must provide 25 cubic feet per minute (cfm) or greater of airflow per inch of wheel diameter and have a filter with 99% or greater efficiency and a cyclonic pre-separator or filter-cleaning mechanism.	Outdoors:	No additional protection required	No additional protection required
Heavy equipment and utility vehicles used to abrade or fracture silica-containing materials (e.g.: hoe-ramming, rock ripping) or used during demolition activities involving silica-containing materials	Operate equipment from within an enclose. When employees outside of the cab are the task, apply water and/or dust suppresent necessary to minimize dust emissions.	engaged in	No additional protection required	No additional protection required.
Heavy equipment and utility vehicles for tasks such as grading and excavating *Does not include: demolishing, abrading, or fracturing silica-containing materials	Apply water and/or dust suppressants a to minimize dust emissions. OR - When the equipment operator is the onlinengaged in the task, operate equipment an enclosed cab.	y employee	No additional protection required	No additional protection required

CONTROLLING SILICA EXPOSURE

BNBuilders

Source: Laborers' Health & Safety Fund of North America, https://www.lhstna.org/index.ctm/controlling-silica-exposure/#fiber

EQUIPMENT OR TASK	ENGINEERING AND WORK PRACTICE CONTROL METHODS	RESPIRATOR REQUIREMENTS AND MINIMUM ASSIGNED PROTECTION FACTOR (APF) FOR 0-4 HOURS	RESPIRATOR REQUIREMENTS AND MINIMUM ASSIGNED PROTECTION FACTOR (APF) FOR 4+ HOURS
Dawal dalling place for compress	For tools, performed outdoors only	APF 10 required	APF 10 required
Dowel drilling rigs for concrete	For tasks performed outdoors only. Use shroud around drill bit with a dust collection system. Dust collector must have a filter with 99% or greater efficiency and a filter-cleaning mechanism. Use a HEPA-filtered vacuum when cleaning holes.	APP 10 required	APP 10 required
Vehicle-mounted drilling rigs for rock and concrete	Use dust collection system with close capture hood or shroud around drill bit with a low-flow water spray to wet the dust at the discharge point from the dust collector. OR - Operate from within an enclosed cab and use water for dust suppression on drill bit.	No additional protection required	No additional protection required
Small drivable milling machines fless than half-lane	 Use a machine equipped with supplemental water sprays designed to suppress dust. Water must be combined with a surfactant. 	No additional protection required	No additional protection required
	Operate and maintain machine to minimize dust emissions.	0	0
Lavas dvivable milling machines	•Encourse of pay double on eachelt anker	No additional	No additional
Large drivable milling machines *half-lane and larger	The second of t	No additional protection required	No additional protection required

CONTROLLING SILICA EXPOSURE

BNBuilders

Source: Laborera' Health & Safety Fund of North America, https://www.thslna.org/index.cfm/controlling-silica-exposure/#fiber

EQUIPMENT OR TASK	ENGINEERING AND WORK PRACTICE CONTROL METHODS	RESPIRATOR REQUIREMENTS AND MINIMUM ASSIGNED PROTECTION FACTOR (APF) FOR 0-4 HOURS	RESPIRATOR REQUIREMENTS AND MINIMUM ASSIGNED PROTECTION FACTOR (APF) FOR 4+ HOURS
Crushing machines	 Use equipment designed to deliver water spray or mist for dust suppression at crusher and other points where dust is generated (e.g., hoppers, conveyors, sieves/ sizing or vibrating components, and discharge points). 	No additional protection required	No additional protection required
	 Operate and maintain machine in accordance with manufacturer's instructions to minimize dust emissions. Use a ventilated booth that provides fresh, climate- controlled air to the operator, or a remote 	0	0
Drivable saws	control station. For tasks performed outdoors only: •Use saw equipped with integrated water delivery system that continuously feeds water to the plade. •Operate and maintain tool in accordance with manufacturer's instructions to minimize dust emissions.	No additional protection required	No additional protection required

BNBuilders

Duties of Assigned Personnel

Declarat Name	I Diete 1	
Project Name	Date Mebila Crane Medal	
Tower Crane Model	Mobile Crane Model	
Tower Crane Serial #	Mobile Crane Serial #	
Tower Crane A/D Director		
I have been designated to this position and have real crane.	d and understood the erection/dismantle procedures specific to thi	s tower
Name	Company	
Title	Contact #	
Signature	Date	
Tower Crane Lift Director		
I have been designated to this position and have real crane.	d and understood the erection/dismantle procedures specific to thi	s tower
Name	Company	
Title	Contact #	
Signature	Date	
Qualified Person providing technical assist	ance to the Tower Crane A/D Director	e kausak
i have been designated to this position and have real drane.	id and understood the erection/dismantle procedures specific to thi	s tower
Name	Company	
Title	Contact #	
Signature	Date	
Toward Cooks Observes		
Tower Crane Operator	d and understood the operating procedures specific to this tower of	roine
Name	Company	i di idi
Title	Contact #	
Signature	Date	
Mobile Crane A/D Director	id and understood the erection/dismantle procedures specific to this	e mobile
crane.	a and understood this electronicismanile procedures specific to this	s mobile
Name	Company	
Title	Contact #	
Signature	Date	
Mobile Crane Operator		
	d and understood the operating procedures specific to this mobile	orane
Name	Company	WINE IN
Title	Contact #	
Signature	Date	
BNB Site Supervisor	Company	
Name	Company	
Title Signature	Contact #	
olgitature	Date	
BNB Alternate Site Supervisor		
Name	Company	
Title	Contact #	
Signature	Date	

BNBuilders Duties of Assigned Personnel

BNB 3rd Party Consultant		
Name	Company	
Title	Contact #	
Signature	Date	

Duties of Assigned Personnel - Tower Crane Daily Operation

Project Name	Start Date	
Tower Crane Model	Updated	
Tower Crane Serial #		

	The second secon	
	osition and have read and understood the operation	al procedures speci
to this tower crane.		
Name.	Company	
Title	Contact #	
Signature		
Backup LD's		
Name	Company	
Title	Contact #	
Signature	17 -	
Vame	Company	
Title	Contact #	
Signature		
1		
I have been designated to this p	osition and have read and understood the operating	procedures specific
I have been designated to this p to this tower crane,	Control of the Contro	procedures specific
I have been designated to this p to this tower crane, Name	Company	procedures specific
to this tower crane, Name Title	Control of the Contro	procedures specific
I have been designated to this p to this tower crane, Name Title	Company	procedures specific
I have been designated to this p to this tower crane, Name Title Signature	Company	procedures specific
have been designated to this p to this tower crane. Name Title Signature	Company Contact #	procedures specific
I have been designated to this posto this tower crane, Name Title Signature BNB Site Supervisor	Company Contact # Company	procedures specific
I have been designated to this posto this tower crane. Name Title Signature BNB Site Supervisor Name Title	Company Contact #	procedures specific
I have been designated to this posto this tower crane. Name Title Signature BNB Site Supervisor Name Title	Company Contact # Company	procedures specific
I have been designated to this posto this tower crane. Name Title Signature BNB Site Supervisor Name Title Signature	Company Contact # Company	procedures specific
have been designated to this posto this tower crane. Name Title Signature BNB Site Supervisor Name Title Signature Signature BNB Alternate Site Supervisors	Company Contact # Company Company Contact #	procedures specific
have been designated to this post to this tower crane. Name Title Signature BNB Site Supervisor Name Title Signature BNB Alternate Site Supervisors Name	Company Contact # Company Contact # Company Contact #	procedures specific
I have been designated to this p to this tower crane, Name	Company Contact # Company Company Contact #	procedures specific
I have been designated to this posto this tower crane. Name Title Signature BNB Site Supervisor Name Title Signature BNB Alternate Site Supervisors Name Title Signature Signature	Company Contact # Company Contact # Company Contact #	procedures specific
I have been designated to this posto this tower crane. Name Title Signature BNB Site Supervisor Name Title Signature BNB Alternate Site Supervisors Name Title	Company Contact # Company Contact # Company Contact #	procedures specifi

Duties of Assigned Personnel - Multiple Crane Daily Operation Tower Crane & Mobile Crane

Project Name	Start	Date
Tower Crane Model		dated
Tower Crane Serial #		1 1
Tautas Canan I if Disaster		
Tower Crane Lift Director	on and have road and understone	The appentional propertures on a
I have been designated to this position this tower crane.	on and have read and understood	the operational procedures spe
Name	Company	1111
Title	Contact #	
Signature		0
Backup LD's		-2
Name	Company	1
Title	Contact #	
Signature	130-330-3	•
Name	Company	110
Title	Contact #	
Signature		
7.3		
Title Signature	Company Contact #	
Mobile Crane Operator I have been designated to this position to this mobile crane.	on and have read and understood	the operating procedures speci
Name	Company	
Title	Contact #	
Signature		=1-
BNB Site Supervisor		
Name	Company	BNBuilders
Title	Contact #	858-775-3291
Signature	1-22-	7.2
BNB Alternate Site Supervisors		
Name	Company	- []
Title	Contact #	
The state of the s		
Signature	Company	i i
Signature Name	Company Contact #	
Signature Name Title		
Signature Name Title Signature		
Signature Name Title Signature BNB Site Safety Name		

Signature

BNBuilders

	Tower Crane Pre-Dismantle Checklist	antle Checklist
Project Name	Date	Mobile Crane
		Operator
Erection Date	BNB	Mobile Crane
	Superintendent	Model
Tower Crane	BNB Safety	Mobile Crane
Model		Serial #
Tower Crane	Lift Director	Tower Crane
Serial #		Operator
Jib Length	A/D Director	Tower Crane
		Technician

a ()	Ū	1.	\ \	O.	ΣП	П	0 Z	4 <	V	<	U	T I	~		2	SS	OT	V	0.0	* 9 O	9 2	0 = >	Check	
Determine If other crane operations, on-site or adjacent, will affect the crane dismantle. If so, a multi-crane communication plan is required, (<i>Note:</i> If applicable, the affected crane	Determine need for overnight site security, e.g., two-day erection process.	Tower Crane per WAC 296-155-53900(62).	Verify the BNB Tower Crane sign is designed and engineered to fit the specific model of	Provide a temporary electrical distribution box at the base of the Tower Crane.	A/D Director and Lift Director for the Erection process.	never that completed Tower Crops Binder is legated on the labelte and condity available to	Notify the local Fire Department of the need for a High Rescue Team in case of an emergency.	Verify a 10th ABC Fire Extinguisher is available at the Tower Crane cab, base, and outside of the base enclosure.	Verify the Tower Crane footing concrete break-strength prior to erection	Verify location of Tower Crane footing is located per the construction plan.	Provide Live Utility Map to all subcontractors.	If applicable, Post "Danger - Overhead Powerlines" signs and implement protective measures per WAC 296-155-53408.	Minimum Clearance Distance per WAC 296-155-53408 - Table 4.	Identify gyerhead power lines, confirm Nominal Voltage with Utility provider, and establish	Notify surrounding neighbors, and businesses of crane erection operations	Schedule a pre-erection meeting with all involved parties, including but not limited to Crane Supplier, Crane Erectors, and Mobile Crane Crewmembers.	Provide Site Specific Safety Orientation for Grane Supplier, Grane Erectors, and Mobile Grane Grewmembers.	Verify underground utilities and structures based on mobile crane outrigger layout.	Schedule Pre-Erection Safety Inspection to be conducted by a 3rd-party accredited crane certifier per WAC 296-155-53206.	Complete the Duties of Assigned Personnel form. All parties must sign the form at the start of each day before commencing work (Note: Two-day erection operations require a separate form to be signed each day).	Notify L&I Crane Management System v/a email (Towercranenotify@Lni.wa.gov). Notification must be sent at least two weeks before erecting.	Apply for FAA Obstruction Evaluation / Airport Airspace Analysis (OE/AAA) (<i>Note:</i> submit the evaluation request at least 45 days prior to any Tower Crane Erection or "Jump" in elevation) https://oeaga.jaa.gov/oeaga/external/gisTops/gisAction.jap		
																							Notes	N. C.

Set base template	
to the BNB project team for the project's duration.	
Ensure daily Tower Crane inspection records are kept in the Tower Crane cab and provided	
Provide Tower Crane Operator with BNB project team contact information.	
Obtain Tower Crane Operator contact information, including emergency contact information.	
Obstruction Marking and Lighting	
Ensure the Tower Crane is marked/illuminated in accordance with FAA AC 70/7460-1M -	
Identify and assign a full-time Lift Director to the project for daily Tower Crane activities.	
per WAC 296-155-53905	
Schedule annual inspection of all turntable and tower bolts for proper condition and torque	
report to duty in their assigned crane)	
operators must attend the dismantle coordination meeting the morning of the dismantle, then	
	-

Chack
Submit Issued for Construction (IFC) Drawings.
Identify Qualified Person providing technical assistance to the Tower Crane A/D Director.
Schedule third-party electrical panel inspection prior to final L&I Crane Inspection.
Technician to set proximity alarms on the Tower Crane for power lines, multiple cranes, etc.
Submit trucking sequence (number of trucks, the arrival time of first truck, spacing timeframes, and staging area).
Schedule ETI Conformity - Company will add sticker to the cab of the crane.
Confirm correct phasing/rotation of motors after grane is energized
Tower Crane Erection & Mobile Crane Provider
Schedule mobile crane(s) for erection
Submit Pick Plan(s) two-weeks before erection
Submit Rigging Diagrams for Crane Pick Plan(s) specific to the Tower Crane model.
Submit approved Traffic Control Plan
Schedule traffic control flaggers and uniformed Police Officers
Supply spotters for overhead power lines or other obstructions.
Paint out crane center pin and outrigger locations
Supply road plates and crane pads as specified in Crane Pick Plan
Assign A/D Director for Tower Crane Erection
Assign Lift Director for Tower Crane Erection

Complete Tower Crane pre-erection inspection and provide a report to BNBuilders. Notify BNBuilders and Tower Crane Provider of any deficiencies identified during the inspection: Provide BNBuilders with final inspection and crane certification for the Tower Crane.	Survey Tower Crane Base after set and provide As-Built drawings Survey Tower Crane Base after foundation is placed and provide As-Built drawings BNB - In house survey: Layout crane foundation, Anchor Base Install and Tower Crane Base Inspection: Survey Tower Crane tower to verify within tolerances prior to setting slewing assembly/turntable Survey to communicate to Lift Director crane tower tolerance prior to setting slewing assembly/turntable	Provide electrician on site for erection Secure power distribution cord running to tower crane cab Confirm power and grounding requirements with the Tower Crane Provider, Complete electrical equipment inspections and ensure electrical inspection tags are visible,
---	---	--

BNBuilders

	Tower Crane Pre-Erection Checklist	tion Checklist
Project Name	Date	Mobile Crane Operator
Erection Date	BNB	Mobile Crane
	Superintendent	Model
Tower Crane	BNB Safety	Mobile Crane
Madel		Serial #
Tower Crane	Lift Director	Tower Crane
Serial #		Operator
Jib Length	A/D Director	Tower Crane
		Technician

Check Apply for FAA Obstruction Evaluation / Air
Apply for FAA Obstruction Evaluation / Airport Airspace Analysis (OE/AAA) (<i>Note</i> : subthe evaluation request at least 45 days prior to any Tower Crane Erection or "Jump" in elevation) https://crossas.foa.gov/osass/external/pisTools/gisAction.jsp Apply for Cal/OSHA mobile crane permit at the regrest Cal/Osha District Office. Cal/O
Title 8:344.71 (b) Cal/OSHA Crane Unit 2 MacArthur Place, Suite 700 Santa Ana, CA 92707 Phone:(714) 567-7142 Ernail:pyow@dir.ca.gov
(Note: Permit application may be completed by the lower grane provider.) Application Instructions: https://www.dr.completed.by.com/mile8/3-44_3-4-Minutes/
Schedule Pre-Erection Safety Inspection to be conducted by a 3rd-party accredited crane certifier per Cal/OSHA Title 8 344.71 (f) (Note: Tower crane must be inspected twice a year, the Initial permit inspection is considered one of two yearly inspections)
Notify the Cal/OSHA district office from which the permit was obtained in writing or by telephone followed by written notification. Notification must be sent at least 24 before erecting and must include date and time of activity per Cal/OSHA Title 8 344.71 (g)(2
Complete the Duties of Assigned Personnel form. All parties must sign the form at the start of each day before commencing work (Note: Two-day erection operations require a separate form to be signed each day).
Verify underground utilities and structures based on mobile crane outrigger layout.
Provide Site Specific Safety Orientation for Crane Supplier, Crane Erectors, and Crane Crewmembers.
Schedule a pre-erection meeting with all involved parties, including but not limited to Crane Supplier, Crane Erectors, and Mobile Crane Crewmembers.
Notify surrounding neighbors and businesses of crane erection operations
Identify overhead power lines, confirm Nominal Voltage with Utility provider, and Minimum Clearance Distance per Cal/OSHA Title 8 1612.1
If applicable, Post "Danger - Overhead Powerlines" signs and implement protective measures per Cal/OSHA Title 8 1612.1 (b).
Provide Live Utility Map to all subcontractors.

the base enclosure. Notify the local Fire Department of the need for a High Rescue Team in case of an emergency. Ensure that completed Tower Crane Binder is located on the jobsite and readily available to A/D brector and Lift Director for the Erection process. Provide a temporary electrical distribution box at the base of the Tower Crane. Verify the BNB Tower Crane sign is designed and engineered to fit the specific model of Tower Crane per Cal/OSHA Title 8 1619.1 (c) Determine need for overnight site security, e.g., two-day erection process. Determine if other crane operations, on-site or adjacent, will affect the orane dismantle. If so, a multi-crane communication plan is required. (Note: If applicable, the affected crane per cal/OSHA Title 8 1619.1 (f) (5) Screptific annual inspection of all unitable and lower botts for proper condition and forque per cal/OSHA Title 8 1619.1 (f) (5) Calvosha Title 8 1619.1 (f) (5) Obstruction Marking and Lighting Obstruction Marking and Lighting Obstruction Marking and Lighting Chiain Tower Crane Operator contact information, including emergency contact information. Provide Tower Crane Operator with BNB project feam contact information. Ensure daily Tower Crane contact inspection records are kept in the Tower Crane cab and provided to the BNB project team for the project's duration. Set base template

-

X Submit Issued for Construction (IFC) Drawings. X Identity Qualfiled Person providing technical assistance to the Tower Crane AID Director. X Provide Tower Crane Manual to be stored in the crane cab. X Schedule third-party electrical panel inspection prior to final Cal OSHA Inspection. X Schedule third-party electrical panel inspection prior to final Cal OSHA Inspection. X Submit trucking sequence (number of trucks, the arrival time of if irst truck, spacing fireframes, etc.) X Schedule mobile crane(s) for erection X Schedule mobile crane(s) for erection Submit Pick Plan(s) two-weeks before erection Submit approved Traffic Control Plan Submit politics and crane pads as specified in Crane Pick Plan(s) two-weeks before erections Supply spotters for overhead power. Innes or other obstructions Supply road plates and crane pads as specified in Crane Pick Plan Assign Lift Director for Tower Crane Erection Assign Lift Director for Tower Crane Erection		Tower Crane Provider	
	Check	Task	Notes
	×	Submit Issued for Construction (IFC) Drawings.	
	×	Tower Crane A/	
	X	Provide Tower Crane Manual to be stored in the crane cab.	
	×	Schedule third-party electrical panel inspection prior to final Cal OSHA Inspection.	
	×		
	×	Submit trucking sequence (number of trucks, the arrival time of first truck, spacing timeframes, and staging area).	
Schedule mobile crane(s) for erection Submit Pick Plan(s) two-weeks before erection Submit approved Traffic Control Plan Schedule traffic control flaggers and uniformed Police Officers. Supply spotters for overhead power lines or other obstructions. Paint out crane center pin and outrigger locations. Supply road plates and crane pads as specified in Crane Pick Plan Assign A/D Director for Tower Crane Erection Assign Lift Director for Tower Crane Erection	×	Schedule ETI Conformity - Company will add sticker to the cab of the crane.	
Mobile Crane er Crane model.	×		
Schedule mobile crane(s) for erection Submit Pick Plan(s) two-weeks before erection Submit Rigging Diagrams for Crane Pick Plan(s) specific to the Tower Crane model. Submit Rigging Diagrams for Crane Pick Plan(s) specific to the Tower Crane model. Submit approved Traffic Control Plan Schedule traffic control flaggers and uniformed Police Officers. Supply spotters for overhead power lines or other obstructions. Paint out crane center pin and outrigger locations. Paint out crane center pin and outrigger locations. Supply road plates and crane pads as specified in Crane Pick Plan Assign A/D Director for Tower Crane Erection. Assign Lift Director for Tower Crane Erection.		Erection & Mobile Crane	
Submit Pick Plan(s) two-weeks before erection Submit Rigging Diagrams for Crane Pick Plan(s) specific to the Tower Crane model. Submit approved Traffic Control Plan Schedule traffic control flaggers and uniformed Police Officers. Supply spotters for overhead power lines or other obstructions. Paint out crane center pin and outrigger locations. Supply road plates and crane pads as specified in Crane Pick Plan Assign A/D Director for Tower Crane Erection. Assign Lift Director for Tower Crane Erection.		Schedule mobile crane(s) for erection	
Submit Rigging Diagrams for Crane Pick Plan(s) specific to the Tower Crane model. Submit approved Traffic Control Plan Schedule traffic control flaggers and uniformed Police Officers. Supply spotters for overhead power lines or other obstructions. Paint out crane center pin and outrigger locations. Supply road plates and crane pads as specified in Crane Pick Plan Assign A/D Director for Tower Crane Erection. Assign Lift Director for Tower Crane Erection.		Submit Pick Plan(s) two-weeks before erection	
Submit approved Traffic Control Plan Schedule traffic control flaggers and uniformed Police Officers. Supply spotters for overhead power lines or other obstructions. Paint out crane center pin and outrigger locations. Supply road plates and crane pads as specified in Crane Pick Plan Assign A/D Director for Tower Crane Erection Assign Lift Director for Tower Crane Erection		Submit Rigging Diagrams for Crane Pick Plan(s) specific to the Tower Crane model.	
Schedule traffic control flaggers and uniformed Police Officers. Supply spotters for overhead power lines or other obstructions. Paint out crane center pin and outrigger locations. Supply road plates and crane pads as specified in Crane Pick Plan Assign A/D Director for Tower Crane Erection Assign Lift Director for Tower Crane Erection		Submit approved Traffic Control Plan	
Supply spotters for overhead power_lines or other obstructions Paint out crane center pin and outrigger locations Supply road plates and crane pads as specified in Crane Pick Plan Assign A/D Director for Tower Crane Erection Assign Lift Director for Tower Crane Erection	1	Schedule traffic control flaggers and uniformed Police Officers	
Paint out crane center pin and outrigger locations Supply road plates and crane pads as specified in Crane Pick Plan Assign A/D Director for Tower Crane Erection Assign Lift Director for Tower Crane Erection		Supply spotters for overhead power lines or other obstructions	
Supply road plates and crane pads as specified in Crane Pick Plan Assign A/D Director for Tower Crane Erection Assign Lift Director for Tower Crane Erection		Paint out crane center pin and outrigger locations	
Assign A/D Director for Tower Crane Erection Assign Lift Director for Tower Crane Erection		Supply road plates and crane pads as specified in Crane Pick Plan	
Assign Lift Director for Tower Crane Erection		Assign A/D Director for Tower Crane Erection	
		Assign Lift Director for Tower Crane Erection	

online nower and grounding requirements with the Lower Crane Provider.		3 rd Party Crane Inspector	Complete Tower Crane pre-erection inspection and provide a report to BNBuilders.	
THE RESERVED TO A PERSON NAMED AND PARTY OF THE PERSON NAMED BY A		Survey Tower Crane Base after set and provide As-Built drawings Survey Tower Crane Base after foundation is placed and provide As-Built drawings BNB - In house survey: Layout crane foundation, Anchor Base Install and Tower Crane Base Inspection Survey Tower Crane tower to verify within tolerances prior to setting slewing assembly/turntable Survey to communicate to Lift Director crane tower tolerance prior to setting slewing assembly/turntable	Survey Tower Crane Base after set and provide As-Built drawings. Survey Tower Crane Base after foundation is placed and provide As-Built drawings. BNB - In house survey: Layout crane foundation, Anchor Base Install and Tower Crane Base Inspection. Survey Tower Crane tower to verify within tolerances prior to setting slewing assembly/turntable. Survey to communicate to Lift Director crane tower tolerance prior to setting slewing assembly/turntable. 3 rd Party Crane Inspector	lags
tags		Survey Tower Crane Base after set and provide As-Built drawings Survey Tower Crane Base after foundation is placed and provide As-Built drawings BNB - In house survey: Layout grane foundation, Anchor Base Install and Tower Crane Base Inspection Survey Tower Crane tower to verify within tolerances prior to setting slewing assembly/turntable Survey to communicate to Lift Director grane tower tolerance prior to setting slewing assembly/turntable	Survey Tower Crane Base after set and provide As-Built drawings. Survey Tower Crane Base after foundation is placed and provide As-Built drawings. BNB - In house survey: Layout crane foundation, Anchor Base Install and Tower Crane Base Inspection. Survey Tower Crane tower to verify within tolerances prior to setting slewing assembly/turntable. Survey to communicate to Lift Director crane tower tolerance prior to setting slewing assembly/turntable. Survey to communicate to Lift Director crane tower tolerance prior to setting slewing assembly/turntable. 8td Party Crane Inspector	Survey
lags	Survey	Survey Tower Crane Base after foundation is placed and provide As-Bullt drawings BNB - In house survey: Layout crane foundation, Anchor Base Install and Tower Crane Base Inspection Survey Tower Crane tower to verify within tolerances prior to setting slewing assembly/turntable Survey to communicate to Lift Director crane tower tolerance prior to setting slewing assembly/turntable	Survey Tower Crane Base after foundation is placed and provide As-Built drawings BNB - In house survey: Layout crane foundation, Anchor Base Install and Tower Crane Base Inspection Survey Tower Crane tower to verily within tolerances prior to setting slewing assembly/turntable Survey to communicate to Lift Director crane tower tolerance prior to setting slewing assembly/turntable 3 rd Party Crane Inspector	Survey Tower Crane Base after set and provide As-Built drawings
nspection lags	Survey Tower Crane Base after set and provide As-Built drawings	BNB - In house survey: Layout crane foundation, Anchor Base Install and Tower Crane Base Inspection Survey Tower Crane tower to verify within tolerances prior to setting slewing assembly/turntable Survey to communicate to Lift Director crane tower tolerance prior to setting slewing assembly/turntable	BNB - In house survey: Layout crane foundation, Anchor Base Install and Tower Crane Base Inspection Survey Tower Crane tower to verify within tolerances prior to setting slewing assembly/turntable Survey to communicate to Lift Director crane tower tolerance prior to setting slewing assembly/turntable 3 rd Party Crane Inspector	Survey Tower Crane Base after foundation is placed and provide As-Bullt drawings
nspection lags	Survey Tower Crane Base after set and provide As-Built drawings. Survey Tower Crane Base after foundation is placed and provide As-Built drawings	Survey Tower Crane tower to verify within tolerances prior to setting slewing assembly/turntable. Survey to communicate to Lift Director crane tower tolerance prior to setting slewing assembly/turntable.	Survey Tower Crane tower to verity within tolerances prior to setting slewing assembly/turntable Survey to communicate to Lift Director crane tower tolerance prior to setting slewing assembly/turntable 8'a Party Crane Inspector	-
nspection lags Vey As-Bullt drawing lall and Tower (vey As-Bullt drawing	Survey to communicate to Lift Director crane tower tolerance prior to setting slewing assembly/turntable	Survey to communicate to Lift Director crane tower tolerance prior to setting slewing assembly/turntable 8 rd Party Crane Inspector	
			3 rd Party Crane Inspector	Survey to communicate to Lift Director crane tower tolerance prior to setting slewing assembly/turntable
Survey Survey Tower Crane Base after set and provide As-Built drawings In house survey: Layout crane foundation, Anchor Base Install, and Tower Crane Base Inspection In house survey: Layout crane foundation, Anchor Base Install, and Tower Crane Base Inspection In house survey: Layout crane foundation, Anchor Base Install, and Tower Crane Base Inspection In house survey: Layout crane foundation, Anchor Base Install, and Tower Crane Base Inspection In house survey: Layout crane tower tolerances prior to setting slewing assembly/turntable In house survey: Layout crane tower tolerance prior to setting slewing assembly/turntable In house survey: Layout crane tower tolerance prior to setting slewing assembly/turntable In house survey: Layout crane tower tolerance prior to setting slewing assembly/turntable In house survey: Layout crane tower tolerance prior to setting slewing assembly/turntable In house survey: Layout crane tower tolerance prior to setting slewing assembly/turntable In house survey: Layout crane tower tolerance prior to setting slewing assembly/turntable In house survey: Layout crane tower tolerance prior to setting slewing assembly/turntable In house survey: Layout crane tower tolerance prior to setting slewing assembly/turntable In house survey: Layout crane tower tolerance prior to setting slewing assembly/turntable In house survey: Layout crane tower tolerance prior to setting slewing assembly/turntable	Survey Tower Crane Base after set and provide As-Built drawings Survey Tower Crane Base after set and provide As-Built drawings Survey Tower Crane Base after foundation is placed and provide As-Built drawings BNB - In house survey: Layout crane foundation, Anchor Base Install and Tower Crane Base Inspection Survey Tower Crane tower to verify within tolerances prior to setting slewing assembly/turntable Survey to communicate to Lift Director crane tower tolerance prior to setting slewing assembly/turntable Survey Tower Crane pre-erection inspection and provide a report to BNBuilders.	Complete Tower Crane pre-erection inspection and provide a report to BNBullders.		
omplete electrical equipment inspections and ensure electrical inspection tags are visible. Survey Survey Tower Crane Base after set and provide As-Built drawings urvey Tower Crane Base after foundation is placed and provide As-Built drawings. NB - In house survey: Layout crane foundation, Anchor Base Install and Tower Crane Base Inspection urvey Tower Crane tower to verify within tolerances prior to setting slewing assembly/turntable urvey to communicate to Lift Director crane tower folerance prior to setting slewing assembly/turntable omplete Tower Crane pre-erection inspection and provide a report to BNBuilders. 8td Party Crane Inspector 8td Party Crane Inspector Ottify BNBuilders and Tower Crane Provider of any deficiencies identified during the inspection.	Survey Tower Crane Base after set and provide As-Built drawings. Survey Tower Crane Base after foundation is placed and provide As-Built drawings. BNB - In house survey: Layout crane foundation, Anchor Base Install and Tower Crane Base Inspection. Survey Tower Crane tower to verify within tolerances prior to setting slewing assembly/turntable. Survey to communicate to Lift Director crane tower tolerance prior to setting slewing assembly/turntable. Survey to communicate to Lift Director crane tower tolerance prior to setting slewing assembly/turntable. Survey to communicate to Lift Director crane tower tolerance prior to setting slewing assembly/turntable. Survey to communicate to Lift Director crane tower tolerance prior to setting slewing assembly/turntable. Survey to communicate to Lift Director crane tower tolerance prior to setting slewing assembly/turntable. Survey to communicate to Lift Director crane tower tolerance prior to setting slewing assembly/turntable.			
Survey Survey Survey Survey Survey Survey Tower Crane Base after set and provide As-Built drawings List Crane Base after foundation is placed and provide As-Built drawings NB - In house survey: Layout crane foundation, Anchor Base Install and Tower Crane Base Inspection NB - In house survey: Layout crane foundation, Anchor Base Install and Tower Crane Base Inspection urvey Tower Crane tower to verify within tolerances prior to setting slewing assembly/turntable urvey to communicate to Lift Director crane tower tolerance prior to setting slewing assembly/turntable omplete Tower Crane pre-erection inspection and provide a report to BNBuilders. Otify BNBuilders and Tower Crane Provider of any deficiencies identified during the inspection. Otify BNBuilders with final inspection and crane certification for the Tower Crane.	Survey Tower Crane Base after set and provide As-Built drawings. Survey Tower Crane Base after foundation is placed and provide As-Built drawings. BNB - In house survey: Layout crane foundation, Anchor Base install and Tower Crane Base Inspection. Survey Tower Crane tower to verify within tolerances prior to setting slewing assembly/turntable. Survey to communicate to Lift Director crane tower folerance prior to setting slewing assembly/turntable. Survey to communicate to Lift Director crane tower folerance prior to setting slewing assembly/turntable. Survey to communicate to Lift Director crane tower folerance prior to setting slewing assembly/turntable. Survey to communicate to Lift Director crane tower folerance prior to setting slewing assembly/turntable. Survey Tower Crane pre-erection inspection and provide a report to BNBuilders. Notify BNBuilders and Tower Crane Provider of any deficiencies identified during the inspection. Provide BNBuilders with final inspection and crane certification for the Tower Crane.			
Survey Tower Crane Base after set and provide As-Built drawings. Area Tower Crane Base after foundation is placed and provide As-Built drawings. NB - In house survey: Layout crane foundation, Anchor Base Install and Tower Crane Base Inspection urvey Tower Crane tower to verify within tolerances prior to setting slewing assembly/turntable urvey to communicate to Lift Director crane tower tolerance prior to setting slewing assembly/turntable or provide Tower Crane pre-erection inspection and provide a report to BNBuilders. 3rd Party Crane Inspector Otify BNBuilders with final inspection and crane certification for the Tower Crane inspection. Oovide BNBuilders with final inspection and crane certification for the Tower Crane.	Survey Tower Crane Base after set and provide As-Built drawings. Survey Tower Crane Base after set and provide As-Built drawings. Survey Tower Crane Base after foundation is placed and provide As-Built drawings. BNB - In house survey: Layout crane foundation, Anchor Base Install and Tower Crane Base Inspection. Survey Tower Crane tower to verify within tolerances prior to setting slewing assembly/turntable. Survey to communicate to Lift Director crane tower tolerance prior to setting slewing assembly/turntable. Complete Tower Crane pre-erection inspection and provide a report to BNBuilders. Notify BNBuilders with final inspection and crane certification for the Tower Crane. Cal OAHA Permit & Safety Inspection. Cal OAHA Permit & Safety Inspection.			
Strivey In specifical equipment inspections and ensure electrical inspection tags are visible. Strivey Inver Grane Base after set and provide As-Built drawings In house survey: Layout grane foundation is placed and provide As-Built drawings NB In house survey: Layout grane foundation, Anchor Base Install and Tower Grane Base Inspection urvey Tower Grane tower to verify within tolerances prior to setting slewing assembly/turntable urvey to communicate to Lift Director grane tower tolerance prior to setting slewing assembly/turntable omplete Tower Grane pre-erection inspection and provide a report to BNBuilders, and Tower Grane Provider of any deficiencies identified during the inspection. of OAHA Permit & Safety Inspection al OAHA - Notify BNBuilders and Tower Grane Provider of any deficiencies identified during the inspection.				

VOLUNTARY USE OF RESPIRATORS

"Information for Employees Using Respirators When Not Required Under the OSHA Standard." A copy of this exhibit is to be provided to any employee who chooses to wear a filtering facepiece or tight-fitting negative pressure respirator on a voluntary basis:

"Respirators are an effective method of protection against designated hazards when properly selected and worn. Respirator use is encouraged, even when exposures are below the exposure limit, to provide an additional level of comfort and protection of workers. However, if a respirator is used improperly or not kept clean, the respirator itself can become a hazard to the worker. Sometimes, workers may wear respirators to avoid exposures to hazards, even if the amount of hazardous substance does not exceed the limits set by OSHA standards."

If BNBuilders provides respirators for your voluntary use, or if you provide your own respirator, you need to take certain precautions to be sure that the respirator itself does not present a hazard.

You should:

- Read and heed all instructions provided by the manufacturer on use, maintenance, cleaning and care, and warnings regarding the respirators limitations. Training is required for all respirator use.
- Choose the respirators certified for use to protect against the contaminant of concern. NIOSH, the National Institute for Occupational Safety and Health of the U.S. Department of Health and Human Services certifies respirators. A label of certification should appear on the respirator or packaging. It will tell you what the respirator is designed for and how much it will protect you.
- 3. Refer to the Chemical Safety Data Sheet (SDS) for additional information or ask your supervisor.
- 4. Do not wear your respirator into atmospheres containing contaminants for which your respirator is not designed to protect against. For example, a respirator designed to filter dust particles will not protect you against gases, vapors, or very small solid particles of fumes or smoke.
- 5. Keep track of your respirator so that you do not mistakenly use someone else's respirator.
- You should have a medical clearance and fit test prior to wearing your own respirator.
- Review L&I respirator guidelines at <u>www.lni.wa.gov</u> WAC Chapter 296-842.

Name	Date
Signature	Company/Project
BNBuilders/Supervisor/Trainer	

BNBuilders 4/18/2014